

ABB	ZCCO Corporate Research	9ADB009045
Issued by department ZCCO/Poland/SST	Last edit date 2015-08-17	Revision 1.0
Customer ABB PLABB	Language English	Classification Confidential
Project name Seismic analyses of HV Instrument Transformers, IEEE 693- high (0.5g)/moderate(0.25g) seismic level		
Project manager Simsery_PPHV_Przasnysz_15172/50005903	CR Program Grzegorz_Juszlewicz/PLCRC/SST	Case ID 15172
Additional Author(s) Marcin Tamowski/PPHV, Pawel Gryzstar/PPHV, Jaroslaw Duzdowski/PPHV, Dariusz Siperek/PPHV, Piotr Mikulski/PPHV, Przemyslaw Nastierowski/PPHV Piotr Saj/PLCRC, Marek Florowski/PLCRC	Status of document Released	Classification CHTET
Keywords simulation, FE method, seismic analysis, frequency modes, response spectrum	Final Approval Date 2015-08-17	
Technical_0106.pdf Ver 1.00		

Electronic document

Technical report

Simulation Support Team

Case submitted by	Marcin Tamowski
Business Unit	PPHV
Type of analysis (used tool)	ABAQUS (seismic analysis)
Description of analysis	Seismic analysis different variants of current, voltage and combined transformers (PA123a/PA145a, PV123, PVA123a/PVA 145a) according to guidelines described in IEEE 693 standard. Consideration of seismic and dead loads.

Executive summary

This report covers investigation related to seismic analysis of HV instrument transformers (PV123, PA123a /PA145a, PVA123a /PVA145a) subjected to various load scenarios. Simulation covered the following load conditions: dead load, terminal force load, seismic load (Moderate - 0.25g; High - 0.5g). Analysis showed that designs: PA123a/PVA145a and PVA123a /PVA145a can withstand moderate seismic level, while PV123 can withstand high seismic load scenario.

ABB	ZCCO Corporate Research	9ADB009045
Doc. title Seismic analyses of HV Instrument Transformers, IEEE 693- high (0.5g)/moderate(0.25g) seismic level	Revision 1.0	Page 2/38

TABLE OF CONTENTS

1	INTRODUCTION	4
2	SIMULATION SOFTWARE	4
3	SIMULATION SETUP	4
3.1	SIMULATION PROCEDURE	4
3.2	SIMULATION STEPS	4
3.2.1	Natural frequency extraction	4
3.2.2	Response spectrum analysis	5
3.3	LOADS AND BOUNDARY CONDITIONS	6
3.3.1	Loads	6
3.3.2	Boundary conditions	6
3.4	ACCEPTANCE CRITERIA	7
3.5	CURRENT TRANSFORMER - PA 123A/PA 145A	8
3.5.1	Model simplifications	8
3.6	MATERIAL AND MASS INFORMATION	10
3.7	FINITE ELEMENT (FE) MODEL	11
3.8	VOLTAGE TRANSFORMER - PV 123	11
3.8.1	Model simplifications	11
3.9	MATERIAL AND MASS INFORMATION	13
3.10	FINITE ELEMENT (FE) MODEL	13
3.11	COMBINED TRANSFORMER - PVA123A/PVA145A	14
3.11.1	Model simplifications	14
3.12	MATERIAL AND MASS INFORMATION	14
3.13	FINITE ELEMENT (FE) MODEL	17
4	SIMULATION RESULTS	18
4.1	PA123A /PA145A	18
4.1.1	Natural frequency extraction	18
4.1.2	Dynamic analysis	20
4.2	PV 123	23
4.2.1	Natural frequency extraction	23
4.2.2	Dynamic analysis	25
4.3	PVA123A /PVA145A	27
4.3.1	Natural frequency extraction	27
4.3.2	Dynamic analysis	29
5	CONCLUSIONS	34
6	BIBLIOGRAPHY	35
7	CHANGE HISTORY	35
8	APPENDICES	36

[Handwritten signature]
339

ABB Doc. title	ZCCO Corporate Research	Revision	9ADB009045
			Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level			
8.1	CURRENT TRANSFORMER PA123A/PA145A.....		36
8.2	VOLTAGE TRANSFORMER PV123.....	1.0	3/38
8.3	COMBINED TRANSFORMER PVA123A/PVA145A.....		37
			38

ABB Doc. title	ZCCO Corporate Research	Revision	9ADB009045
			Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level			
1	INTRODUCTION		4/38

8.1	CURRENT TRANSFORMER PA123A/PA145A.....		36
8.2	VOLTAGE TRANSFORMER PV123.....		37
8.3	COMBINED TRANSFORMER PVA123A/PVA145A.....		38

1 INTRODUCTION

The goal of the analysis was to evaluate seismic performance of PA123a/PA145a (see 8.1), PV123 (see 8.2), PVA145a/PVA123a (see 8.3) type transformers. Simulation was done using guidelines of IEEE 693 standard. For more information please see [1].

Computations concerned evaluation of stress field distribution and maximum bending moment between flange and insulator. Present report describes used simulation technique, analysis steps, loads and boundary conditions variations and summarizes obtained results.

2 SIMULATION SOFTWARE

All simulations were performed using Abaqus/CAE package. Abaqus includes FEM (finite element method) solver, pre- and post processor and enables performing many types of multiphysics simulations: mechanical, thermal, acoustic, piezoelectric, seismic, and others.

Parts and assemblies can be created in Abaqus, or they can be imported from CAD systems using native file formats. Abaqus functionality enables to define materials, interactions, loads, boundary conditions, mesh. User is also available to set up simulation parameters such as pre-processing memory. It is always possible to change all simulation settings and properties, because they're all parameterized.

Simulation results can be visualized in Abaqus postprocessor or in external software, which is able to import simulation results in Abaqus format. In postprocessor user can view all predefined field outputs, show or hide part instances, create cross-sections, make animations, automatically generate reports, diagnose model (warnings, errors). For more information about ABAQUS please see [2].

3 SIMULATION SETUP

Analysis has been made using Finite Element Method.

3.1 Simulation procedure

According to [1] analysis included three main simulation steps:

- Static load:
 - Terminal load.
 - Gravitational load.
- Natural frequency extraction.
- Dynamic analysis.

3.2 Simulation steps

Simulation consisted of three main simulation steps.

3.2.1 Natural frequency extraction

In the first simulation step natural frequency extraction was performed. The frequency extraction procedure performs eigenvalue extraction to calculate the natural frequencies and the corresponding mode shapes of a system.

The eigenvalue problem for the natural frequencies of an undamped finite element model can be described by equation (3-1):

	ZCCO Corporate Research	9ADB009045	Revision	Page
			1.0	6/38
Doc. title Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level				

3.3 Loads and boundary conditions

3.3.1 Loads

The following static load scenarios have been considered

1. Gravitational load, $g=9.81 \text{ m/s}^2$.
2. Terminal operating load. These load conditions were specified according to [3] (Table 7 – Static withstand test loads). For considered voltage-current range static withstand force (Load class II) should be equal to 3000 N. With respect to 'NOTE 1 The sum of the loads acting in routinely operating conditions should not exceed 50% of the specified withstand test load', maximum operating force is equal to 1500 N.

Seismic load have been predefined according design response spectrum described in the standard [1] – ground acceleration reference – Moderate/High Required Response Spectrum. Main input parameters were the following:

- XYZ base motion with vertical load (N) equal to 80% of horizontal direction.
- Damping ratio – 2%.

As the final outcome from the analysis static loads were, combined with the seismic load.

3.3.2 Boundary conditions

Simulation assumes that the apparatus will be mounted on ground. During analysis model has been fixed at the bottom face of used test frame. General view of static loads and boundary conditions is presented in Figure 2. Area highlighted by red has been constrained (Y-rotation released). Base of the bottom tank has been supported in Y direction (as it is placed on the ground). Described boundary conditions have been used for all analyzed models.




Figure 2. Boundary conditions – general view

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden. © 2015 ABB Ltd.

	ZCCO Corporate Research	9ADB009045	Revision	Page
			1.0	5/38
Doc. title Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level				

$$(-\omega^2 M^{MN} + K^{MN}) \phi^N = 0 \quad (3-1)$$

where: M^{MN} – mass matrix (kg); K^{MN} – stiffness matrix (Pa), which includes initial stiffness effects if the base state (gravitational load); ϕ – eigenvector (the mode of vibration); M, N – degrees of freedom (-). Based on specification [1] one can assume that most critical frequency modes are in range of 0-35 Hz.

3.2.2 Response spectrum analysis

The response spectrum method is a convenient way of describing shock motion in terms of the maximum response of a single degree of freedom (1-DOF) oscillator of arbitrary natural period and damping ratio. Each data point of the response spectrum curve represents the peak response from a time history analysis of the earthquake applied to 1-DOF oscillator system. The ordinate defines the natural period at which the oscillator is tuned. Repeating the procedure for a great many frequencies defines a continuous curve for an assumed level of damping.

A spectral response analysis estimates the maximum displacement of the structure during a 'design' shock load without recourse of direct integration. Finite element implementation of the response spectrum calculate the response of each mode independent, and then combine the scaled response one of a number of established combination rules, to give an estimate of peak response. Spectrum plot used in simulation is presented in Figure 1.




Figure 1. Design response spectrum (RS) – 0.5g

— Moderate required RS - 0.25g - - - High required RS - 0.5g

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden. © 2015 ABB Ltd.

[Handwritten signature]
344

342

ABB ABB	ZCCO Corporate Research	Revision	9ADB009045
		Page	7/38
Doc. title			
Seismic analyses of HV Instrument Transformers. IEEE 693- High (0.5g)/moderate(0.25g) seismic level			

3.4 Acceptance criteria

With respect to the standard [1] the following acceptance criteria were used

- Seismic load should be combined with dead load and possible normal operating loads.
- The maximum allowable bending moment shall not exceed 6.65 kNm (50% of ultimate load/stress)
- Aluminum components shall not exceed 73 MPa (minimum ultimate tensile strength divided by 2.2 safety factor).

ABB ABB	ZCCO Corporate Research	Revision	9ADB009045
		Page	8/38
Doc. title			
Seismic analyses of HV Instrument Transformers. IEEE 693- High (0.5g)/moderate(0.25g) seismic level			

3.5 Current transformer - PA 123a/PA 145a

This chapter gathers details related to FE model of current transformer PA 123a/PA 145a.

3.5.1 Model simplifications

For simulation requirements some areas of the model were simplified. Small geometrical features like casting rounding, chamfers were removed in order to improve mesh generation process. Details of the geometry and center of mass can be found in Figure 3. Red point indicates center of mass of the transformer.





Figure 3. Simplified representation of the PA 123a/PA 145a transformer

Concrete between flange and ceramic insulator has been introduced using connector element with predefined rotational stiffness.

Because of the simulation method (dynamics based on modal analysis) components were connected together using bonded connection or conformal mesh.

3.6 Material and mass information

Component naming is presented in Figure 4.

	ZCCO Corporate Research	9ADB009045	Page
			Revision
Doc. title	1.0	9/38	
Seismic analyses of HV Instrument Transformers. IEEEE 693- high (0.5g)/moderate(0.25g) seismic level			




Figure 4. Assembly – component naming

Material and mass information is listed in Table 1


Table 1. Mass and material data

Drawing number	Component name	Material name	Mass [Kg]	Young's modulus [MPa]	Yield strength [MPa]	Ultimate strength [MPa]
2GKA310015	Base J123	EN-AC 43200 (grade F)	16.5	69000	80	160
2GKA310404	Insulator	Porcelain	71	100000	140	
	Insulator - Flange	EN-AC 43200 (grade F)	3.5	69000	180	220
2GKA414718	Head	EN-AC 43200 (grade F)	22.5	69000	80	160
2GKK314089	Head cover	EN-AC 43200 (grade F)	20	69000	80	160
2GKK311093R	Coil		150			
	Control box	EN-AC 43200 (grade F)	5.5	69000	80	160
	Oil		120			

The ultimate bending moment for ceramic insulator is equal to $M_{ig}=13.3$ kNm.

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden. © 2015 ABB Ltd.

[Handwritten signature]
323

	ZCCO Corporate Research	9ADB009045	Page
			Revision
Doc. title	1.0	10/38	
Seismic analyses of HV Instrument Transformers. IEEEE 693- high (0.5g)/moderate(0.25g) seismic level			

3.7 Finite element (FE) model

General view of FE model is presented in Figure 5.




Figure 5. FE model – general view

Mesh statistics were the following:

- Total number of nodes: 533430
- Total number of elements: 242866
 - 210555 quadratic tetrahedral elements of type C3D10
 - 31050 quadratic hexahedral elements of type C3D20R
 - 1243 quadratic quadrilateral elements of type S8R
 - 18 quadratic triangular elements of type STR165

Description of the coordinate system.

- X – 1st horizontal axis.
- Z – 2nd horizontal axis.
- Y – vertical axis.

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden. © 2015 ABB Ltd.

ABB ABB	ZCCO Corporate Research	9ADB009045
Doc. title	Revision	Page
Seismic analyses of HV Instrument Transformers, IEEE 693- high (0.5g)/moderate(0.25g) seismic level	1.0	11/38

3.8 Voltage transformer - PV 123

This chapter gathers details related to FE model of voltage transformer PV 123.

3.8.1 Model simplifications

For simulation requirements some areas of the model were simplified. Small geometrical features like casting rounding, chamfers were removed in order to improve mesh generation process. Details of the geometry and center of mass can be found in Figure 6. Red point indicates center of mass of the transformer.




Figure 6. Simplified representation of the PV 123 transformer

Concrete between flange and ceramic insulator has been introduced using connector element with predefined rotational stiffness.

Because of the simulation method (dynamics based on modal analysis) components were connected together using bonded connection or conformal mesh.

3.9 Material and mass information

Component naming is presented in Figure 7.

ABB ABB	ZCCO Corporate Research	9ADB009045
Doc. title	Revision	Page
Seismic analyses of HV Instrument Transformers, IEEE 693- high (0.5g)/moderate(0.25g) seismic level	1.0	12/38





Figure 7. Assembly - component naming

Material and mass information is listed in Table 2.

Table 2. Mass and material data

Drawing number	Component name	Material name	Mass [kg]	Young's modulus [MPa]	Yield strength [MPa]	Ultimate strength [MPa]
2GK310150P	Bottom tank	EN-AC 43200 (grade F)	25	69000	80	160
2GK310147P	Core	Steel	22.5	206000	300	370
2GK314005	Tank cover	EN-AC 43200 (grade F)	15.5	69000	80	160
2GKA310404	Insulator	Porcelain	71	100000	140	
	insulator flange	EN-AC 43200 (grade TB)	3.5	69000	160	220
	Oil	-	30			
2GK311093R	Control box	EN-AC 43200 (grade F)	5.5	69000	80	160
	Oil		60			

The ultimate bending moment for ceramic insulator is equal to $M_B=13.3$ kNm.

	ZCCO	9ADB009045
	Corporate Research	Revision
Doc. title	1.0	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		13/38

3.10 Finite element (FE) model

General view of FE model is presented in Figure 8.




Figure 8. FE model – general view


Mesh statistics were the following:

- Total number of nodes: 608507
- Total number of elements: 236033
 - 4606 quadratic quadrilateral elements of type S8R
 - 58 quadratic triangular elements of type STR165
 - 58965 quadratic hexahedral elements of type C3D20R
 - 8577 linear hexahedral elements of type C3D8R
 - 163827 quadratic tetrahedral elements of type C3D10

Description of the coordinate system.

- X – 1st horizontal axis.
- Z – 2nd horizontal axis.
- Y – vertical axis.

[Handwritten signature]
345

	ZCCO	9ADB009045
	Corporate Research	Revision
Doc. title	1.0	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		14/38

3.11 Combined transformer – PVA123a /PVA145a

This chapter gathers details related to FE model of combined transformer PVA123a /PVA145a.

3.11.1 Model simplifications

For simulation requirements some areas of the model were simplified. Small geometrical features like casting rounding, chamfers were removed in order to improve mesh generation process. Details of the geometry and center of mass can be found in Figure 9. Red point indicates center of mass of the transformer.




Figure 9. Simplified representation of the PVA123a /PVA145a transformer

Concrete between flange and ceramic insulator has been introduced using connector element with predefined rotational stiffness.

Because of the simulation method (dynamics based on modal analysis) components were connected together using bonded connection or conformal mesh.

3.12 Material and mass information

Component naming is presented in Figure 10

346

ABB Doc. title	ZCCO Corporate Research	9ADB009045 Revision	Page 15/38
Seismic analyses of HV Instrument Transformers. IEEE 693-high (0.5g)/moderate(0.25g) seismic level			




Figure 10. Assembly – component naming
Material and mass information is listed in Table 3.

ABB Doc. title	ZCCO Corporate Research	9ADB009045 Revision	Page 16/38
Seismic analyses of HV Instrument Transformers. IEEE 693-high (0.5g)/moderate(0.25g) seismic level			

Table 3. Mass and material data

Drawing number	Component name	Material name	Mass [kg]	Young's modulus [MPa]	Yield strength [MPa]	Ultimate strength [MPa]
2GKK314076	Tank	EN-AC 43200 (grade F)	25	69000	80	160
2GKK314084	Core	Steel	33.8	206000	300	370
2GKK314075	Tank cover	EN-AC 43200 (grade F)	18	69000	80	160
2GKK314070	Insulator	Porcelain	131	100000	140	
	Insulator flange	EN-AC 43200 (grade F6)	5	69000	180	220
2GKK314080	Head	EN-AC 43200 (grade F)	23.5	69000	80	160
2GKK314089	Head cover PVA-PA123A /PA145A-145	EN-AC 43200 (grade F)	23	69000	80	160
2GKK310802	Below	Stainless steel	5	190000	200	500
2GKK310014P	Below enclosure	EN-AC 43200 (grade F)	7	69000	80	160
-	Voltage coil	-	30	-	-	-
-	Current coil	-	150	-	-	-
2GKK310802	Epoxy insulator	-	2.5	-	-	-
2GKK311083R	Control box	EN-AC 43200 (grade F)	5.5	69000	80	160
-	Oil	-	150	-	-	-

The ultimate bending moment for ceramic insulator is equal to $M_B=13.3$ kNm.

3.13 Finite element (FE) model

General view of FE model is presented in Figure 11.




Figure 11. FE model – general view

Mesh statistics were the following:

- Total number of nodes: 1009580
- Total number of elements: 463007
 - 58507 quadratic hexahedral elements of type C3D20R
 - 300489 quadratic tetrahedral elements of type C3D10
 - 2519 linear quadrilateral elements of type S4R
 - 97 linear triangular elements of type S3
 - 9900 linear hexahedral elements of type C3D8R
 - 528 quadratic wedge elements of type C3D15
 - 90967 quadratic tetrahedral elements of type C3D10M

Description of the coordinate system.

- X – 1st horizontal axis.
- Z – 2nd horizontal axis.
- Y – vertical axis.

[Handwritten signature]
347

[Handwritten signature]

4 SIMULATION RESULTS

This chapter gathers simulation results evaluated in the analysis. Obtained outcome includes static and the seismic load.

4.1 PA123a /PA145a

4.1.1 Natural frequency extraction

Effective modal mass plot is presented Figure 12. Bubble size indicated amount of mass which participates in motion at specific frequency range. Based on presented plot one can see that the most critical modes were located between 6.9 – 8.2 Hz.




Figure 12. Natural frequency extraction – effective modal mass
Effective modes and associated with the shapes are presented in Figure 13.

[Handwritten signature]

348




Figure 13. Natural frequency extraction - mode shapes

Summary of modal mass participation is listed in Table 4.

Table 4. Modal mass participation - summary

Mode no	Frequency [Hz]	X-direction	Y-direction	Z-direction
1	6.9	40%	0%	35%
2	8.2	34%	0%	40%
3	38.9	2%	0%	6%
4	39.7	6%	0%	2%
5	46.9	0%	0%	0%
6	98.7	0%	89%	0%
7	129.2	0%	0%	2%
8	150.3	4%	0%	0%
9	166.6	0%	0%	4%
10	167.4	2%	0%	0%

4.1.2 Dynamic analysis

Stress distribution for tank component is presented in Figure 14 and Figure 15. Stress scale has been limited to 73 MPa as the maximum allowable stress level.





Figure 14. Von-Mises stress [Pa] distribution - tank (view 01)



Figure 15. Von-Mises stress [Pa] distribution - tank (view 02)

Displacement field is presented in Figure 16.

 Doc. title	ZCCO Corporate Research	9ADB009045	Page
	Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g/moderate(0.25g) seismic level	Revision 1.0	22/38




Figure 17. Von-Mises stress [Pa] distribution (AF3) - tank (View 01)





Figure 18. Von-Mises stress [Pa] distribution (AF3) - tank (View 02)

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden.
© 2015 ABB Ltd.

 Doc. title	ZCCO Corporate Research	9ADB009045	Page
	Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g/moderate(0.25g) seismic level	Revision 1.0	21/38




Figure 16. Displacement [mm] field - distribution

The maximum bending moment evaluated at the interface between flange and insulator was equal to:

- $M_x = 7961 \text{ Nm}$.
- $M_z = 7992 \text{ Nm}$.

Insulator has not satisfied the maximum bending moment condition. One can observe that stresses evaluated at the base are slightly above allowable value. Therefore small yielding may occur. One must have in mind that analysis did not cover possible casting imperfections.

Design has been verified according to Moderate seismic level (0.25 g Zero Period Acceleration). Stress distribution for such load scenario is presented from Figure 17 to Figure 18. Obtained stress level was below allowable level.

The maximum bending moment evaluated at the interface between flange and insulator was equal to:

- $M_x = 4816 \text{ Nm}$.
- $M_z = 4821 \text{ Nm}$.

Insulator has satisfied allowable bending moment condition.

Handwritten signature
349

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden.
© 2015 ABB Ltd.

4.2 PV 123

4.2.1 Natural frequency extraction

Effective modal mass plot is presented Figure 19. Bubble size indicated amount of mass which participates in motion at specific frequency range. Based on presented plot one can see that the most critical modes were located between 24.7– 25.3 Hz.




Figure 19. Natural frequency extraction – effective modal mass Effective modes and associated with the shapes are presented in Figure 20.




Figure 20. Natural frequency extraction – mode shapes Summary of modal mass participation is listed in Table 5.

Table 5. Modal mass participation – summary

Mode no.	Frequency [Hz]	X-direction direction	Y-direction direction	Z-direction direction
1	24.7	24%	0%	0%
2	25.2	0%	0%	24%
3	25.4	0%	0%	0%
4	26.5	0%	0%	0%
5	135.5	37%	0%	0%
6	139.3	0%	0%	0%
7	161.3	0%	34%	36%
8	162.4	0%	0%	0%
9	175.8	0%	0%	0%
10	176.2	0%	0%	0%

ABB ABB	ZCCO Corporate Research	9ADB009045	Page
Doc. title		Revision	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		1.0	25/38

4.2.2 Dynamic analysis
Stress distribution for tank component is presented in Figure 21 and Figure 22. As described in chapter 3.8.1 location of center of mass is close to the ground level, therefore expected bending moment and so the stress was low. One can see that the maximum stress level reached ca. 24 MPa and it was located at vicinity of coupling constraint. Stress level satisfies required safety condition.




Figure 21. Von-Mises stress [Pa] distribution - tank (view 01)




Figure 22. Von-Mises stress [Pa] distribution - tank (view 02)

ABB ABB	ZCCO Corporate Research	9ADB009045	Page
Doc. title		Revision	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		1.0	26/38

Displacement field is presented in Figure 23.




Figure 23. Displacement [m] field - distribution

The maximum bending moment evaluated at the interface between flange and insulator was equal to:

- $M_x = 2224 \text{ Nm}$.
- $M_y = 2228 \text{ Nm}$.

Insulator has satisfied the maximum bending moment condition.

352

ABB	ZCCO Corporate Research	9ADB009045
Doc. title	Revision	Page
Seismic analyses of HV Instrument Transformers, IEEE 693- high (0.5g)/moderate(0.25g) seismic level	1.0	27/38

4.3 PVA123a /PVA145a

4.3.1 Natural frequency extraction

Effective modal mass plot is presented Figure 24. Bubble size indicated amount of mass which participates in motion at specific frequency range. Based on presented plot one can see that the most critical modes were located between 3.8– 4.1 Hz.




Figure 24. Natural frequency extraction – effective modal mass
Effective modes and associated with the shapes are presented in Figure 25.

ABB	ZCCO Corporate Research	9ADB009045
Doc. title	Revision	Page
Seismic analyses of HV Instrument Transformers, IEEE 693- high (0.5g)/moderate(0.25g) seismic level	1.0	28/38





Figure 25. Neutral frequency extraction – mode shapes
Summary of modal mass participation is listed in Table 6.

Table 6. Modal mass participation – summary


Mode no.	Frequency [Hz]	X-direction	Y-direction	Z-direction
1	3.8	35%	0%	32%
2	4.1	32%	0%	35%
3	22.4	7%	0%	0%
4	23.2	0%	2%	8%
5	26.5	0%	95%	0%
6	29.2	0%	0%	1%
7	29.3	1%	0%	0%
8	34.6	10%	0%	0%
9	35.5	0%	0%	8%
10	36.2	0%	0%	3%

	ZCCO Corporate Research	9ADB009045	Page
			29/38
Doc. title		Revision	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		1.0	29/38

4.3.2 Dynamic analysis
Stress distribution for tank component is presented in Figure 26 and Figure 27. One can see that the maximum stress was above 73 MPa allowable limit.



Figure 26. Von-Mises stress [Pa] distribution - tank (view 01)

	ZCCO Corporate Research	9ADB009045	Page
			30/38
Doc. title		Revision	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		1.0	30/38




Figure 27. Von-Mises stress [Pa] distribution - tank (view 02)
Displacement field is presented in Figure 28.

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]

354

ABB	ZCCO Corporate Research	9ADB009045	Page
Doc. title		Revision	1.0
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level			31/38




Figure 28. Displacement [m] field - distribution

The maximum bending moment evaluated at the interface between flange and insulator was equal to:

- $M_x = 10451 \text{ Nm}$.
- $M_z = 8515 \text{ Nm}$.

Insulator has not satisfied the maximum bending moment condition. Stress distribution for moderate seismic level is presented in Figure 29 and Figure 30.

ABB	ZCCO Corporate Research	9ADB009045	Page
Doc. title		Revision	1.0
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level			32/38



Figure 29. Von-Mises stress [Pa] distribution - tank (View 01)






Figure 30. Von-Mises stress [Pa] distribution - tank (View 02)

	ZCCO Corporate Research	9ADB009045	Page
			33/38
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		Revision	1.0

The maximum bending moment evaluated at the interface between flange and insulator was equal to:

- $M_1=6335$ Nm.
- $M_2=4080$ Nm.

The maximum bending moment satisfies allowable value.

	ZCCO Corporate Research	9ADB009045	Page
			34/38
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		Revision	1.0

5 CONCLUSIONS

The goal of the analysis was to investigate family of HV Instrument Transformers using guidelines described in IEEE 693 standard. Summary of satisfied criteria is presented in Table 7. Column 'IEEE 693' lists allowable seismic level for selected design. Columns (2, 3) list seismic level where obtained stresses/bending moment were below yield strength/ultimate bending moment.

Table 7. Summary of acceptance criteria


Design name	(1) IEEE 693	(2) Yield strength	(3) Ultimate bending load
PA123a /PA145a	MODERATE	HIGH	HIGH
PV 123	HIGH	HIGH	HIGH
PVA123a /PVA145a	MODERATE	HIGH	HIGH

With respect to IEEE 693 criteria main conclusions are the following:

- PA123a/PA145a withstands Moderate seismic qualification level.
- PV 123 withstands High seismic qualification level.
- PVA123a/PVA145a withstand Moderate seismic qualification level.


Disclaimer

The analysis documented herein has been prepared in accordance with reasonable standards of scientific endeavor and the best knowledge of the author(s).
 The simulation results may depend on a variety of factors, including quality of input data, applied model simplifications and chosen numerical methods.


 355



356

 ABB <small>Doc. file</small>	ZCCO Corporate Research	<small>Revision</small> 1.0	<small>Page</small> 35/38
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level			


6 BIBLIOGRAPHY

- [1] IEEE 693 – *IEEE Recommended Practice for Seismic Design and Substations*, The Institute of Electrical and Electronics Engineers, Inc, NY 10016-5997, USA
- [2] ABAQUS, *ABAQUS 6.13 Documentation*, DS Simulia, USA, www.simulia.com
- [3] IEC 61869-1 – *Instrument transformers – Part 1: General requirements*, International standard, Edition 1.0 2007-10

7 CHANGE HISTORY


Date	Revision	Author(s)	Change
2015-08-31	Rev. 1	Juskiewicz Grzegorz	original document

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden.
 © 2015 ABB Ltd.

 ABB <small>Doc. file</small>	ZCCO Corporate Research	<small>Revision</small> 1.0	<small>Page</small> 36/38
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level			

8 APPENDICES


8.1 Current transformer PA123a /PA145a



We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden.
 © 2015 ABB Ltd.

ABB ABB	ZCCO Corporate Research	9ADB009045
	Doc. title	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		37/38
		Revision
		1.0

8.2 Voltage transformer PV123




We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden.
© 2012 ABB Ltd.

Handwritten signature
357

ABB ABB	ZCCO Corporate Research	9ADB009045
	Doc. title	Page
Seismic analyses of HV Instrument Transformers. IEEE 693- high (0.5g)/moderate(0.25g) seismic level		38/38
		Revision
		1.0

8.3 Combined transformer PVA123a /PVA145a



Handwritten signature

We reserve all rights in this document and in the information contained therein. Reproduction, use or disclosure to third parties without express authority is strictly forbidden.
© 2012 ABB Ltd.

Handwritten signature



INSTYTUT ENERGETYKI
 INSTITUTE OF POWER ENGINEERING
 LABORATORIUM WIELKOPRĄDOWE
 HIGH CURRENT LABORATORY

01-530 Warszawa
 ul. Mocy 5
 tel. 22 34-51-386
 tel./fax 22 836-80-16
 e-mail: ewp@ien.com.pl
 www.ien.com.pl/ewp

Test Report No.
 EWP/10/E/2014-1e

INSTITUTE OF POWER ENGINEERING
 HIGH CURRENT LABORATORY



**TEST REPORT No.
 EWP/10/E/2014-1e**

TEST OBJECT: Combined instrument transformer type PVA 145a

MANUFACTURER: ABB Sp. z o.o.
 Power Products
 59 Leszno Str.
 06-300 Przasnysz, Poland

TESTS ORDERED BY: Institute of Power Engineering
 High Voltage Department
 Internal order No. EWN/145/E/13/14 dated 15.01.2014

TYPE OF TESTS: Temperature-rise test (construction)

TEST PROCEDURE: IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011,
 IEC 61869-4:2013, IEC 62271-1:2011, PN-EN 61869-1:2009E,
 PN-EN 61869-2:2013-06E, PN-EN 61869-3:2011E,
 PN-EN 62271-1:2009/A1:2011E.

TEST OBJECT DELIVERED: 13.01.2014
DATE OF TESTS: 15.01.2014-16.01.2014
TESTS RESULTS: Positive

THE TESTS WERE WITNESSED BY: Jacek Tymochowicz M.Sc. Eng. *Tymoch*
TEST ENGINEER: Lidia Gruza M.Sc. Eng. *Lidia*

HEAD OF LABORATORY: Warsaw, 21.01.2014r.

Contents	
1.	Description of the test object
2.	Technical data declared by the Manufacturer
3.	Technical documentation of the test object
4.	Scope of the tests
5.	Tests and their results
6.	Summary
7.	Opinions and interpretations
8.	Photographic documentation
9.	Records made during tests

Report contains 17 numbered pages with:	
1	Drawing
2	Photographs
2	Appendixes

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]

Tests result refers only to the test object.
 The Test Report consist tests from and beyond the scope of accreditation (details in sub-cl. 4)
 Publishing or reproducing of this report in other version then exact and complete without written permission of laboratory is forbidden



1.	Description of the test object
Test object	Combined instrument transformer
Type	PVA 145a
Serial number	2GKP013K1486145
Manufacturer	ABB Sp. z o.o. Power Products 59 Leszno Str. 06-300 Przasnysz, Poland
Year of production	2013
Insulator	Composite insulator
Number of windings	CT part - 5, CT part - 4
Oil type	Nytro Libra
Minimum creepage distance	4495 mm
Insulating oil weight	150 kg
Total weight	540 kg
Dimensions	According to drawing no. 2GKK614123
The laboratory made the identification of test objects on the base of the documentation given in par. 3 - see Appendix.	
The test object is shown in the photographs No. 1 and 2. The object was prepared for testing by the Manufacturer.	

2.	Technical data declared by the Manufacturer
Maximum operating voltage	145 kV
Rated frequency	50 Hz
Voltage factor and time	1,9U _n /8h
Rated continuous thermal current, I _{cth}	180-360 A
Rated short-time thermal current, I _{st} /1s	20-20 kA
Rated dynamic current, I _{dyn}	50-50 kA



VT part						
Type of secondary winding	1a-1n	2a-2n	3a-3n	4a-4n	da-dn	
Rated secondary voltage	110·√3 V	110·√3 V	110·√3 V	110·√3 V	110 V	
Rated output	100 VA	100 VA	100 VA	100 VA	200 VA	
Accuracy class	1,0	1,0	1/3P	3/3P	3,0	
Thermal limiting output	1000 VA	1000 VA	1000 VA	1000 VA	450 VA	
CT part						
Type of secondary winding	1S1-1S2	2S1-2S2	3S1-3S2	4S1-4S2		
Rated secondary current	5 A	1 A	5 A	1 A		
Rated output	30 VA	40 VA	60 VA	60 VA		
Accuracy class	0,2	5P	5P	5P		
FS/ALF	5	20	20	20		
Ext.	120 %	-	-	-		

3.	Technical documentation of the test object
1.	Drawing no. 2GKK614123 - Dimensional drawing. Combined instrument transformer PVA 123a - 145a, ABB Sp. z o.o. Power Products, approved 17.12.2013
2.	Routine tests report of combined instrument transformer, typ PVA 145a, serial number: 2GKP013K1486145, ABB Sp. z o.o., Przasnysz, 04.12.2013



4. Scope of the tests		
Test programme agreed with Orderer comprised of tests:		
No.	Kind of test	Location of the test
1.	Temperature-rise tests	EWP
		IEC 61869-1:2007 p. 6.4.1 p. 7.2.2, IEC 61869-2:2012 p. 6.4.1 p. 7.2.2.204, IEC 61869-3:2011 p. 6.4.1 p. 7.2.2, IEC 61869-4:2013 p. 6.4.1 p. 7.2.2, IEC 62271-1:2011, table 3.
EWP The test was performed in Institute of Power Engineering, by High - Current Laboratory.		

5. Tests and their results
<p>Combined transformer was installed at the test stand, as it was during normal operation. Electric diagram of terminal box of tested combined transformer is given in Fig. 1.</p> <p>The rated voltage with a required value was applied to the primary voltage winding. The secondary voltage windings and the residual voltage winding were loaded with the suitable power, according to the test programme given below, which was agreed with the Orderer. Primary current terminals P1 and P2/A was bridged at the range of 300 A.</p> <p>According to Manufacturer's request current in primary current winding was equal to $I_{ch} = 360$ A.</p> <p>The arrangement of the thermocouples is given in Figure No. 2.</p> <p>The temperature-rises of windings were measured by the resistance rise method.</p> <p>During the test, the measurements of loaded windings were made every 1 hour and registered the deflection of oil level indicator.</p> <p>The resistances of all windings were measured before the tests and after of each stage of tests.</p> <p>The abstract of the protocol of temperature-rise test is given in Table No. 1.</p> <p>The summary of test results is given in Table 2.</p> <p>The temperature-rise of windings were calculated from the formula:</p> $\Delta T = \frac{R - R_0 - R_0}{R_0 \alpha} = \frac{R_0 - R_0}{R_0 \cdot 0,004}$

W.P.
364



Stage No. 1 Test at the rated load
<p>Test was performed according to the IEC 61869-1 p. 6.4.1 p. 7.2.2; IEC 61869-2 p. 6.4.1 p. 7.2.2.204; IEC 61869-3 p. 6.4.1 p. 7.2.2; IEC 61869-4 p. 6.4.1 p. 7.2.2.</p> <p>The voltage value $1,2 U_n = 91,5$ kV was applied to the P2/A terminal.</p> <p>The secondary voltage windings were loaded as follows: 1a-1n $\Rightarrow 100$ VA, $\cos \varphi = 1$, at the voltage $100/\sqrt{3}$ V; 2a-2n $\Rightarrow 100$ VA, $\cos \varphi = 1$, at the voltage $100/\sqrt{3}$ V; 3a-3n $\Rightarrow 100$ VA, $\cos \varphi = 1$, at the voltage $100/\sqrt{3}$ V; 4a-4n $\Rightarrow 100$ VA, $\cos \varphi = 1$, at the voltage $100/\sqrt{3}$ V.</p> <p>The winding of residual voltage remained open.</p> <p>The secondary current windings of the CT were loaded as follows: 1S1-1S2 $\Rightarrow 30$ VA, $\cos \varphi = 1$; 2S1-2S2 $\Rightarrow 40$ VA, $\cos \varphi = 1$; 4S1-4S2 $\Rightarrow 60$ VA, $\cos \varphi = 1$.</p> <p>Supply (current control) was applied to the secondary current winding 3S1-3S2.</p> <p>Terminals P1 and P2/A were short-circuited at the range 300 A.</p> <p>The test was performed till reached steady state of the measured temperatures.</p>
Stage No. 2 Test of 8 h
<p>Test was done immediately after the Stage No. 1 according to the IEC 61869-1 p. 6.4.1 p. 7.2.2; IEC 61869-2 p. 6.4.1 p. 7.2.2.204; IEC 61869-3 p. 6.4.1 p. 7.2.2; IEC 61869-4 p. 6.4.1 p. 7.2.2.</p> <p>The voltage value $1,9 U_n = 144,8$ kV was applied to the P2/A terminal.</p> <p>The secondary voltage windings were loaded as follows: 1a-1n $\Rightarrow 100$ VA, $\cos \varphi = 1$, at the voltage $100/\sqrt{3}$ V; 2a-2n $\Rightarrow 100$ VA, $\cos \varphi = 1$, at the voltage $100/\sqrt{3}$ V; 3a-3n $\Rightarrow 100$ VA at the voltage $100/\sqrt{3}$ V; 4a-4n $\Rightarrow 100$ VA, $\cos \varphi = 1$, at the voltage $100/\sqrt{3}$ V.</p> <p>The residual winding da-dn was loaded by $\Rightarrow 450$ VA, $\cos \varphi = 1$, at the voltage 100 V.</p> <p>The secondary windings of the CT part were loaded by powers: 1S1-1S2 $\Rightarrow 30$ VA $\cos \varphi = 1$; 2S1-2S2 $\Rightarrow 40$ VA $\cos \varphi = 1$; 4S1-4S2 $\Rightarrow 60$ VA, $\cos \varphi = 1$.</p> <p>Supply (current control) was applied to the secondary current winding 3S1-3S2.</p> <p>Terminals P1 and P2/A were short-circuited at the range 300 A.</p> <p>The duration of the test was 8 h.</p>
Stage No. 2 Test with thermal limit power
<p>Test was done immediately after Stage No. 2 according to the IEC 61869-1 p. 6.4.1 p. 7.2.2; IEC 61869-2 p. 6.4.1 p. 7.2.2.204; IEC 61869-3 p. 6.4.1 p. 7.2.2; IEC 61869-4 p. 6.4.1 p. 7.2.2.</p> <p>The voltage value $U_n = 76,2$ kV was applied to the P2/A terminal.</p> <p>According to Manufacturers request secondary voltage windings (1a-1n, 2a-2n, 3a-3n and 4a-4n) were loaded by limit power 1000 VA at $\cos \varphi = 1$.</p> <p>The residual winding remained open.</p> <p>The secondary current winding of the CT part were loaded as follows: 1S1-1S2 $\Rightarrow 30$ VA, $\cos \varphi = 1$; 2S1-2S2 $\Rightarrow 40$ VA; 4S1-4S2 $\Rightarrow 60$ VA, $\cos \varphi = 1$.</p> <p>Supply (current control) was applied to secondary current winding 3S1-3S2.</p> <p>Terminals P1 and P2/A were short-circuited at the range 300 A.</p> <p>The test was performed till reaching the steady state of the measured temperatures.</p>

W.P.



Measuring instruments

The temperatures were measured by means of type K thermocouples (NiCr - NiAl) with accuracy $\pm 0,6^{\circ}\text{C}$.
The ambient temperature was measured using four mercurial thermometers immersed into tank filled with oil. These thermometers were placed in the distance of 1 meter from the tested transformer at the height of 1 meter above floor - the accuracy of measurement $\pm 0,03^{\circ}\text{C}$.
The resistance was measured by means of meter type 2291 manufactured by TEI TEX Instrument with accuracy $0,01 \text{ m}\Omega$




Fig. 1. Electrical diagram of terminal box of tested combined instrument transformer

1. The expanded uncertainty assigned corresponds to a coverage probability of 95 % and the coverage factor $k = 2$.
 2. The expanded uncertainty assigned corresponds to a coverage probability of 95 % and the coverage factor $k = 2$.
 3. The expanded uncertainty assigned corresponds to a coverage probability of 95 % and the coverage factor $k = 2$.




Fig. 2. Arrangement of thermocouples during temperature-rise test:
 1 - oil (over current coil), 2 - head (contraction of the flange connecting the head the the insulator), 3 - under the flange of tank lid, 4 - lower tank (placed inside over earthing terminal, 5 - terminal P1, 6 - terminal P1, 7 - terminal P2/A (300A), 8 - terminal P2/A (300A).

362

Handwritten signature

Table 1, cont.

Heating time [h]

Stage 1

Deflection of the oil level Indicator mm	2	4	6	8	10	13	14	16	18	21	23	24	27	29	30	30	31	32	33	35	35	36
ΔT _{max} K	-	1.70	2.18	2.91	3.15	4.00	4.73	5.58	5.70	5.94	6.30	7.03	7.64	8.00	8.24	8.49	8.73	9.48	10.31	10.55	10.67	10.79
ΔT _{max} K	-	1.56	2.29	3.80	3.20	4.21	4.14	5.62	6.49	6.88	7.46	7.67	7.83	7.96	8.05	8.26	8.27	8.39	9.29	10.42	11.85	12.02
ΔT _{max} K	-	1.43	3.09	3.20	4.21	7.86	5.64	6.07	6.61	6.88	7.17	7.47	7.67	7.85	7.97	8.08	8.23	8.39	9.27	10.39	11.42	12.05
ΔT _{max} K	-	0.99	2.60	3.20	3.64	8.19	5.10	5.62	5.98	6.38	6.84	7.04	7.17	7.40	7.47	7.57	7.68	7.73	8.70	9.88	10.83	11.41
R _{max} KΩ	20.62	20.76	20.80	20.86	20.88	21.01	21.08	21.21	21.28	21.41	21.20	21.25	21.28	21.28	21.30	21.32	21.34	21.40	21.49	21.50	21.51	21.51
R _{max} mΩ	34.900	34.487	34.683	34.821	35.011	35.011	35.011	35.122	35.168	35.208	35.242	35.278	35.289	35.310	35.334	35.344	35.352	35.360	35.478	35.618	35.745	35.827
R _{max} mΩ	51.266	51.559	51.900	52.114	52.859	52.419	52.596	52.616	52.672	52.736	52.795	52.832	52.872	52.898	52.916	52.929	52.957	52.987	53.167	53.396	53.697	53.731
R _{max} mΩ	48.790	48.933	49.298	50.642	50.845	51.325	51.317	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325	51.325
R _{max} mΩ	47.648	47.669	47.986	49.177	49.062	49.464	49.563	48.626	48.700	48.730	48.784	48.828	48.855	48.883	48.904	48.922	48.946	49.048	49.275	49.548	49.653	49.653

INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY

Test Report No. EWP/10/E/2014-1e

Handwritten signature

Table 1: Temperature-rise test results of combined instrument transformer PVA 145a, nr fabr. ZOKP013K1486145

Heating time [h]

Stage 1

No of thermocouple	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
U _{max} kV	0.0	6.10	6.07	6.05	6.07	6.07	6.07	6.08	6.08	6.09	6.04	6.04	6.04	6.05	6.06	6.05	6.05	6.05	6.06	6.05	6.05	6.05
T _{max} °C	0.0	6.080	6.056	6.053	6.072	6.051	6.032	6.042	6.053	6.062	6.024	6.036	6.037	6.037	6.054	6.050	6.070	6.060	6.060	6.060	6.060	6.060
I ₁₅₁₋₁₅₁ A	0.0	364.8	363.4	363.2	364.3	363.1	361.9	362.5	363.2	363.7	361.4	362.2	362.2	365.4	364.8	364.2	363.0	363.6	360.6	363.6	363.6	364.8
I ₁₅₁₋₁₅₁ mA	0.0	364.8	363.4	363.2	364.3	363.1	361.9	362.5	363.2	363.7	361.4	362.2	362.2	365.4	364.8	364.2	363.0	363.6	360.6	363.6	363.6	364.8
R _{max} mΩ	234.21	238.16	240.66	244.83	246.84	250.47	251.04	253.06	255.05	256.38	257.58	258.67	259.65	260.55	261.37	262.18	262.99	263.79	264.59	265.39	266.19	266.99
R _{max} mΩ	779.98	790.00	797.90	806.61	814.45	821.80	828.88	835.17	841.13	846.74	852.05	856.93	861.39	865.36	869.09	872.53	875.63	878.26	880.44	882.18	883.54	884.44
R _{max} mΩ	378.94	389.15	392.89	396.47	400.24	403.03	406.11	409.21	412.89	415.07	416.88	419.12	421.09	423.24	425.43	426.73	428.67	429.50	430.72	432.50	434.79	437.29
R _{max} mΩ	9.2106	9.3358	9.4414	9.5302	9.6128	9.6893	9.7608	9.8272	9.8894	9.9472	10.0010	10.0510	10.1036	10.1536	10.2029	10.2503	10.2956	10.3398	10.3820	10.4232	10.4624	10.4995
ΔT _{max} mΩ	0.8788	-	-	-	11.34	13.48	15.48	17.36	19.03	20.70	22.24	23.66	24.95	26.06	27.16	28.12	28.99	29.86	30.66	31.59	32.65	33.48
ΔT _{max} K	-	-	-	-	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09	0.09
ΔT _{max} K	-	-	-	-	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34	3.34
ΔT _{max} K	-	-	-	-	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05	14.05
ΔT _{max} K	-	-	-	-	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91	19.91
ΔT _{max} K	-	-	-	-	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87	15.87
ΔT _{max} K	-	-	-	-	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27	11.27
ΔT _{max} K	-	-	-	-	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26	6.26
ΔT _{max} K	-	-	-	-	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40	3.40

INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY

Test Report No. EWP/10/E/2014-1e

Handwritten signature

Table 1. Temperature-rise test results of combined instrument transformer PVA 145a, nr Faber, ZGKP013X1486145

Stage	Heating time [h]		R _{100%} mΩ		R _{10%} mΩ		R _{5%} mΩ		R _{2%} mΩ		Deflection of the oil level indicator [mm]	
	25	26	25	26	25	26	25	26	25	26	AT _{100%} K	AT _{10%} K
Stage 2	25	26	49,809	51,118	52,713	54,183	54,949	55,615	56,918	57,099	21,54	11,64
	24	25	49,851	51,118	52,713	54,183	54,949	55,615	56,918	57,099	21,58	11,64
Stage 3	29	28	49,726	51,623	53,286	54,912	56,308	57,337	58,412	59,402	21,54	11,77
	28	29	49,809	51,486	53,141	54,656	56,157	57,229	58,308	59,382	21,55	11,77
Stage 4	23	24	49,809	51,486	53,141	54,656	56,157	57,229	58,308	59,382	21,55	11,77
	22	23	49,809	51,486	53,141	54,656	56,157	57,229	58,308	59,382	21,55	11,77
Stage 5	30	29	49,809	51,486	53,141	54,656	56,157	57,229	58,308	59,382	21,55	11,77
	29	30	49,809	51,486	53,141	54,656	56,157	57,229	58,308	59,382	21,55	11,77

Table 1, cont.

**INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY**

Test Report No. EWP/10/E/2014-1e

Table 1, cont.

No. of thermocouple	Heating time [h]		T _{100%} °C		T _{10%} °C		T _{5%} °C		T _{2%} °C		U _{100%} kV	
	25	26	25	26	25	26	25	26	25	26	1448	1448
AT 1 K	13,10	13,30	14,03	14,05	14,03	14,05	14,03	14,05	14,03	14,05	6,03	6,03
	13,10	13,30	14,03	14,05	14,03	14,05	14,03	14,05	14,03	14,05	6,03	6,03
AT 2 K	10,50	10,85	11,25	11,25	11,25	11,25	11,25	11,25	11,25	11,25	6,06	6,06
	10,50	10,85	11,25	11,25	11,25	11,25	11,25	11,25	11,25	11,25	6,06	6,06
AT 3 K	5,80	6,13	6,35	6,35	6,35	6,35	6,35	6,35	6,35	6,35	6,06	6,06
	5,80	6,13	6,35	6,35	6,35	6,35	6,35	6,35	6,35	6,35	6,06	6,06
AT 4 K	1,92	2,32	2,35	2,35	2,35	2,35	2,35	2,35	2,35	2,35	6,06	6,06
	1,92	2,32	2,35	2,35	2,35	2,35	2,35	2,35	2,35	2,35	6,06	6,06
AT 5 K	10,88	11,35	11,63	11,75	11,75	11,75	11,75	11,75	11,75	11,75	6,06	6,06
	10,88	11,35	11,63	11,75	11,75	11,75	11,75	11,75	11,75	11,75	6,06	6,06
AT 6 K	13,08	13,53	13,65	13,75	13,75	13,75	13,75	13,75	13,75	13,75	6,06	6,06
	13,08	13,53	13,65	13,75	13,75	13,75	13,75	13,75	13,75	13,75	6,06	6,06
AT 7 K	9,85	10,43	10,45	10,60	10,60	10,60	10,60	10,60	10,60	10,60	6,06	6,06
	9,85	10,43	10,45	10,60	10,60	10,60	10,60	10,60	10,60	10,60	6,06	6,06
AT 8 K	10,73	11,20	11,23	11,30	11,30	11,30	11,30	11,30	11,30	11,30	6,06	6,06
	10,73	11,20	11,23	11,30	11,30	11,30	11,30	11,30	11,30	11,30	6,06	6,06
T _{100%} °C	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18
	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18	17,18
U _{100%} kV	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75
	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75	16,75

Table 1, cont.

**INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY**

Test Report No. EWP/10/E/2014-1e

403



Table 2. Temperature-rises $\Delta T [K]$ given during the tests combined instrument transformer PVA 145a serial number 2GKP013K1486145

Winding	ΔT after Stage 1	ΔT after Stage 2	ΔT after Stage 3	ΔT_{dep}
IS1-IS2	29,86	34,76	36,30	
2S1-2S2	31,59	36,73	38,44	
3S1-3S2	31,49	36,62	39,12	75 ^{1),2),3)}
4S1-4S2	32,09	37,36	39,20	
P1-P2/A	Not measured	Not measured	28,82	
1a-1n	7,92	12,72	22,38	
2a-2n	7,73	12,48	23,44	
3a-3n	8,39	13,08	24,55	
4a-4n	8,39	13,08	25,09	75 ^{2),3)}
da-dn	7,73	12,27	22,61	
P2/A-N	9,46	12,00	35,89	

No. of thermo-couple	Location	ΔT after Stage 1	ΔT after Stage 2	ΔT after Stage 3	ΔT_{dep}
1	Oil	11,35	14,05	15,08	55 ^{1),2),3),4)}
2	Head - top part next to terminal	10,30	11,38	12,10	
3	Under the tank lid from side of terminal box	4,50	6,65	7,03	40 ³⁾
4	Enclosure of lower tank	1,57	2,37	2,02	
5	Terminal P1	11,53	11,75	12,50	
6	Terminal P1	13,68	13,75	14,98	
7	Terminal P2/A	10,08	10,60	11,45	65 ³⁾
8	Terminal P2/A	11,28	11,30	12,33	

¹⁾ acc. to IEC 61869-1, ²⁾ acc. to IEC 61869-2, ³⁾ acc to IEC 61869-3, ⁴⁾ acc to IEC 61869-4, ⁵⁾ acc. to IEC 62271-1

$\Delta\theta_{dep}$ - temperature-rises; $\Delta\theta_{dep}$ - permitted value in steady state

Handwritten signature
3/65



6. Summary

In tested combined instrument transformer type PVA 145a, with composite insulator, as results of temperature rise test with current $I_{th} = 360$ A:

- in steady state, at the rated load of secondary current and voltage windings (without residual winding), at $\cos \phi = 1$ and supply voltage $1,2U_n$ (Stage No. 1), permitted temperature-rise limits were not exceeded.

The tested combined transformer met requirements of IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011, IEC 61869-4:2013 IEC 62271-1:2011 standards.

- results of test 8 h at supply voltage $1,9U_n$ and rated load of current and voltage windings at $\cos \phi = 1$ and load of residual winding with thermal limit power (Stage No. 2), shows that permitted temperature-rise limits were not exceeded.

The tested combined transformer met requirements of IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011, IEC 61869-4:2013 IEC 62271-1:2011 standards.

- results of test with thermal limit power (Stage No. 3) at rated load of current windings at $\cos \phi = 1$ and supply voltage U_n , and at the same time loading of all voltage windings (without residual windings) with thermal limit power, shows that permitted temperature-rise limits were not exceeded.

The tested combined transformer met requirements of IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011, IEC 61869-4:2013 IEC 62271-1:2011 standards.


7. Opinions and interpretations

None

Handwritten signature




8. Photographic documentation



Photograph No. 1. Combined transformer on the test stand during temperature-rise test.



Photograph No. 2. The conductors short-circuiting of P1-P2/A terminals.




366



INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY

Test Report No.
EWF/10/E/2014-1c

APPENDIX No.2

 ABB Sp. z o.o.	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND
<p>DECLARATION OF CONFORMITY No. 092/2013 (EN) (acc. to ISO/IEC 17060-1)</p>		
<p>Manufacturer: ABB Sp. z o.o. Dept. in Przasnysz</p>		
<p>Address: Str. Leśzna 59 06-300 Przasnysz / POLAND</p>		
<p>Product: Combined Instrument Transformer PVA 145a</p>		
<p>Above mentioned product conforms with the following standard :</p>		
<p>Standard IEC 61869 - 4</p>	<p>Title Combined Instrument Transformers</p>	<p>Edition/Date 2013</p>
<p>Additional information: Serial numbers: ZGKP013K1486145;</p>		
<p>Place and date of issue of declaration Przasnysz 13.01.2014</p>		
<p>ABB Sp. z o.o. ul. Zaczarowana 1, 04-713 Warszawa NIP: 525-000-44-54; PL5250004454 Region 010011160 O D D Z I A S W P A S N Y S Z U ul. Leśzna 59, 06-300 Przasnysz tel. (22) 225 8021, fax (22) 225 8050 (9)</p>	<p>ABB Sp. z o.o. ul. Zaczarowana 1, 04-713 Warszawa NIP: 525-000-44-54; PL5250004454 Region 010011160 O D D Z I A S W P A S N Y S Z U ul. Leśzna 59, 06-300 Przasnysz tel. (22) 225 8021, fax (22) 225 8050 (9)</p>	<p>ABB Sp. z o.o. ul. Zaczarowana 1, 04-713 Warszawa NIP: 525-000-44-54; PL5250004454 Region 010011160 O D D Z I A S W P A S N Y S Z U ul. Leśzna 59, 06-300 Przasnysz tel. (22) 225 8021, fax (22) 225 8050 (9)</p>
<p>Przedstawiciel Przasnysz Przasnysz</p>	<p>Przedstawiciel Przasnysz Przasnysz</p>	<p>Przedstawiciel Przasnysz Przasnysz</p>
<p>..... (Name) (Signature)</p>		

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
367



INSTYTUT ENERGETYKI
 INSTITUTE OF POWER ENGINEERING
LABORATORIUM WIELKOPRAĐOWE
 HIGH CURRENT LABORATORY

01-330 Warszawa
 ul. Młocze 8
 tel./fax 22 34-31-336
 tel./fax 22 836-80-16
 e-mail: ewp@ieh.com.pl
 www.ieh.com.pl/ewp



AB 323



TEST REPORT No.
EWP/47/E/2014-1e

TEST OBJECT: Current instrument transformer type PA 145a

MANUFACTURER: ABB Sp. z o.o.
 Branch Office in Przasnysz
 59 Leszno Str.
 06-300 Przasnysz, Poland

TESTS ORDERED BY: ABB Sp. z o.o.
 Branch Office in Przasnysz
 59 Leszno Str.
 06-300 Przasnysz, Poland
 Order No. 4500574872 dated on 22.07.2014

TYPE OF TESTS: Temperature-rise test
TESTS PROCEDURE:: IEC 61869-1:2007, IEC 61869-2:2012, IEC 62271-1:2011, PN-EN 61869-1:2009E, PN-EN 61869-2:2013-06E, PN-EN 62271-1:2009/A1:2011E

OBJECT DELIVERED: 23.07.2014
DATE OF TESTS: 30.07-31.07.2014
TESTS RESULTS: Positive for current $I_{th} = 1800$ A (at range 1500 A)

THE TESTS WERE WITNESSED BY: -
TEST ENGINEER: Mariusz Sul M. Sc. Eng. *Mariusz Sul*
HEAD OF LABORATORY: Lidia Gruza M. Sc. Eng. *Lidia Gruza*
TRANSLATED BY: Jacek Tynochowicz M. Sc. Eng. *Jacek Tynochowicz*

Warsaw, 5.08.2014

Handwritten signature

369

Tests result refers only to the test object.
 The Test Report consist test from and beyond the scope of accreditation (details in sub-cl. 4)
 Publishing or reproducing of this report in other version than exact and complete without written permission of laboratory is forbidden

Handwritten signature

	INSTITUTE OF POWER ENGINEERING HIGH CURRENT LABORATORY	Test Report No. EWP/47/E/2014-1e
--	---	---

Contents	
1.	Description of the test object
2.	Technical data declared by the Manufacturer
3.	Technical documentation of the test object
4.	Scope of the tests
5.	Tests and their results
6.	Summary
7.	Opinions and interpretations
8.	Photographic documentation

Report contains 12 numbered pages with:	
1	drawing
1	photograph
2	appendixes

Handwritten signature

1. Description of the test object	
Test object	Current instrument transformer
Type	PA 145a
Serial number	2GKP014A1287155
Manufacturer	ABB Sp. z o.o. Branch Office in Przasnysz 59 Leszno Str. 06-300 Przasnysz, Poland
Year of production	2014
Insulator	Composite insulator
Number of windings	5
Oil type	Nytro Libra
Minimum creepage distance	3075 mm
Insulating oil weight	120 kg
Total weight	360 kg
Dimensions	According to drawing no. 2GKA614301
The laboratory made the identification of test objects on the base of the documentation given in sub-cl. 3 – see Appendix no. 1.	
The test object is shown in the photographs No. 1. The object was prepared for tests by the Manufacturer.	

2. Technical data declared by the Manufacturer	
Maximum operating voltage	145 kV
Rated frequency	50 Hz
Rated continuous thermal current, I_{th}	1800 A
Rated short-time thermal current, $I_{sh}/1s$	63 kA
Rated dynamic current, I_{dyn}	158 kA

Winding	Rated current winding	Rated output	Accuracy class	FS/ALF	Ext.%
1S1-1S2	5 A	200 VA	0,2	10	120
2S1-2S2	1 A	100 VA	0,1	5	120
3S1-3S2	5 A	20 VA	5P	60	
4S1-4S2	1 A	35 VA	10P	40	
5S1-5S2	1 A	40 VA	10P	20	

3. Technical documentation of the test object	
1.	Drawing no. 2GKA614301 – Dimensional drawing, „Current transformer PA 145a”, ABB Sp. z o.o. Power Products, approved 01.08.2014
2.	Drawing no. 2GKK314141 – „Tor prądowy, przet 40 Cu, rura 60x4 Al. 3600A”, ABB Sp. z o.o. Power Products, approved 24.06.2014
3.	Routine tests report of current instrument transformer, type PA 145, serial number: 2GKP014A1287155, ABB Sp. z o.o., Przasnysz, 16.07.2014

4. Scope of the tests	
Test programme agreed with Orderer comprised of tests:	

No.	Kind of test	Tests according the Standard	Location of the test
1.	Temperature-rise tests	IEC 61869-1:2007 sub-cl. 6.4 and sub-cl. 7.2.2, IEC 61869-2:2012 sub-cl.6.4.1 and sub-cl. 7.2.2.204 IEC 62271-1:2011, table 3	A EWP

EWP	The test was performed in the High Current Laboratory of the Institute of Power Engineering.		
A	The test method accredited by Polish Centre for Accreditation. Accreditation Certificate No. AB 323.		

370

5. Tests and their results

Test was performed according to IEC 61869-1 sub-cl. 6.4 and sub-cl. 7.2.2; IEC 61869-2 sub-cl. 6.4.1 and sub-cl. 7.2.2.204. Current transformer was installed at the test stand, as it was during normal operation. Supply was applied to the primary current terminals P1- P2/A.

The secondary windings were loaded with the suitable power: 1S1-1S2 \Rightarrow 200 VA, $\cos \varphi = 1$;
2S1-2S2 \Rightarrow 100 VA, $\cos \varphi = 1$; 3S1-3S2 \Rightarrow 20 VA, $\cos \varphi = 1$; 4S1-4S2 \Rightarrow 35 VA, $\cos \varphi = 1$;
5S1-5S2 \Rightarrow 40 VA, $\cos \varphi = 1$.

Primary current terminals P1 i P2/A was bridged at the range of 1500 A. According to Manufacturer's request current in primary current winding was equal to $I_{th} = 1800$ A. The test was performed till reaching the steady state of the measured temperatures.

The temperature-rise of windings were calculated from the following formula:

$$\Delta T = \frac{R}{R_0} \alpha \frac{R_1 - R_0}{R_0} \cdot 0,004$$

During the test, the measurements of loaded windings were made every 1 hour and registered the deflection of oil level indicator. The arrangement of the thermocouples is given in Figure No. 1.

The abstract of the protocol of temperature-rise test is given in Table No. 1.

The summary of test results is given in Table No. 2.

Measuring instruments

The temperatures were measured by means of type K thermocouples (NFCr - NiAl) with accuracy $\pm 0,3^\circ\text{C}$.

The ambient temperature was measured using four mercurial thermometers immersed into tank filled with oil. These thermometers were placed in the distance of 1 meter from the tested transformer at the height of 1 meter above floor- the accuracy of measurement $\pm 0,3^\circ\text{C}$.

The resistance was measured by means of meter type 2291 manufactured by TETTEX Instrument with accuracy $\pm 0,001 \text{ m}\Omega$.




Fig. 1. Arrangement of thermocouples during temperature-rise test:
1 - oil (over current coil), 2 - head (contraction of the flange connecting the head with the insulator), 3 - terminal P1, 4 - terminal P1, 5 - terminal P1, 6 - terminal P2/A, 7 - thermocouple inside instrument transformer current path 3000 A.

[Handwritten signature]

¹ The expanded uncertainty assigned corresponds to a coverage probability of 95 % and the coverage factor $k = 2$.

[Handwritten signature]

[Handwritten signature]

Table 1. Results of the temperature-rise test of current instrument transformer PA 145a, serial number 2GKR0141287155

Table 1. Cont.

INSTITUTE OF POWER ENGINEERING HIGH CURRENT LABORATORY Test Report No. RWP/A7/E/2014-1e

Table 1. Results of the temperature-rise test of current instrument transformer PA 145a, serial number 2GKR0141287155

INSTITUTE OF POWER ENGINEERING HIGH CURRENT LABORATORY Test Report No. RWP/A7/E/2014-1e

Table 2. Temperature-rises given during the tests current instrument transformer PA 145a serial number 2GKP014A1287155

Winding	ΔT [K]	ΔT_{top} [K]
1S1-1S2	62,0	65 ^{1),2)}
2S1-2S2	63,6	
3S1-3S2	63,3	
4S1-4S2	62,2	
5S1-5S2	62,7	
Thermocouple		
No.	Location	ΔT_{top} [K]
1	Oil	37,1
2	Head (contraction of the flange connecting the head with the insulator)	28,5
3	Terminal P1	42,4
4	Terminal P1	50,8
5	Terminal P2/A 3000 A	39,5
6	Terminal P2/A 3000 A	43,6
7	Current path 3000 A	48,8

¹⁾ acc. to IEC 61869-1, ²⁾ acc. to IEC 61869-2, ³⁾ acc. to IEC 62271-1, ΔT - temperature-rise; ΔT_{top} - permitted value in steady state


6. Summary

In tested current instrument transformer type PA 145a with composite insulator, as results of temperature rise test with current $I_{th} = 1800$ A in steady state at range of 1500 A, permitted temperature-rise limits were not exceeded. The tested current transformer met requirements of IEC 61869-1:2007, IEC 61869-2:2012 i IEC 62271-1:2011.

7. Opinions and interpretations

None

8. Photographic documentation



Photograph No. 1. Current transformer on the test stand during temperature-rise test.

Handwritten signature

Handwritten signature

Handwritten signature


274



INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY

Test Report No.
EWP/47/E/2014-1e


APPENDIX No. 1.



INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY

Test Report No.
EWP/47/E/2014-1e

APPENDIX No. 2.





INSTYTUT ENERGETYKI
 INSTITUTE OF POWER ENGINEERING
 LABORATORIUM WIELKOPRAĐOWE
 HIGH CURRENT LABORATORY

01-330 Warszawa
 ul. Mory 6 886
 tel. 22 34 83 86
 tel/fax: 22 834 804 16
 e-mail: ewp@icn.tamp.pl
 www.icn.com.pl/ewp



**INSTITUTE OF POWER ENGINEERING
 HIGH CURRENT LABORATORY**

Test Report No.
 EWP/35/E/2013-1E

**TEST REPORT
 NO. EWP/35/E/2013-1E**

TEST OBJECT: Combined instrument transformer type PVA 145a
MANUFACTURER: ABB Sp. z o.o.
 Power Products
 59 Leszno Str.
 06-300 Przasnysz, Poland

TESTS ORDERED BY: Institute of Power Engineering, High Voltage Department
 Internal order No. EWN/145/E/13 dated 03.12.2013 r.

TYPE OF TESTS: Temperature-rise test
TEST PROCEDURE: IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011, IEC 61869-4:2013, IEC 62271-1:2011

TEST OBJECT DELIVERED: 28.11.2013
DATE OF TESTS: 04.12.2013
TESTS RESULTS: Positive

THE TESTS WERE WITNESSED BY: -
TEST ENGINEER: Mariusz SUL M.Sc. Eng.

HEAD OF LABORATORY: Lidia GRUZA M.Sc. Eng.

Warsaw, 19.02.2014r.

Contents	
1.	Description of the test object
2.	Technical data declared by the Manufacturer
3.	Technical documentation of the test object
4.	Scope of the tests
5.	Tests and their results
6.	Summary
7.	Opinions and interpretations
8.	Photographic documentation

Report contains 18 numbered pages with:	
2	drawings
2	photographs
3	appendices

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
 375



1.	Description of the test object
Test object	Combined instrument transformer
Type	PVA 145a
Serial number	2GKP013K1486140
Manufacturer	ABB Sp. z o.o. Power Products 59 Leszno Str. 06-300 Przasnysz, Poland
Year of production	2013
Insulator	Porcelain insulator
Number of windings	VT part - 5, CT part- 6
Oil type	Nytro Libra
Minimum creepage distance	4495 mm
Insulating oil weight	150 kg
Total weight	620 kg
Dimensions	According to drawing no. 2GKK614121

The laboratory made the identification of test objects on the base of the documentation given in par. 3, appendix no 1. The test object is shown in the photographs No. 1. The object was prepared for testing by the Manufacturer.

2.	Technical data declared by the Manufacturer
Rated voltage	132-√3 kV
Maximum operating voltage	145 kV
Rated frequency	50 Hz
Voltage factor and time	1,9U _w /8h
Rated continuous thermal current, I _{ca}	1200-2400 A
Rated short-time thermal current, I _{sh} /1s	63-63 kA
Rated dynamic current, I _{dyn}	158-158 kA



VT part, variant 1					
Winding	1a-1n	2a-2n	3a-3n	4a-4n	da-dn
Rated secondary voltage	110-√3 V	110-√3 V	110-√3 V	110-√3 V	110 V
Rated output	25 VA	25 VA	25 VA	25 VA	150 VA
Accuracy class	0,2	0,2	0,2/3P	3/3P	1,0
Thermal limiting output	1000 VA	1000 VA	1000 VA	1000 VA	450 VA

VT part, variant 2					
Winding	1a-1n	2a-2n	3a-3n	4a-4n	da-dn
Rated secondary voltage	110-√3 V	110-√3 V	110-√3 V	110-√3 V	110 V
Rated output	25 VA	25 VA	500 VA	25 VA	400 VA
Accuracy class	3	3	3/3P	3/3P	3P
Thermal limiting output	1000 VA	1000 VA	1000 VA	1000 VA	450 VA

CT part					
Winding	Rated secondary current	Rated output	Accuracy class	FS/ALF	Ext.
1S1-1S2	5 A	100 VA	0,2	10	120 %
2S1-2S2	1 A	70 VA	0,1	5	120 %
3S1-3S2	1 A	35 VA	5P	20	-
4S1-4S2	5 A	15 VA	5P	60	-
5S1-5S2	1 A	Rb=1Ω, class PX, Ek=250 V, Ie<0,1 A, Ret=7Ω Rb=20Ω, class TPY, 15x13, Ret=7Ω, Ts=500 ms, cykl 100 ms, Tps=50 ms			
6S1-6S2	1 A	10 VA, class 5PR20, Ret=8Ω Rb=20Ω, class PXR, 2-1/2000, Ek=500V, Ie<0,1 A / 250 V, Ret=5Ω, Ks=20			

3. Technical documentation of the test object	
1.	Drawing no. 2GKK614121 – Dimensional drawing. Combined instrument transformer PVA 123a-145a, ABB Sp. z o.o. Power Products, approved 17.12.2013
2.	Combined transformer verification protocol type PVA 145a, Series No.: 2GKP013K.1486140, ABB Sp. z o.o., Przasnysz, 12.11.2013

4. Scope of the tests			
Test programme agreed with Orderer comprised of tests:			
No.	Kind of test	Tests according the Standard	Location of the test
1.	Temperature-rise tests	IEC 61869-1:2007 p. 6.4.1 7.2.2, IEC 61869-2:2012 p.6.4.1 i 7.2.2.204 IEC 61869-3:2011 p. 6.4.1 i p.7.2.2 IEC 61869-4:2013 p. 6.4.1 i 7.2.2 IEC 62271-1:2011, table no. 3	EWP
EWP The test was performed in Institute of Power Engineering, by High - Current Laboratory.			

5. Tests and their results
<p>Combined transformer was installed at the test stand, as it was during normal operation. Electric diagram of terminal box of tested combined transformer is given in Fig. 1.</p> <p>The rated voltage with a required value was applied to the primary voltage winding. The secondary voltage windings and the residual voltage winding were loaded with the suitable power, according to the test programme given below, which was agreed with the Orderer.</p> <p>Primary current terminals P1 and P2/A was bridged at the range of 2000 A.</p> <p>According to Manufacturer's request current in primary current winding was equal to $I_{th} = 2400$ A.</p> <p>The arrangement of the thermocouples is given in Figure No. 2.</p> <p>The temperature-rises of windings were measured by the resistance rise method.</p> <p>During the test, the measurements of loaded windings were made every 1 hour and registered the deflection of oil level indicator.</p> <p>The resistances of all windings were measured before the tests and after of each stage of tests.</p> <p>The abstract of the protocol of temperature-rise test is given in Table No. 1.</p> <p>The summary of test results is given in Table 2.</p> <p>The temperature-rise of windings were calculated from the formula:</p> $\Delta T = \frac{R - R_0}{R_0} \cdot R_0 \cdot 0,004$

[Signature] 377

Stage No. 1: Test at the rated load

Test was performed according to the IEC 61869-1 sub-cl. 6.4 and 7.2.2; IEC 61869-2 sub-cl. 6.4.1 and 7.2.2.204; IEC 61869-3 sub-cl. 6.4.1 and 7.2.2; IEC 61869-4 sub-cl. 6.4.1 and 7.2.2. The voltage value $1,2 U_n = 91,5$ kV was applied to the P2/A terminal.

The secondary voltage windings were loaded as follows: 1a-1n \Rightarrow 25 VA, $\cos \varphi = 1$, at the voltage 110/√3 V; 2a-2n \Rightarrow 25 VA, $\cos \varphi = 1$, at the voltage 110/√3 V; 3a-3n \Rightarrow 500 VA, $\cos \varphi = 1$, at the voltage 110/√3 V; 4a-4n \Rightarrow 25 VA, $\cos \varphi = 1$, at the voltage 110/√3 V. The winding of residual voltage remained open.

The secondary current windings of the CT were loaded as follows: IS1-1S2 \Rightarrow 100 VA, $\cos \varphi = 1$; 2S1-2S2 \Rightarrow 70 VA, $\cos \varphi = 1$; 3S1-3S2 \Rightarrow 35 VA, $\cos \varphi = 1$; 5S1-5S2 \Rightarrow 2Ω; 6S1-6S2 \Rightarrow 20Ω. Supply (current control) was applied to the secondary current winding 4S1-4S2.

Terminals P1 and P2/A were short-circuited at the range 2000 A.

The test was performed till reached steady state of the measured temperatures.

Stage No. 2: Test of 8 h

Test was performed according to the IEC 61869-1 sub-cl. 6.4 and 7.2.2; IEC 61869-2 sub-cl. 6.4.1 and 7.2.2.204; IEC 61869-3 sub-cl. 6.4.1 and 7.2.2; IEC 61869-4 sub-cl. 6.4.1 and 7.2.2. The voltage value $1,9 U_n = 144,8$ kV was applied to the P2/A terminal.

The secondary voltage windings were loaded as follows: 1a-1n \Rightarrow 25 VA, $\cos \varphi = 1$, at the voltage 110/√3 V; 2a-2n \Rightarrow 25 VA, $\cos \varphi = 1$, at the voltage 110/√3 V; 3a-3n \Rightarrow 500 VA at the voltage 110/√3 V; 4a-4n \Rightarrow 25 VA, $\cos \varphi = 1$, at the voltage 110/√3 V.

The residual winding db-dn was loaded by \Rightarrow 450 VA, $\cos \varphi = 1$, at the voltage 110 V.

The secondary current windings of the CT were loaded as follows: IS1-1S2 \Rightarrow 100 VA, $\cos \varphi = 1$; 2S1-2S2 \Rightarrow 70 VA, $\cos \varphi = 1$; 3S1-3S2 \Rightarrow 35 VA, $\cos \varphi = 1$; 5S1-5S2 \Rightarrow 2Ω; 6S1-6S2 \Rightarrow 20Ω. Supply (current control) was applied to the secondary current winding 4S1-4S2.

Terminals P1 and P2/A were short-circuited at the range 2000 A.

The duration of the test was 8 h.

Stage No. 3: Test with thermal limit power

Test was performed according to the IEC 61869-1 sub-cl. 6.4 and 7.2.2; IEC 61869-2 sub-cl. 6.4.1 and 7.2.2.204; IEC 61869-3 sub-cl. 6.4.1 and 7.2.2; IEC 61869-4 sub-cl. 6.4.1 and 7.2.2. The voltage value $U_n = 63$ kV was applied to the P2/A terminal.

According to Manufacturer's request secondary voltage windings (i.e. 1a-1n, 2a-2n, 3a-3n and 4a-4n) were loaded by limit power 1000 VA, at $\cos \varphi = 1$. The residual winding remained open.

The secondary current windings of the CT were loaded as follows: IS1-1S2 \Rightarrow 100 VA, $\cos \varphi = 1$; 2S1-2S2 \Rightarrow 70 VA, $\cos \varphi = 1$; 3S1-3S2 \Rightarrow 35 VA, $\cos \varphi = 1$; 5S1-5S2 \Rightarrow 2Ω; 6S1-6S2 \Rightarrow 20Ω. Supply (current control) was applied to the secondary current winding 4S1-4S2. Terminals P1 and P2/A were short-circuited at the range 2000 A.

The test was performed till reaching the steady state of the measured temperatures.

[Signature]

378

Measuring instruments

The temperatures were measured by means of type K thermocouples (NiCr - NiAD) with accuracy $\pm 0.6^{\circ}\text{C}$!

The ambient temperature was measured using four mercurial thermometers immersed into tank filled with oil. These thermometers were placed in the distance of 1 meter from the tested transformer at the height of 1 meter above floor- the accuracy of measurement $\pm 0.03^{\circ}\text{C}$!

The resistance was measured by means of meter type 2291 manufactured by TEITEX Instruments with accuracy $\pm 0.01 \text{ m}\Omega$!




Fig. 1. Electrical diagram of terminal box of tested combined instrument transformer

¹ The expanded uncertainty assigned corresponds to a coverage probability of 95 % and the coverage factor $k = 2$.




Fig. 2. Arrangement of thermocouples during temperature-rise test:
 1 - oil (over current coil), 2 - head (contraction of the flange connecting the head the the insulator), 3 - under the flange of tank lid, 4 - lower tank (placed inside over earthing terminal), 5 - terminal P1, 6 - terminal P1, 7 - terminal P2/A (2000A), 8 - terminal P2/A (2000A), 9 - current path inside the combined instrument transformer.

Table No. 1, cont.


Stage No. 1		Stage No. 2		Stage No. 3	
No. of thermo-couple	Heating time (h)	No. of thermo-couple	Heating time (h)	No. of thermo-couple	Heating time (h)
48	22	48	32	48	33
49	23	49	33	49	34
50	24	50	34	50	35
51	25	51	35	51	36
52	26	52	36	52	37
53	27	53	37	53	38
54	28	54	38	54	39
55	29	55	39	55	40
56	30	56	40	56	41
57	31	57	41	57	42
58	32	58	42	58	43
59	33	59	43	59	44
60	34	60	44	60	45
61	35	61	45	61	46
62	36	62	46	62	47
63	37	63	47	63	48
64	38	64	48	64	49
65	39	65	49	65	50
66	40	66	50	66	51
67	41	67	51	67	52
68	42	68	52	68	53
69	43	69	53	69	54
70	44	70	54	70	55
71	45	71	55	71	56
72	46	72	56	72	57
73	47	73	57	73	58
74	48	74	58	74	59
75	49	75	59	75	60
76	50	76	60	76	61
77	51	77	61	77	62
78	52	78	62	78	63
79	53	79	63	79	64
80	54	80	64	80	65
81	55	81	65	81	66
82	56	82	66	82	67
83	57	83	67	83	68
84	58	84	68	84	69
85	59	85	69	85	70
86	60	86	70	86	71
87	61	87	71	87	72
88	62	88	72	88	73
89	63	89	73	89	74
90	64	90	74	90	75
91	65	91	75	91	76
92	66	92	76	92	77
93	67	93	77	93	78
94	68	94	78	94	79
95	69	95	79	95	80
96	70	96	80	96	81
97	71	97	81	97	82
98	72	98	82	98	83
99	73	99	83	99	84
100	74	100	84	100	85
101	75	101	85	101	86
102	76	102	86	102	87
103	77	103	87	103	88
104	78	104	88	104	89
105	79	105	89	105	90
106	80	106	90	106	91
107	81	107	91	107	92
108	82	108	92	108	93
109	83	109	93	109	94
110	84	110	94	110	95
111	85	111	95	111	96
112	86	112	96	112	97
113	87	113	97	113	98
114	88	114	98	114	99
115	89	115	99	115	100
116	90	116	100	116	101
117	91	117	101	117	102
118	92	118	102	118	103
119	93	119	103	119	104
120	94	120	104	120	105
121	95	121	105	121	106
122	96	122	106	122	107
123	97	123	107	123	108
124	98	124	108	124	109
125	99	125	109	125	110
126	100	126	110	126	111
127	101	127	111	127	112
128	102	128	112	128	113
129	103	129	113	129	114
130	104	130	114	130	115
131	105	131	115	131	116
132	106	132	116	132	117
133	107	133	117	133	118
134	108	134	118	134	119
135	109	135	119	135	120
136	110	136	120	136	121
137	111	137	121	137	122
138	112	138	122	138	123
139	113	139	123	139	124
140	114	140	124	140	125
141	115	141	125	141	126
142	116	142	126	142	127
143	117	143	127	143	128
144	118	144	128	144	129
145	119	145	129	145	130
146	120	146	130	146	131
147	121	147	131	147	132
148	122	148	132	148	133
149	123	149	133	149	134
150	124	150	134	150	135
151	125	151	135	151	136
152	126	152	136	152	137
153	127	153	137	153	138
154	128	154	138	154	139
155	129	155	139	155	140
156	130	156	140	156	141
157	131	157	141	157	142
158	132	158	142	158	143
159	133	159	143	159	144
160	134	160	144	160	145
161	135	161	145	161	146
162	136	162	146	162	147
163	137	163	147	163	148
164	138	164	148	164	149
165	139	165	149	165	150
166	140	166	150	166	151
167	141	167	151	167	152
168	142	168	152	168	153
169	143	169	153	169	154
170	144	170	154	170	155
171	145	171	155	171	156
172	146	172	156	172	157
173	147	173	157	173	158
174	148	174	158	174	159
175	149	175	159	175	160
176	150	176	160	176	161
177	151	177	161	177	162
178	152	178	162	178	163
179	153	179	163	179	164
180	154	180	164	180	165
181	155	181	165	181	166
182	156	182	166	182	167
183	157	183	167	183	168
184	158	184	168	184	169
185	159	185	169	185	170
186	160	186	170	186	171
187	161	187	171	187	172
188	162	188	172	188	173
189	163	189	173	189	174
190	164	190	174	190	175
191	165	191	175	191	176
192	166	192	176	192	177
193	167	193	177	193	178
194	168	194	178	194	179
195	169	195	179	195	180
196	170	196	180	196	181
197	171	197	181	197	182
198	172	198	182	198	183
199	173	199	183	199	184
200	174	200	184	200	185
201	175	201	185	201	186
202	176	202	186	202	187
203	177	203	187	203	188
204	178	204	188	204	189
205	179	205	189	205	190
206	180	206	190	206	191
207	181	207	191	207	192
208	182	208	192	208	193
209	183	209	193	209	194
210	184	210	194	210	195
211	185	211	195	211	196
212	186	212	196	212	197
213	187	213	197	213	198
214	188	214	198	214	199
215	189	215	199	215	200
216	190	216	200	216	201
217	191	217	201	217	202
218	192	218	202	218	203
219	193	219	203	219	204
220	194	220	204	220	205
221	195	221	205	221	206
222	196	222	206	222	207
223	197	223	207	223	208
224	198	224	208	224	209
225	199	225	209	225	210
226	200	226	210	226	211
227	201	227	211	227	212
228	202	228	212	228	213
229	203	229	213	229	214
230	204	230	214	230	215
231	205	231	215	231	216
232	206	232	216	232	217
233	207	233	217	233	218
234	208	234	218	234	219
235	209	235	219	235	220
236	210	236	220	236	221
237	211	237	221	237	222
238	212	238	222	238	223
239	213	239	223	239	224
240	214	240	224	240	225
241	215	241	225	241	226
242	216	242	226	242	227
243	217	243	227	243	228
244	218	244	228	244	229
245	219	245	229	245	230
246	220	246	230	246	231
247	221	247	231	247	232
248	222	248	232	248	233
249	223	249	233	249	234
250	224	250	234	250	235
251	225	251	235	251	236
252	226	252	236	252	237
253	227	253	237	253	238
254	228	254	238	254	239
255	229	255	239	255	240
256	230	256	240	256	241
257	231	257	241	257	242
258	232	258	242	258	243
259	233	259	243	259	244
260	234	260	244	260	245
261	235	261	245	261	246
262	236	262	246	262	247
263	237	263	247	263	248
264	238	264	248	264	249
265	239	265	249	265	250
266	240	266	250	266	251
267	241	267	251	267	252
268	242	268	252	268	253
269	243	269	253	269	254
270	244	270	254	270	255
271	245	271	255	271	256
272	246	272	256	272	257
273	247	273	257	273	258
274	248	274	258	274	259
275	249	275	259	275	260
276	250	276	260	276	261
277	251	277	261	277	262
278	252	278	262	278	263
279	253	279	263	279	264
280	254	280	264	280	265
281	255	281	265	281	266
282	256	282	266	282	267
283	257	283	267	283	268
284	258				

Table No. 2. Temperature-rises [K] given during the tests combined instrument transformer PVA 145a serial no. 2GKP013K1486140

Winding	ΔT after Stage No. 1	ΔT after Stage No. 2	ΔT after Stage No. 3	ΔT_{dep}
1S1-1S2	58,06	60,63	63,61	
2S1-2S2	61,56	63,15	66,79	
3S1-3S2	58,31	62,44	65,50	75 ^{1), 2), 4)}
4S1-4S2	61,09	65,14	68,17	
5S1-5S2	57,00	61,17	64,18	
6S1-6S2	57,35	61,46	64,48	
P1-P2/A	Not measured	Not measured	57,49	
1a-1n	9,78	17,49	24,45	
2a-2n	9,91	17,89	25,74	
3a-3n	9,97	18,11	26,50	75 ^{1), 2), 4)}
4a-4n	9,95	18,25	27,33	
da-dn	10,37	19,42	29,56	
P2/A-N	12,84	20,97	39,94	

No.	Location	ΔT after Stage No. 1	ΔT after Stage No. 2	ΔT after Stage No. 3	ΔT_{dep}
1	Oil	35,06	34,00	37,08	55 ^{1), 2), 3), 4)}
2	Head - top part next to terminal	28,20	27,31	32,14	
3	Under the tank lid from side of terminal box	3,37	6,08	6,05	40 ⁵⁾
4	Enclosure of lower tank	<i>Inconsistent results, indicating damage of the thermocouple.</i>			
5	Terminal P1	52,30	48,34	54,98	
6	Terminal P1	56,57	52,13	58,81	65 ⁵⁾
7	Terminal P2/A	38,20	35,23	40,51	
8	Terminal P2/A	41,43	38,76	44,63	
9	Current path inside the combined instrument transformer	46,03	44,59	48,93	75 ^{1), 2), 4)}

¹⁾ acc. to IEC 61869-1, ²⁾ wg IEC 61869-2, ³⁾ acc. to IEC 61869-3, ⁴⁾ acc. to IEC 61869-4, ⁵⁾ acc. to IEC 62271-1,
 ΔT - temperature-rise; ΔT_{dep} - permitted value in steady state

 381

6. Summary

In tested combined instrument transformer type PVA 145a, with porcelain insulator, as results of temperature rise test with current $I_{tab} = 2400$ A:

- in steady state, at the rated load of secondary current and voltage windings (without residual winding), at $\cos \phi = 1$ and supply voltage $1,2U_n$ (Stage No. 1), permitted temperature-rise limits were not exceeded.
- The tested combined transformer met requirements of IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011, IEC 61869-4:2013 and IEC 62271-1:2011 standards.
- results of test 8 h at supply voltage $1,9U_n$ and rated load of current and voltage windings at $\cos \phi = 1$ and load of residual winding with thermal limit power (Stage No. 2), shows that permitted temperature-rise limits were not exceeded.
- The tested combined transformer met requirements of IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011, IEC 61869-4:2013 and IEC 62271-1:2011 standards.
- results of test with thermal limit power (Stage No. 3) at rated load of current windings at $\cos \phi = 1$ and supply voltage U_n , and at the same time loading of all voltage windings (without residual windings) with thermal limit power, shows that permitted temperature-rise limits were not exceeded.
- The tested combined transformer met requirements of IEC 61869-1:2007, IEC 61869-2:2012, IEC 61869-3:2011, IEC 61869-4:2013 and IEC 62271-1:2011 standards.

7. Opinions and interpretations

None




382




INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY

Test Report No.
EWP/35/E/2013-1E

8. Photographic documentation



Photograph No. 1. Combined transformer on the test stand during temperature-rise test.




Photograph No. 2. The conductors short-circuiting of P1-P2A terminals.



INSTITUTE OF POWER ENGINEERING
HIGH CURRENT LABORATORY

Test Report No.
EWP/35/E/2013-1E

APPENDIX NO. 1



APPENDIX NO. 2

ABB

Combined Instrument Transformer

Insulation level: 145/275/650 kV Standard: IEC 61869-4 In: 50 Hz

Oil type: Nytro Libra Weight/Oil: 620 / 150 kg Temperature: -50°C → +40°C

S/N: 2GKP013K1486140 Voltage factor: 1,9Un/8h Ue: 0,2 mV/kA

CURRENT PART

K_n : 1000-2000 / 5-1-1-5-1-1 A/A A-N 132:√3 kV

I_{dyn} : 63-63 kA 158-158 kA

I_{th} : 1200-2400 A

Klasa	VA		FS/ALF		Ext.%
	VA	VA	VA	VA	
1S1-1S2	5	100	0,2	10	120
2S1-2S2	1	70	0,1	5	120
3S1-3S2	1	35	5P	20	-
4S1-4S2	5	15	5P	60	-
5S1-5S2	1	Rd=1Ω, klasa PX, Ek=250V, Ia<=0,1 A, Rct<=7Ω	Rd=2Ω, klasa TPY 15x13, Rct<=7Ω, Ts=500 ms, cykl 100 ms, Tp=50 ms	10 VA klasa 5PR20, Rct<=8 Ω	10 VA klasa 5PR20, Rct<=8 Ω
6S1-6S2	1	Rd=20Ω, klasa PXR, 2-1/2000, Ek=500 V, Ia<=0,1 A / 250 V, Rct<=5Ω, Kx=20			

VOLTAGE PART

Transportation: Vertical/Horizontal

Klasa	VA		FS/ALF		Ext.%
	VA	VA	VA	VA	
1a-1n	110:√3	110:√3	110:√3	110:√3	110
2a-2n	110:√3	110:√3	110:√3	110:√3	150
3a-3n	25	25	0,2	0,2/3P	150
4a-4n	25	25	0,2	3/3P	150
da-dn	110:√3	110:√3	110:√3	110:√3	110
1000	(3)	(3)	(3)	(3/3P)	450
1000	(3)	(3)	(3)	(3/3P)	450

[Handwritten Signature]

APPENDIX NO. 3

ABB

DECLARATION OF CONFORMITY No. 093/2013 (EN)
(acc. to ISO/IEC 17050-1)

Manufacturer: ABB Sp. z o.o. Dept. in Przasnysz

Address: Str. Leszno 59
06-300 Przasnysz / POLAND


Product: Combined Instrument Transformer PVA 145a

Above mentioned product conforms with the following standard :

Standard: IEC 61869 - 4 Title: Combined Instrument Transformers Edition/Date: 2013

Additional information: Serial numbers: 2GKP013K1486140;

Place and date of issue of declaration: Przasnysz 13.01.2014


ABB Sp. z o.o.
 ul. Zegnotka 1, 04-713 Warszawa
 NIP: 526-090-44-64; PL 5260004464
 Region of registration: Mazowiecki
 O D Z I A K N 142777 A S N Y S Z U
 ul. Leszno 59, 06-300 Przasnysz
 tel. (22) 223 8821, fax (22) 223 8859
 -strona ul. Zapylonego Jarka-
 Oddzial w Przasnyszu
 ABB Sp. z o.o.
 Oddzial w Przasnyszu
 ul. Porzeczna 1, Przasnysz

(Name)
 (Signature)

[Handwritten Signature]

(

(



Instytut Elektrotechniki

Electrotechnical Institute



ZESPÓŁ LABORATORIÓW INSTYTUTU ELEKTROTECHNIKI
LABORATORIUM BADAWCZE APARATURY ROZDZIELCZEJ

ul. M. Przemyskiego 28, 04-703 WARSZAWA
tel.: (+48 22) 11 25 300, email: zwiarcie@iel.waw.pl



Laboratorium Badawcze akredytowane przez Polskie Centrum Akredytacji,
systemowa porozumień EA, MILA / ILAC MRA, Nr akredytacji AB 074

AB 074

SPRAWOZDANIE Z BADAŃ nr 8624/NZL/NBR/15

Spis treści

1	Spis norm mających zastosowanie.....	3
2	Program badań.....	3
3	Parametry techniczne deklarowane przez producenta.....	4
4	Podstawowe dane identyfikacyjne obiektu badań.....	4
5	Sprawdzenie przyrządów temperatury.....	5
6	Zajęcia.....	9
7	Rysunki techniczne.....	10
8	Niepewność pomiaru wielkości elektrycznych i nieelektrycznych w laboratorium NBR.....	12

Obiekt badań:	Przekładnik prądowy PA 145a
Zleciłodawca:	ABB Sp. z o.o. ul. Leszno 59, 06-300 Przasnysz
Producent:	ABB Sp. z o.o. ul. Leszno 59, 06-300 Przasnysz
Zlecone badania:	Sprawdzenie przyrządów temperatury
Według norm:	PN-EN 61869-2:2013-06
Numer tematu / zlecenia:	504-028100/038
Data zakończenia badań:	02 kwiecień 2015 r.
Wynik badań:	POZYTYWNY

Autoryzował

[Signature]
mgr inż. Michał Babuch

Kierownik Zespołu
Laboratoriów Instytutu
Elektrotechniki

[Signature]
dr inż. Przemysław Berowski

WARSZAWA, 06.05.2015

Prezentowane w sprawozdaniu wyniki badań dotyczą tylko badanych obiektów. Producent ponosi odpowiedzialność za każdy egzemplarz wyrobu oznakowany identycznie jak wyrob badany.

⊕ Niniejsze sprawozdanie może być powielane tylko w całości. Powielanie częściowe jest możliwe po uzyskaniu pisemnej zgody Laboratorium

Sprawozdanie zawiera 12 stron

[Signature]
385

[Handwritten mark]

[Handwritten mark]

**1 Spis norm mających zastosowanie**

- PN-EN 61869-1:2009 Przekładniki - Część 1: Wymagania ogólne
- PN-EN 61869-2:2013-06 Przekładniki - Część 2: Wymagania szczegółowe dotyczące przekładników prądowych

2 Program badań

- Sprawdzenie przystosów temperatury wg PN-EN 61869-2:2013-06 pkt. 7.2.2

3 Parametry techniczne deklarowane przez producenta

Znamionowy prąd pierwotny.....	I_p	300 – 600 A
Znamionowy długotrwały prąd ciepłny.....	I_{th}	450 – 900 A
Częstotliwość znamionowa.....	f	50 Hz
Najwyższe napięcie robocze.....	U_n	145 kV
Napięcie znamionowe wytrzymywane o częstotliwości sieciowej.....		275 kV
Napięcie znamionowe udarowe wytrzymywane.....		650 kV
Znamionowy krótkotrwały prąd ciepłny.....	I_{th}	40 – 40 kA
Znamionowy prąd dynamiczny.....	I_{dyn}	100 – 100 kA
Czas znamionowy trwania zwarcia.....	t_k	1 s


4 Podstawowe dane identyfikacyjne obiektu badań

Objekt badany:	Przekładnik prądowy
Typ:	PA 145a
Producent:	ABB Sp. z o.o., ul. Leszno 59, 06-300 Przasnysz
Numer fabryczny:	2GKP014A1287181
Rok produkcji:	2014
Tabliczka znamionowa:	Rysunek 4, str. 10
Dokumentacja techniczna:	Rysunek wymiarowy nr 2GKA612003

Wykaz wyposażenia i jego dokładne parametry zawiera dokumentacja: Rysunek wymiarowy nr 2GKA612003



Punkty pomiaru temperatur



Rysunek 2 Rozmieszczenie termopar

Sprawdzenie przyrostów temperatury prądem 900 A / 50 Hz - wyniki

Tabela 1 Wyniki pomiarów przyrostów temperatury

Miejsce pomiaru	Numer termopary	Przyrost temperatury [K]	
		Zmierzony	Dopuszczalny
Obudowa pomiędzy głowicą i mieszkiem	1	37,70	—
Głowica	2	24,90	—
Zacisk P1- podstawa zacisku ruchomego	3	40,60	75
Zacisk P1 - podstawa zacisku stałego	4	44,25	75
Zacisk P2 - podstawa zacisku ruchomego	5	32,7	75
Zacisk P2 - podstawa zacisku najwyższego zakresu	6	35,85	75
Olaj w komorze głównej	7	35,55	55


Handwritten signature



5 Sprawdzenie przyrostów temperatury

Badanie wykonano wg PN-EN 61869-2:2013-06 pkt. 7.2.2
 Stan obiektu przed próbami:..... Nowy
 Data badań:..... 1 kwiecień 2015 r.
 Temperatura otoczenia:
 • Przed próbą..... 14,9°C
 • Po próbie..... 16,5°C
 Czas trwania próby:..... 16 h 25 min.
 Prąd:..... 900 A
 Częstotliwość:..... 50 Hz
 Zakres przekładnika:..... 600 A
 Połączenia zasilańca:..... szyna miedziana 1x1000 mm²
 Rozmieszczenie termopar:..... Rysunek 2; strona 6
 Obiekt na stanowisku probierczym:..... Zdjęcie 1; strona 9

Pomiary przyrostu temperatur wykonano rejestratorem HIOKI 8423, nr inw. NBR-801-30600 oraz termoparami typu K.
 Próba była kontynuowana aż do czasu gdy przyrost temperatury osiągnął stabilną wartość.



Rysunek 1 Schemat obwodu przekładnika podczas próby

Handwritten signature

Handwritten signature and number 387


Tabela 2 Wyniki pomiarów rezystancji i przyrosty temperatury uzwojeń obwodów wtórnych przekładnika

Godz. [h]	T _{olej} [°C]	Pomiary						Wychylenie wskaznika poziomu oleju [mm]
		R _{151,152} [mΩ]	R _{151,152} [mΩ]	R _{151,152} [Ω]	ΔT _{151,152} [K]	ΔT _{151,152} [K]	ΔT _{151,152} [K]	
0	14,90	389,8	431,2	9,20	0	0	0	
1	15,34	402,9	442,6	9,42	8,40	6,60	5,95	
2	15,76	409,6	450,0	9,58	12,75	10,95	10,30	
3	15,99	416,0	456,9	9,76	16,85	14,95	15,25	
4	16,25	423,5	465,9	9,94	21,70	20,20	20,05	
5	16,38	430,3	473,8	10,11	26,10	24,85	24,80	
6	16,55	436,1	480,2	10,28	29,90	28,60	29,45	
7	16,60	442,9	488,3	10,44	34,25	33,30	33,85	
8	16,45	448,5	494,7	10,58	37,85	37,05	37,65	
9	16,63	453,6	500,7	10,72	41,20	40,55	41,50	
10	16,39	462,8	511,2	10,96	44,20	43,70	44,80	
11	16,56	466,5	515,6	11,06	49,50	49,25	50,80	
12	16,48	474,0	520,0	11,16	54,30	51,80	53,50	
14	16,41	473,4	523,6	11,24	53,90	53,85	55,70	
15	16,53	476,3	527,0	11,31	55,80	55,90	57,60	
16	16,50	478,9	530,0	11,38	57,50	57,65	59,55	
Dopuszczalny przyrost temperatury								65 K

Tabela 3 Pomiar rezystancji i przyrost temperatury uzwojeń obwodu pierwotnego przekładnika

	Przed próbą	Po próbie
Data pomiaru	01.04.2015	02.04.2015
R _{P1-P2/A} [μΩ]	347,9	429,3
Temperatura otoczenia [°C]	14,9	16,5
Temperatura uzwojenia pierwotnego [°C] (po ekstrapolacji)	---	75,2
Przyrost temperatury [K]	---	58,7
Dopuszczalny przyrost temperatury [K]	---	65

Pomiary rezystancji wykonano prądem stałym o wartości: obwód pierwotny: 100 A
 obwody wtórne 5 A: 0,5 A
 Pomiary wykonano za pomocą przyrządu pomiarowego typu RMO100GF nr 14G743G
 obwody wtórne 1 A: 0,1 A



Rysunek 3 Temperatura uzwojenia przekładnika po wyłączeniu

Zgodnie z normą PN-EN 61862-2 pkt. 7.2.2.2.03 wyznaczono stałe czasowe z próby nagrzewania, jako czas, jaki upłynął do osiągnięcia 63% wartości maksymalnego zmierzonego przyrostu temperatury.

Tabela 4 Wyznaczone wartości stałych czasowych

Miejsce pomiaru	Numer termopary	Stać czasowa T ₀ [h]
Obudowa pomiędzy głowicą i mieszkiem	1	5
Głowica	2	5,5
Zacisk P1 - zacisk ruchomy	3	1,8
Zacisk P1 - zacisk stały	4	1,8
Zacisk P2 - zacisk ruchomy (600 A)	5	2,8
Zacisk P2 - zacisk stały (600 A)	6	4
Oil w komorze głównej	7	6

Stan obiektu po badaniach:

- Przyrosty temperatury różnych części aparatu nie przekroczyły wartości podanych w normie PN-EN 61869-1:2009, pkt. 6.4.1, tabela 5.
- Nie zauważono żadnych zniszczeń oraz uszkodzeń.

Wynik próby: Pozytywny



7 Rysunki techniczne

ABB

Przekładnik prądowy

Typ: PA 145a

Norma: PN-EN 61869-2

Temperatura pracy: 50 Hz

Temperatura pracy: -40°C ~ +40°C

Waga: 420 / 120 kg

Nyrod: Libra

NF: 2GRKF014A1287181

K_n : 300-600/5-5-1 A/A

$I_n/1S$: 40-40 kA I_{thm} : 100-100 kA

I_{thm} : 450-900 A


A	VA	Klasa	FS/ALF	Ext.%
15H-16Z	5	40	0,2	5
23H-26Z	5	60	5P	20
35H-36Z	1	120	10P	15
45H-46Z				
55H-56Z				
65H-66Z				

Transport: Pionowy/Poziomy


Rysunek 4 Tabliczka znamionowa



6 Zdjęcia



Zdjęcie 1 Przekładnik na stanowisku probierczym próby nagrzewania




Zdjęcie 2 Przekładnik podczas próby nagrzewania



8 Niepewność pomiaru wielkości elektrycznych i nieelektrycznych w laboratorium NBR

Wielkość mierzona / rodzaj przyrządu	Zakres	Częstotliwość	Parametr mierzony / niepewność w [%]	
Napięcie U / dzielnik FC	0 ≤ U ≤ 1000V	dc - 20kHz	RMS	≤ ± 1.5
	1000 V ≤ U ≤ 10kV	> 20kHz	RMS	≤ ± 2.0
		dc - 20kHz	RMS	≤ ± 2.0
	U > 10kV	> 20kHz	RMS	≤ ± 2.5
		50Hz - 20kHz	RMS	≤ ± 3.0
	Prąd I / bocznik	0 ≤ I ≤ 100A	> 20kHz	RMS
dc - 5kHz			RMS	≤ ± 3.0
dc - 5kHz			Całk. Joule'a	≤ ± 1.5
> 5kHz			Całk. Joule'a	≤ ± 2.0
dc - 5kHz			Całk. Joule'a	≤ ± 3.0
> 5kHz			Całk. Joule'a	≤ ± 3.0
I > 10kA		> 5kHz	RMS	≤ ± 1.5
		dc - 5kHz	RMS	≤ ± 2.0
		> 5kHz	Całk. Joule'a	≤ ± 2.0
		> 5kHz	Całk. Joule'a	≤ ± 3.0
		> 5kHz	Całk. Joule'a	≤ ± 3.0
		> 5kHz	Całk. Joule'a	≤ ± 3.0
Prąd I / prądniczk	0 ≤ I ≤ 100A	> 5kHz	RMS	≤ ± 2.5
		50Hz - 5kHz	RMS	≤ ± 2.0
		> 5kHz	Całk. Joule'a	≤ ± 2.5
		> 5kHz	Całk. Joule'a	≤ ± 2.5
		> 5kHz	Całk. Joule'a	≤ ± 3.0
		> 5kHz	Całk. Joule'a	≤ ± 3.0
	100 A ≤ I ≤ 30kA	> 5kHz	RMS	≤ ± 3.0
		50Hz - 5kHz	RMS	≤ ± 2.0
		> 5kHz	Całk. Joule'a	≤ ± 2.5
		> 5kHz	Całk. Joule'a	≤ ± 3.0
		> 5kHz	Całk. Joule'a	≤ ± 3.0
		> 5kHz	Całk. Joule'a	≤ ± 3.0
Rezystancja R / mostek, multimetr	20 μΩ ≤ R ≤ 600 μΩ			≤ ± 5 %
	0.6 mΩ ≤ R ≤ 600 mΩ			≤ ± 3 %
	0.6 Ω ≤ R ≤ 100 MΩ			≤ ± 1 %
	10 kHz ≤ f ≤ 1 MHz			≤ ± 0.2 %
	≤ 1 ps			≤ ± 0.5 %
	1 ps ≤ t ≤ 1 ms			≤ ± 2.0 %
	> 1 ms			≤ ± 1.0 %
	-50 °C ≤ t ≤ 100 °C			≤ ± 1ms
	-100 °C ≤ t ≤ 200 °C			≤ ± 0.2 °C - (termometr)
	20 % do 90% RH			≤ ± 0.8 °C - (termopary K, rejestrator)
	≤ 1 mm			≤ ± 5 % RH
	1 mm ≤ l ≤ 30 mm			≤ ± 0.05 mm
> 30 mm			≤ ± 0.1 mm	
≤ 20 bar			≤ ± 5 %	
20 bar ≤ p ≤ 200 bar			≤ ± 10 %	
Ciążenie atmosferyczne			≤ ± 0.01 MPa	



Rysunek 5 Rysunek wymiarowy





Instytut Elektrotechniki Electrotechnical Institute



ZESPÓŁ LABORATORIÓW INSTYTUTU ELEKTROTECHNIKI
LABORATORIUM BADAWCZE APARATURY ROZDZIELCZEJ
ul. M. Pożaryskiego 28, 04-703 WARSZAWA
tel.: +48 22 812 23 38, fax: +48 22 812 04 07

Testing Laboratory is accredited by Polish Centre of Accreditation,
signature of EA, No. AB 074

AB 074

Table of contents

1	List of applicable standards	3
2	Range of tests performed	3
3	Ratings assigned by the manufacturer	4
4	Temperature rise test	5
5	Photographs	9
6	Drawings	10
7	Uncertainty electrical and non electrical quantities in laboratory	12

TEST REPORT No. 8595/ANZL/NBR/15

Test objects:	Current transformer PA 145a
Client:	ABB Sp. z o.o. ul. Leszno 59, 06-300 Przasnysz
Manufacturer:	ABB Sp. z o.o. ul. Leszno 59, 06-300 Przasnysz
Test specification:	Temperature rise test
Normative document(s):	PN-EN 61869-2:2013-06
Reference/Order number:	504-021300/038
Date of tests completion:	15 January 2015 r.
Test results:	POSITIVE

Authorised by

Piotr Berowski, Ph.D.

Head of Laboratories of the
Electrotechnical Institute

Robert Franaszek, M.Sc.

WARSAW, 11.02.2015

The Test Report applies only to the apparatus tested. The responsibility for conformity of any apparatus having the same designators with that tested rests with the Manufacturer.
© Only integral reproduction of this Test Report is permitted without written permission from Laboratory.

This Test Report comprises 12 sheets in total.



1 List of applicable standards

- PN-EN 61869-1:2009 Instrument transformers - Part 1: General requirements
- PN-EN 61869-2:2013-06 Instrument transformers - Part 2: Additional requirements for current transformers

2 Range of tests performed

- Temperature rise test by PN-EN 61869-2:2013-06 clause 7.2.2

3 Ratings assigned by the manufacturer

Test object: Current transformer
 Type: PA 145a
 Manufacturer: ABB Sp. z o.o., ul. Leszno 59, 06-300 Przasnysz
 Serial No.: 2GKF014A1287155
 Year of manufacture: 2014
 Rating plate: Figure 1, page 10
 Design documentation: 1. Dimensional drawing No. 2GKA612004
 2. Drawing of current circuit No. 2GKK314159A0001

Rated primary current.....	I_p	1500 – 3000 A
Rated continuous thermal current.....	I_{cth}	1800 – 3000 A
Rated frequency.....	f	50 Hz
Highest system voltage.....	U_M	145 kV
Rated power-frequency withstand voltage.....		275 kV
Rated lighting-impulse withstand voltage.....		650 kV
Rated short-time thermal current.....	I_{sh}	63 – 63 kA
Rated dynamic current.....	I_{dyn}	158 – 158 kA
Rated duration of short circuit.....	t_k	1 s

Detailed list of components specified in technical project:

1. Dimensional drawing No. 2GKA612004
2. Drawing of current circuit No. 2GKK314159A0001

392



4 Temperature rise test

Test performed according to PN-EN 61869-2:2013-06 clause 7.2.2

Condition of test object before test:.....New

Date of test:.....14 January 2015 r.

Ambient temperature:

- Before test.....20,4°C
- After test.....18,8°C

Duration of the test:.....24 h 25 min.

Test current:.....1. 3 600 A

.....2. 3 000 A - after 16 hours

Frequency:.....50 Hz


Primary current range:.....3000 A

Supply connection:.....Bars Cu 3x1000 mm²

Test object on testing stand:.....Phot. 1 - 2, page 9

The temperatures were measured with used of recorder HIOKI 8423, No. NBR-801-30600 and thermocouples type K.

Measurement points



Handwritten signature or initials

Handwritten signature

Handwritten signature and number 393

Temperature rise test at current 3000 A / 50 Hz - results

Table 1 Temperature rise test results

Thermocouple location	Thermocouple No.	Stabilized temperature rise [K]	
		Measured	Permitted
Oil in top core	1	31,80	55
Head	2	29,45	—
Connection terminal P1	3	54,25	75
Bolt connection P1	4	56,25	75
Connection terminal P2	5	48,95	75
Bolt connection P2	6	47,70	75
Current circuit 3000 A	7	49,15	—

Table 2 Resistance and temperature rise of secondary windings test results

Heating time [h]	T _a [°C]	Measurements										Deflection of the oil level indicator [mm]						
		R ₁₅₁₋₁₅₂ [mΩ]	R ₁₅₃₋₁₅₄ [mΩ]	R ₁₅₅₋₁₅₆ [mΩ]	R ₁₅₇₋₁₅₈ [mΩ]	R ₁₅₉₋₁₆₀ [mΩ]	R ₁₆₁₋₁₆₂ [mΩ]	R ₁₆₃₋₁₆₄ [mΩ]	R ₁₆₅₋₁₆₆ [mΩ]	ΔT ₁₅₁₋₁₅₂ [K]	ΔT ₁₅₃₋₁₅₄ [K]		ΔT ₁₅₅₋₁₅₆ [K]	ΔT ₁₅₇₋₁₅₈ [K]	ΔT ₁₅₉₋₁₆₀ [K]	ΔT ₁₆₁₋₁₆₂ [K]	ΔT ₁₆₃₋₁₆₄ [K]	ΔT ₁₆₅₋₁₆₆ [K]
0	17,20	450,2	5,458	587,5	5,675	0	0	0	0	0	0	0	0	0	0	0	0	0
1	18,15	463,2	5,540	601,5	5,722	7,30	3,65	5,70	2,00	2,00	2,00	2,00	2,00	2,00	2,00	2,00	2,00	2,00
2	19,00	467,9	6,601	608,2	5,789	10,00	6,40	8,50	4,90	4,90	4,90	4,90	4,90	4,90	4,90	4,90	4,90	4,90
3	19,50	474,1	5,676	616,3	5,863	13,30	9,95	12,00	8,20	8,20	8,20	8,20	8,20	8,20	8,20	8,20	8,20	8,20
4	19,85	480,4	5,736	624,7	5,946	17,10	13,75	15,75	11,95	11,95	11,95	11,95	11,95	11,95	11,95	11,95	11,95	11,95
5	20,15	487,3	5,841	633,5	6,034	21,00	17,95	19,80	16,10	16,10	16,10	16,10	16,10	16,10	16,10	16,10	16,10	16,10
6	20,25	493,7	5,923	642,2	6,119	24,65	22,10	23,95	20,25	20,25	20,25	20,25	20,25	20,25	20,25	20,25	20,25	20,25
7	20,35	500,3	6,003	650,8	6,203	28,40	26,30	28,15	24,50	24,50	24,50	24,50	24,50	24,50	24,50	24,50	24,50	24,50
8	20,40	506,1	6,076	658,5	6,280	31,70	30,20	32,05	28,45	28,45	28,45	28,45	28,45	28,45	28,45	28,45	28,45	28,45
9	20,50	511,7	6,147	665,8	6,354	34,90	34,05	35,85	32,40	32,40	32,40	32,40	32,40	32,40	32,40	32,40	32,40	32,40
10	20,50	516,9	6,210	672,8	6,421	37,85	37,65	39,60	36,10	36,10	36,10	36,10	36,10	36,10	36,10	36,10	36,10	36,10
11	20,55	521,6	6,270	678,9	6,483	40,55	41,00	42,95	39,55	39,55	39,55	39,55	39,55	39,55	39,55	39,55	39,55	39,55
12	20,55	525,6	6,323	684,7	6,540	42,80	44,05	46,15	42,85	42,85	42,85	42,85	42,85	42,85	42,85	42,85	42,85	42,85
13	20,60	529,8	6,375	690,0	6,593	45,20	47,10	49,20	45,95	45,95	45,95	45,95	45,95	45,95	45,95	45,95	45,95	45,95
14	20,65	533,3	6,420	694,8	6,641	47,20	49,75	52,00	48,85	48,85	48,85	48,85	48,85	48,85	48,85	48,85	48,85	48,85
15	20,60	536,7	6,463	699,5	6,685	49,10	52,30	54,75	51,55	51,55	51,55	51,55	51,55	51,55	51,55	51,55	51,55	51,55
16	20,70	539,8	6,501	703,3	6,725	50,90	54,65	57,10	54,05	54,05	54,05	54,05	54,05	54,05	54,05	54,05	54,05	54,05
17	20,60	540,6	6,517	704,4	6,749	51,35	55,55	58,50	56,35	56,35	56,35	56,35	56,35	56,35	56,35	56,35	56,35	56,35
18	20,50	541,5	6,529	705,6	6,764	51,80	56,30	59,50	57,80	57,80	57,80	57,80	57,80	57,80	57,80	57,80	57,80	57,80
19	20,45	541,2	6,535	706,2	6,771	51,65	56,55	60,00	58,90	58,90	58,90	58,90	58,90	58,90	58,90	58,90	58,90	58,90
20	20,15	542,0	6,537	701,4	6,775	52,05	56,75	60,50	59,05	59,05	59,05	59,05	59,05	59,05	59,05	59,05	59,05	59,05
21	18,75	541,7	6,533	706,3	6,773	51,55	56,65	59,00	57,00	57,00	57,00	57,00	57,00	57,00	57,00	57,00	57,00	57,00
22	18,35	541,7	6,533	706,2	6,773	51,50	56,45	58,90	56,65	56,65	56,65	56,65	56,65	56,65	56,65	56,65	56,65	56,65
23	18,60	541,1	6,528	705,8	6,764	51,20	56,10	58,60	56,35	56,35	56,35	56,35	56,35	56,35	56,35	56,35	56,35	56,35
24	18,85	541,0	6,523	705,0	6,758	51,20	55,85	58,15	55,95	55,95	55,95	55,95	55,95	55,95	55,95	55,95	55,95	55,95
Permitted temperature rise											65 K							

Table 3 Resistance and temperature rise of primary windings test results

Date of test	Before test	After test
14.01.2015	14.01.2015	15.01.2015
R _{P1-P2/A} [μΩ]	29	34,5
Ambient temperature [°C]	20,4	18,8
Temperature rise [K]	—	48,1
Permitted temperature rise [K]	—	65

Resistance was measured at direct current : primary circuit: 100 A
 secondary circuit 5 A: 0,5 A
 The measuring instrument type RMO100GP No. 14G743G secondary circuit 1 A: 0,1 A

According to PN-EN 61862-2 clause 7.2.2.2.03 was estimated thermal time constants as the time elapsed until 63% of maximum estimated temperature rise.

Table 4 Thermal time constants

Thermocouple location	Thermocouples No.	Time constant T ₀ [h]
Oil in top core	1	6
Head	2	4
Connection terminal P1	3	1
Bolt connection P1	4	1
Connection terminal P2	5	1,5
Bolt connection P2	6	1,8
Current circuit 3000 A	7	2,5

Condition of tested object after the test:

- The stabilized temperature rise of various parts of the current transformer did not exceed the values specified in the PN-EN 61869-1:2009, clause 6.4.1, table 5.
- No deterioration and failure was noted.

Test result: Object passed the test



6 Drawings

ABB
Current Transformer

Insulation level: 145/175/650 kV Type: PA 145a
 Standard: PN-EN 61869-2 f_n: 50 Hz
 Weight/Oil weight: 360 / 120 kg Temp. range: -40°C ~ +40°C
 Oil type: Nyro Libra
 S/N: 2GKP014A1287155

K_n: 1500-3000/5-1-5-1-1 A/A
 I_{th}/1s: 63-63 kA I_{dyn}: 158-158 kA
 I_{eth}: 1800-3000 A

A	VA	Class	FSI/ALF	Ext.%
1S1-1S2	5	200	0.2	10
2S1-2S2	1	100	0.1	5
3S1-3S2	5	20	5P	60
4S1-4S2	1	35	10P	40
5S1-5S2				
6S1-6S2				



Transportation: Vertical / Horizontal

Figure 1 Rating plate


Handwritten signature



5 Photographs



Phot. 1 Test object on temperature rise testing stand



Phot. 2 Test object on temperature rise testing stand

Handwritten signature

Handwritten text: 395

7 Uncertainty electrical and non electrical quantities in laboratory

Measured quantity	Range	Frequency	Measured parameter / uncertainty (%)	
Voltage U / Divider RC	0 ≤ U ≤ 1000 V	dc - 20kHz	RMS ±1.5 Peak ±1.0	
	1000 V ≤ U ≤ 10 kV	> 20kHz	RMS ±2.5 Peak ±2.0	
		> 20kHz	RMS ±2.5 Peak ±1.5	
		50Hz - 20kHz	RMS ±3.0 Peak ±2.5	
Current I / Shunt	U > 10 kV	> 20kHz	RMS ±3.5 Peak ±3.0	
		dc - 5kHz	RMS ±1.5 Peak - Peak/√8 ±1.0	
	0 ≤ I ≤ 100 A	> 5kHz	RMS ±2.0 Peak - Peak/√8 ±1.5	
		dc - 5kHz	RMS ±3.0 Peak - Peak/√8 ±3.0	
	100 A ≤ I ≤ 10 kA	> 5kHz	RMS ±2.0 Peak - Peak/√8 ±2.0	
		dc - 5kHz	RMS ±3.0 Peak - Peak/√8 ±3.0	
		> 5kHz	RMS ±2.5 Peak - Peak/√8 ±2.0	
		50Hz - 5kHz	RMS ±2.0 Peak - Peak/√8 ±1.5	
		> 5kHz	RMS ±2.5 Peak - Peak/√8 ±2.0	
		dc - 5kHz	RMS ±3.0 Peak - Peak/√8 ±3.0	
Current I / Current transformer	0 ≤ I ≤ 100 A	> 5kHz	RMS ±2.5 Peak - Peak/√8 ±2.5	
		50Hz - 5kHz	RMS ±2.0 Peak - Peak/√8 ±1.5	
		> 5kHz	RMS ±2.5 Peak - Peak/√8 ±2.0	
	100 A ≤ I ≤ 10 kA	> 5kHz	RMS ±2.0 Peak - Peak/√8 ±1.5	
		50Hz - 5kHz	RMS ±2.5 Peak - Peak/√8 ±2.5	
	10 kA ≤ I ≤ 30 kA	> 5kHz	RMS ±3.0 Peak - Peak/√8 ±3.0	
		50Hz - 5kHz	RMS ±3.5 Peak - Peak/√8 ±3.5	
Resistance R bridge, multimeter	20 pΩ ≤ R ≤ 600 pΩ		±3.5 % Peak - Peak/√8	
	0.6 mΩ ≤ R ≤ 600 mΩ		±3 % Peak - Peak/√8	
	0.6 Ω ≤ R ≤ 100 MΩ		±1 % Peak - Peak/√8	
	Frequency f oscilloscope, recorder TR	≤ 10 kHz		±0.2 % Peak - Peak/√8
		10 kHz ≤ f ≤ 1 MHz		±0.5 % Peak - Peak/√8
		≤ 1 μs		±20 % Peak - Peak/√8
		1 μs ≤ t ≤ 1 ms		±10 % Peak - Peak/√8
	Time t oscilloscope, recorder TR	> 1 ms		±5 % RH Peak - Peak/√8
		≤ 1 ms		±10 % Peak - Peak/√8
	Temperature T thermocouples	-50 °C ≤ T ≤ 100 °C		±0.2 °C - thermometer Peak - Peak/√8
		-100 °C ≤ T ≤ 200 °C		±0.8 °C - thermocouples K, recorder Peak - Peak/√8
Relative humidity	20 % db 90% RH		±5 % RH Peak - Peak/√8	
	≤ 1 mm		±5 % Peak - Peak/√8	
	1 mm ≤ L ≤ 30 mm		±10 % Peak - Peak/√8	
Length Lengthmeter	> 30 mm		±5 % Peak - Peak/√8	
	≤ 30 mm		±10 % Peak - Peak/√8	
Gas pressure p	≤ 20 bar		±5 % Peak - Peak/√8	
	20 bar ≤ p ≤ 200 bar		±10 % Peak - Peak/√8	
Atmosph. pressure	≤ 20 bar		±5 % Peak - Peak/√8	
	20 bar ≤ p ≤ 200 bar		±10 % Peak - Peak/√8	




Figure 2 Dimensional drawing

366

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	3
4. Tests and their detailed results	4
5. Test results evaluation	4
Annexes: 1. Photographs taken during the tests	5
2. Documentations delivered by orderer	8

TEST REPORT No. EUR/34/E/14-1 E

TEST OBJECT: Current transformer type PA 145a with spiral composite insulator
Serial No. 2GKP014A1287155

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegalska 1, 04-713 Warszawa
order No. 4500574872 dated 22.07.2014

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 21.08.2014

TESTS RESULT: Positive for
Fr = 3600 N

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

Test engineer

HEAD OF LABORATORY

Tomasz Kaczmareczyk

Lidia Gruza

Warsaw, 05.09.2014

[Handwritten signature] 397

Report contents:

numbered pages	9
tables	1
photographs	6

1. TEST OBJECT

1.1 Description

Current transformer type PA 145a is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of current transformer mounted housing with spiral composite insulator immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

- Maximum operating voltage 145 kV
- Rated frequency 50 Hz
- Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:

- dimensional drawing current instrument transformer PA 145, No. 2GKA612004, 01.08.2014,
- rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised the following tests according to requirements of IEC 61869-1:2007:

- mechanical tests acc. to item 7.4.5 of above standard for $F_R = 3600$ N of P1 and P2 3000 A terminals.

During the tests deflection of the transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the transformer was fixed to the rigid construction of the test stand. Mechanical tests were performed applying the load consecutively to the transformer's P1 and P2 3000 A terminals as shown on photographs in Annex 1.

4. TESTS AND THEIR DETAILED RESULTS

Tests results presents table 1. The load was increased and released smoothly (30 – 90 s) and was maintained 60 s. During the tests deflection of the transformer was recorded by laser displacement sensor (accuracy of measurement $\pm 0,1$ mm).

During the tests the following records were made:

- phot. 1 to 6 - current transformer during mechanical tests.
- (Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3620$ N

Test No.	Terminal	Load direction	Test time s	Observations
1	P1	longitudinal	60	During the static load deflection was 16,9 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.
2	P1	transverse	60	During the static load deflection was 21,4 mm. Residual deflection was 1,3 mm. After tests no damage nor oil leak was stated.
3	P1	vertical	60	During the static load deflection was 4,9 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.
4	P2 3000 A	longitudinal	60	During the static load deflection was 16,3 mm. Residual deflection was 1,3 mm. After tests no damage nor oil leak was stated.
5	P2 3000 A	transverse	60	During the static load deflection was 20,9 mm. Residual deflection was 0,3 mm. After tests no damage nor oil leak was stated.
6	P2 3000 A	vertical	60	During the static load deflection was 3,9 mm. Residual deflection was 0,1 mm. After tests no damage nor oil leak was stated.

5. TESTS RESULTS EVALUATION


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of tests of tested current transformer is positive for:

$F_R = 3600$ N.




ANNEX 1


Photographs taken during the tests




Phot. 1. Longitudinal load of terminal P1



Phot. 2. Transverse load of terminal P1



Phot. 3. Vertical load of terminal P1



Phot. 4. Longitudinal load of terminal P2 3000 A

Handwritten signature


Handwritten signature

MU/399




INSTITUTE OF POWER ENGINEERING
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.
EUR/34/E/14-1 E
Page 7/9



Phot. 5. Transverse load of terminal P2 3000 A



Phot. 6. Vertical load of terminal P2 3000 A




INSTITUTE OF POWER ENGINEERING
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.
EUR/34/E/14-1 E
Page 8/9

ANNEX 2

Documentations delivered by orderer






Current Transformer

Insulation level 145/275/650 kV Standard PN-EN 61869-2 Type PA 145a
 Oil type Nyro Libra Weight / Oil 360 / 120 kg Temp. range -40°C → +40°C
 S/N 26KP014A12B7155

K_n 1500-3000/5-1-5-1-1 A/A
 I_{th}/I_s 63-63 kA I_{dyn} 158-158 kA
 I_{th} 1800-3600 A

A	VA	Class	FS/ALF	Ext.%
1S1-1S2	5	200	0,2	10
2S1-2S2	1	100	0,1	5
3S1-3S2	5	20	5P	60
4S1-4S2	1	35	10P	40
5S1-5S2	1	40	10P	20
6S1-6S2				

Transportation Vertical / Horizontal



Instrument transformer electrical diagram

- ATTENTION!**
- HIGH VOLTAGE AT OPER. CURRENT SECONDARY TERMINALS XS1 - XS2
 - DURING INSTRUMENT TRANSFORMER OPERATION TERMINAL 1S6 MUST BE EARTHED

[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
201

TEST REPORT No. EUR/34/E/14-2 E

TEST OBJECT: Current transformer type PA 145a with composite insulator
Serial No. 2GKP014A1287180

MANUFACTURER: ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

TESTS ORDERED BY: ABB Sp. z o.o., ul. Żegalska 1, 04-713 Warszawa
order No. 4500574872 dated 22.07.2014

TYPE OF TESTS: Mechanical tests

TESTS PROCEDURE: According to IEC 61869-1:2007 p. 7.4.5

DATE OF TESTS: 22.08.2014

TESTS RESULT: Positive for
Fr = 3600 N

Tests result refers only to the test object

THE TESTS WERE WITNESSED BY:

Test engineer

[Signature]

Tomasz Kaczmarczyk

HEAD OF LABORATORY

[Signature]

Lidia Gruza

Warsaw, 23.09.2014

[Signature]

Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	3
4. Tests and their detailed results	4
5. Test results evaluation	4
Annexes: 1. Photographs taken during the tests	5
2. Documentations delivered by orderer	8

Report contents:

numbered pages	9
tables	1
photographs	6

[Handwritten mark]

[Handwritten mark] 403

1. TEST OBJECT

1.1 Description

Current transformer type PA 145a is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of current transformer mounted housing with composite insulator immersed with transformer oil.

1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

- Maximum operating voltage 145 kV
- Rated frequency 50 Hz
- Rated static load 3600 N

1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:

- dimensional drawing current instrument transformer PA 145a, No. 2GKK612002, 11.09.2014, - rating plate,
- instrument transformer electrical diagram prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate.

1.4 Preparation for tests

The test object was prepared for test by factory.

2. SCOPE OF TESTS

Test program, agreed with orderer, comprised the following tests according to requirements of IEC 61869-1:2007:

- mechanical tests acc. to item 7.4.5 of above standard for $F_R = 3600$ N of P1 and P2 2000 A terminals.

During the tests deflection of the transformer shall be recorded.

3. TEST AND MEASURING CIRCUITS

For the tests the transformer was fixed to the rigid construction of the test stand. Mechanical tests were performed applying the load consecutively to the transformer's P1 and P2 2000 A terminals as shown on photographs in Annex 1.

4. TESTS AND THEIRS DETAILED RESULTS

Tests results presents table 1. The load was increased and released smoothly (30 – 90 s) and was maintained 60 s.

During the tests the following records were made:

- phot. 1 to 6 - current transformer during mechanical tests.
- (Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at $F = 3620$ N

Test No.	Terminal	Load direction	Test time s	Observations
1	P1	longitudinal	60	During the static load deflection was 32,5 mm. Residual deflection was 0,8 mm. After tests no damage nor oil leak was stated.
2	P1	transverse	60	During the static load deflection was 42,5 mm. Residual deflection was 0,5 mm. After tests no damage nor oil leak was stated.
3	P1	vertical	60	During the static load deflection was 4,5 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.
4	P2 2000 A	longitudinal	60	During the static load deflection was 36,3 mm. Residual deflection was 1,1 mm. After tests no damage nor oil leak was stated.
5	P2 2000 A	transverse	60	During the static load deflection was 39,8 mm. Residual deflection was 0,4 mm. After tests no damage nor oil leak was stated.
6	P2 2000 A	vertical	60	During the static load deflection was 7,0 mm. Residual deflection was 0,1 mm. After tests no damage nor oil leak was stated.

5. TESTS RESULTS EVALUATION


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of tests of tested current transformer is positive for:

$F_R = 3600$ N.




ANNEX 1


Photographs taken during the tests




Phot. 1. Longitudinal load of terminal P1



Phot. 2. Transverse load of terminal P1



Phot. 3. Vertical load of terminal P1




Phot. 4. Longitudinal load of terminal P2 2000 A


Handwritten signature

Handwritten signature

Handwritten signature / 2105




Phot. 5. Transverse load of terminal P2 2000 A



Phot. 6. Vertical load of terminal P2 2000 A



ANNEX 2 Documentations delivered by orderer





ABB


Current Transformer

Insulation level Standard Type
 Oil type Weight/Oil weight Temp. range
 S/N

K_n A/A
 I_{th}/I_s kA kA
 I_{cth} A

A	VA	Class	FS/ALF	Ext.%
1S1-4S2	5	100	0,2	10
2S1-2S2	1	70	0,1	5
3S1-3S2	1	35	5P	20
4S1-4S2	5	15	5P	60
5S1-5S2	1	30	5P	30
6S1-6S2	1	10	5P	20

Transportation Vertical / Horizontal



Instrument transformer electrical diagram

- ATTENTION!
- HIGH VOLTAGE AT OPEN CURRENT SECONDARY TERMINALS X51 - X52
 - DURING INSTRUMENT TRANSFORMER OPERATION TERMINAL '96 MUST BE EARTHED

SM

[Signature]

[Signature]
1107



**„Доставка на електрически апарати
110кV“, реф. № РРД 17-064.**

**Обособена позиция 2 – Доставка на
токови измервателни трансформатори
110кV за монтаж на открито – 21бр.**

ПРИЛОЖЕНИЕ 5



ПОЛСКИ ЦЕНТЪР ЗА АКРЕДИТАЦИЯ



Подписваща страна ЕА МСА

СЕРТИФИКАТ ЗА АКРЕДИТАЦИЯ НА ЛАБОРАТОРИЯ ЗА КАЛИБРИРАНЕ

№ AP 168

Това е, за да се потвърди, че:

ABB Sp. z o.o.,
Ул. Зеганска 1, 04-713 Варшава
Лаборатория за калибриране
ABB Продукти Високо Напрежение клон в Пшашниш
ул. Лешно 59, 06-300 Пшашниш, Полша

отговаря на изискванията на стандарт PN-EN ISO/IEC 17025:2005

Акредитирана дейност се определя в обхвата на акредитация № AP 168

Тази акредитация остава в сила, при условие че Лабораторията съблюдава изискванията на органа за акредитация, определени в договор № AP 168

Сертификатът за акредитация е валиден до 20.12.2020 г.

Директор
Лучина Олборска

Варшава, 21 Декември 2016 г.

LMB

POLSKIE CENTRUM AKREDYTACJI

POLISH CENTRE FOR ACCREDITATION

ABB Sp. z o.o.
ul. Żegańska 1, 04-713 Warszawa
KRS 0000444444, PL 266304464
NIP 525-104-7168
BIURO W PRZASNYSZU
ul. Leszno 59, 06-300 Przasnysz
t. (22) 223 8849, fax (22) 223 8958
(16)



Sygnatariusz EA MLA
EA MLA Signatory

CERTYFIKAT AKREDYTACJI

LABORATORIUM WZORCUJĄCEGO

ACCREDITATION CERTIFICATE OF CALIBRATION LABORATORY

Nr AP 168

Potwierdza się, że: / This is to confirm that:


ABB Sp. z o.o.
ul. Żegańska 1, 04-713 Warszawa
Laboratorium Wzorcujące
ABB PGHV w Przasnyszu
ul. Leszno 59, 06-300 Przasnysz

spełnia wymagania normy PN-EN ISO/IEC 17025:2005
meets requirements of the PN-EN ISO/IEC 17025:2005 standard

Akredytowana działalność jest określona w Zakresie Akredytacji Nr AP 168
Accredited activity is defined in the Scope of Accreditation No AP 168

Akredytacja pozostaje w mocy pod warunkiem przestrzegania
wymagań jednostki akredytującej określonych w kontrakcie Nr AP 168
This accreditation remains in force provided the Laboratory observes
the requirements of Accreditation Body defined in the Contract No AP 168

Certyfikat akredytacji ważny do dnia 20.12.2020 r.
The certificate of accreditation is valid until 20.12.2020



DYREKTOR
POLSKIEGO CENTRUM AKREDYTACJI

Lucyna Olborska
LUCYNA OLBORSKA

Warszawa, dnia 21 grudnia 2016 roku

LMB
213

ПОЛСКИ ЦЕНТЪР ЗА АКРЕДИТАЦИЯ



Подписваща страна ЕА МСА

СЕРТИФИКАТ ЗА АКРЕДИТАЦИЯ НА СЕРТИФИЦИРАЩ ОРГАН ЗА ПРОДУКТИ № АС 117

Това е, за да се потвърди, че:

**ИНСТИТУТ ПО ЕНЕРГЕТИКА
ИНСТИТУТ ЗА ИЗСЛЕДВАНИЯ
отдел СЕРТИФИЦИРАНЕ
ул. Мори 8, 01-330 Варшава**

отговаря на изискванията на стандарт PN-EN ISO/IEC 17065:2013-03

Акредитирана дейност се определя в обхвата на акредитация № АС 177

Тази акредитация остава в сила, при условие че Организацията съблюдава изискванията на органа за акредитация, определени в договор № АС 117

Сертификатът за акредитация е валиден до 03.02.2021 г.

Акредитацията е предоставена на 04.02.2005 г.

р.о. Директор
Лучина Олборска

Варшава, 27 Януари 2017 г.

ПОЛСКИ ЦЕНТЪР ЗА АКРЕДИТАЦИЯ



Подписваща страна ЕА МЛА

СЕРТИФИКАТ ЗА АКРЕДИТАЦИЯ НА ЛАБОРАТОРИЯ ЗА ИЗПИТАНИЯ № АВ 323

Това е, за да се потвърди, че:

ИНСТИТУТ ПО ЕНЕРГЕТИКА
Лаборатория Високо Напрежение
ул. Мори 8, 01-330 Варшава

отговаря на изискванията на стандарт PN-EN ISO/IEC 17025:2005

Акредитирана дейност се определя в обхвата на акредитация № АВ 323

Тази акредитация остава в сила, при условие че Лабораторията съблюдава изискванията на органа за акредитация, определени в договор № АВ 323

Сертификатът за акредитация е валиден до 27.12.2019 г.

Акредитацията е предоставена на 28.12.2000 г.

ДИРЕКТОР
ПОЛСКИ ЦЕНТЪР ЗА АКРЕДИТАЦИЯ
Луцина Олборска

Варшава, 16 Ноември 2015 г.

ПОЛСКИ ЦЕНТЪР ЗА АКРЕДИТАЦИЯ



Подписваща страна EA MLA

СЕРТИФИКАТ ЗА АКРЕДИТАЦИЯ НА ЛАБОРАТОРИЯ ЗА ИЗПИТАНИЯ
№ АВ 324

Това е, за да се потвърди, че:

ИНСТИТУТ ПО ЕНЕРГЕТИКА
Лаборатория Разпределителни Устройства
ул. Мори 8, 01-330 Варшава

отговаря на изискванията на стандарт PN-EN ISO/IEC 17025:2005

Акредитирана дейност се определя в обхвата на акредитация № АВ 324

Тази акредитация остава в сила, при условие че Лабораторията съблюдава изискванията на органа за акредитация, определени в договор № АВ 324

Сертификатът за акредитация е валиден до 27.12.2019 г.

Акредитацията е предоставена на 28.12.2000 г.

ДИРЕКТОР
ПОЛСКИ ЦЕНТЪР ЗА АКРЕДИТАЦИЯ
Луцина Олборска

Варшава, 24 Ноември 2015 г.

()

()

SMW

POLSKIE CENTRUM AKREDYTACJI

POLISH CENTRE FOR ACCREDITATION



Sygnatariusz EA MLA
EA MLA Signatory

CERTYFIKAT AKREDYTACJI

JEDNOSTKI CERTYFIKUJĄCEJ WYROBY

ACCREDITATION CERTIFICATE FOR PRODUCT CERTIFICATION BODY

Nr AC 117

Potwierdza się, że: / This is to confirm that:

INSTYTUT ENERGETYKI
INSTYTUT BADAWCZY
ZESPÓŁ ds. CERTYFIKACJI
ul. Mory 8, 01-330 Warszawa

spełnia wymagania normy PN-EN ISO/IEC 17065:2013-03
meets requirements of the PN-EN ISO/IEC 17065:2013-03 standard

Akredytowana działalność jest określona w Zakresie Akredytacji Nr AC 117
Accredited activity is defined in the Scope of Accreditation No AC 117

Akredytacja pozostaje w mocy pod warunkiem przestrzegania
wymagań jednostki akredytującej określonych w kontrakcie Nr AC 117
This accreditation remains in force provided the Body observes
the requirements of Accreditation Body defined in the Contract No AC 117

Certyfikat akredytacji ważny do dnia 03.02.2021 r.
The certificate of accreditation is valid until 03.02.2021

Akredytacji udzielono dnia 04.02.2005 r.
Accreditation was granted on 04.02.2005



DYREKTOR
POLSKIEGO CENTRUM AKREDYTACJI

LUCYNA OLBORSKA

Warszawa, 27 stycznia 2017 roku

90/2017/1119

C

O

Lomo

POLSKIE CENTRUM AKREDYTACJI

POLISH CENTRE FOR ACCREDITATION



Sygnatariusz EA MLA
EA MLA Signatory

CERTYFIKAT AKREDYTACJI

LABORATORIUM BADAWCZEGO

ACCREDITATION CERTIFICATE OF TESTING LABORATORY

Nr AB 324

Potwierdza się, że: / This is to confirm that:

INSTYTUT ENERGETYKI
LABORATORIUM URZĄDZEŃ ROZDZIELCZYCH
ul. Mory 8, 01-330 Warszawa

spełnia wymagania normy PN-EN ISO/IEC 17025:2005
meets requirements of the PN-EN ISO/IEC 17025:2005 standard

Akredytowana działalność jest określona w Zakresie Akredytacji Nr AB 324
Accredited activity is defined in the Scope of Accreditation No AB 324

Akredytacja pozostaje w mocy pod warunkiem przestrzegania
wymagań jednostki akredytującej określonych w kontrakcie Nr AB 324
This accreditation remains in force provided the Laboratory observes
the requirements of Accreditation Body defined in the Contract No AB 324

Certyfikat akredytacji ważny do dnia 27.12.2019 r.
The certificate of accreditation is valid until 27.12.2019

Akredytacji udzielono dnia 28.12.2000 r.
Accreditation was granted on 28.12.2000

DYREKTOR
POLSKIEGO CENTRUM AKREDYTACJI

Lucyna Olborska
LUCYNA OLBORSKA




ABB
ABB Sp. z o.o.
ul. Puławska 1, 04-713 Warszawa
t. 22 630 41 41, PL 5000304484
Regon: 14047168
DZIAŁ W PRZASNYSZU
ul. Leszno 52, 08-300 Przasnysz
t. (22) 223 8849, fax (22) 223 8958
(16)

Warszawa, 24 listopada 2015 roku

APK/21

POLSKIE CENTRUM AKREDYTACJI
POLISH CENTRE FOR ACCREDITATION



Sygnatariusz EA MLA
EA MLA Signatory

CERTYFIKAT AKREDYTACJI
LABORATORIUM BADAWCZEGO
ACCREDITATION CERTIFICATE OF TESTING LABORATORY
Nr AB 323

Potwierdza się, że: / This is to confirm that:

INSTYTUT ENERGETYKI
LABORATORIUM WIELKOPRĄDOWE
ul. Mory 8, 01-330 Warszawa

spełnia wymagania normy PN-EN ISO/IEC 17025:2005
meets requirements of the PN-EN ISO/IEC 17025:2005 standard


Akredytowana działalność jest określona w Zakresie Akredytacji Nr AB 323
Accredited activity is defined in the Scope of Accreditation No AB 323

Akredytacja pozostaje w mocy pod warunkiem przestrzegania
wymagań jednostki akredytującej określonych w kontrakcie Nr AB 323
This accreditation remains in force provided the Laboratory observes
the requirements of Accreditation Body defined in the Contract No AB 323

Certyfikat akredytacji ważny do dnia 27.12.2019 r.
The certificate of accreditation is valid until 27.12.2019

Akredytacji udzielono dnia 28.12.2000 r.
Accreditation was granted on 28.12.2000

ABB
ABB Sp. z o.o.
Regańska 1, 04-713 Warszawa
526-0261404, PL5260304484
Regon 1410017168
DZIAŁ W PRZASNYSZU
ul. Leszno 59, 08-300 Przasnysz
t. (22) 223 8849, fax (22) 223 8958
(16)



DYREKTOR
POLSKIEGO CENTRUM AKREDYTACJI

LUCYNA OLBORSKA

Warszawa, 16 listopada 2015 roku



**„Доставка на електрически апарати
110кV“, реф. № РРД 17-064.**

**Обособена позиция 2 – Доставка на
токови измервателни трансформатори
110кV за монтаж на открито – 21бр.**

ПРИЛОЖЕНИЕ 6



MS

ABB		ROUTINE TEST PLAN for Current Transformers Plan próby wyrobu Przekładników Prądowych				Number / Numer 2GKA614153	Page / Strona 1 Pages / Stron 3	
Test		Valid for order / KU Obowiązuje do zam. dla / KU						
Sl. No	Badanie	Test according to: Badanie według:	Requirement according to: Wymaganie według:	Place of test Miejsce badania	Remarks Uwagi	Date Data	Acceptance Akceptacja	Signature Podpis
1	Enclosure tightness test at ambient temperature	IEC 61869-1	Cl. 7.3.7.2	Quality control - ABB Przasnysz			<input type="checkbox"/>	
2	Sprawdzenie szczelności obudowy w temperaturze otoczenia Verification of terminal markings and technical parameters	IEC 61869-1 IEC 61869-2	Cl. 6.13; 7.3.6 Cl. 6.13	Kontrola Jakości Quality control - ABB Przasnysz			<input type="checkbox"/>	
3	Sprawdzenie oznakowania zacisków i parametrów technicznych Power-frequency voltage withstand tests on primary windings and partial discharge measurement	IEC 61869-1 IEC 61869-2 IEC 60270	Cl. 7.3.1; 7.3.2 Cl. 7.3.1	Kontrola Jakości Quality control - ABB Przasnysz			<input type="checkbox"/>	
4	Measurement of windings' internal resistance and ambient temperature Pomiar wewnętrznych rezystancji uzwojeń i temperatury otoczenia	IEC 61869-2	Cl. 7.3.201 Order (if special requirements) Zamówienie (jeśli są specjalne wymagania)	Kontrola Jakości Quality control - ABB Przasnysz			<input type="checkbox"/>	
Prepared by Opracował		Date Data	Checked by Sprawdził	Date Data	Approved by Zatwierdził		Date Data	
Ł. Lubieniecki		27.07.2015	J. Duzdowski	27.07.2015	P. Dębski		27.07.2015	

MS

425

ABB		ROUTINE TEST PLAN for Current Transformers <i>Plan próby wyrobu dla Przekładników Prądowych</i>				Number / Numer 2GKA614153	Page / Strona 2 Pages / Stron 3	
						Type/ Typ		
		Valid for order / KU Obowiązuje do zam. dla / KU						
Sl. No	Test <i>Badanie</i>	Test according to: <i>Badanie według:</i>	Requirement according to: <i>Wymaganie według:</i>	Place of test <i>Miejsce badania</i>	Remarks <i>Uwagi</i>	Date <i>Data</i>	Acceptance <i>Akceptacja</i>	Signature <i>Podpis</i>
5	Power-frequency voltage withstand tests on secondary terminals and between sections (if applicable) <i>Próba izolacji uzwojeń wtórnych oraz między sekcjami uzwojeń (jeśli ma zastosowanie) napięciem o częstotliwości sieciowej</i>	IEC 61869-1	Cl. 7.3.3; 7.3.4	Quality control - ABB Przasnysz Kontrola Jakości			<input type="checkbox"/>	
6	Measurement of factors: FS/ALF/Ts/Ek/Ie/Kr and magnetizing characteristic <i>Pomiar współczynników: FS/ALF/Ts/Ek/Ie/Kr i charakterystyki magnesowania</i>	IEC 61869-2	Cl. 7.2.6.202; 7.3.5.203; 7.3.5.205; 7.3.202; 7.3.203; 7.2.6.206	Quality control - ABB Przasnysz Kontrola Jakości			<input type="checkbox"/>	
7	Inter-turn overvoltage test <i>Próba izolacji międzyzwojowej</i>	IEC 61869-2	Order Zamówienie	Quality control - ABB Przasnysz Kontrola Jakości			<input type="checkbox"/>	
8	Capacitance and dielectric dissipation factor measurement <i>Pomiar pojemności i współczynnika strat dielektrycznych</i>	IEC 61869-1 IEC 61869-2	Cl. 7.4.3 Cl. 7.4.3	Quality control - ABB Przasnysz Kontrola Jakości			<input type="checkbox"/>	
Prepared by <i>Opracował</i>		Date <i>Data</i>	Checked by <i>Sprawdził</i>	Date <i>Data</i>	Approved by <i>Zatwierdził</i>	Date <i>Data</i>		
Ł. Lubieniecka		27.07.2015	J. Duzdowski	27.07.2015	P. Dębski	27.07.2015		

ABB ABB		ROUTINE TEST PLAN for Current Transformer <i>Plan próby wyrobu dla Przekładników Prądowych</i>				Number / Numer 2GKA614153	Page / Strona 3 Pages / Stron 3	
						Type/ Typ		
						Valid for order / KU Obowiązuje do zam. dla / KU		
Sl. No	Test	Test according to: Badanie według:	Requirement according to: Wymaganie według:	Place of test Miejsce badania	Remarks Uwagi	Date Data	Acceptance Akceptacja	Signature Podpis
9	Test for accuracy of the current transformer: • Tests for ratio error and phase displacement of measuring CT; • Tests for ratio error and phase displacement of class P; PR; TPX; TPY and TPZ protective CT • Test for turns ratio error for class PX and PXR protective CT <i>Próby dokładności przekładnika prądowego:</i> • Próby błędów przekładni i przesunięcia kąтового przekładnika pomiarowego; • Próby błędów przekładni i przesunięcia kąтового przekładnika zabezpieczeniowego o klasach P, PR, TPX, TPY, TPZ • Próba błędów przekładni zwojowej dla klas PX i PXR przekładnika zabezpieczeniowego	IEC 61869-2	Cl. 7.3.5.201, 7.3.5.202, 7.3.5.204, 7.3.5.206	Quality control - ABB Przasnysz Kontrola Jakości			<input type="checkbox"/>	
10	Inspection : visual check & verification of parameters according to order <i>Ogledziny – sprawdzenie zgodności parametrów z zamówieniem</i>	--	Order	Quality control - ABB Przasnysz Kontrola Jakości			<input type="checkbox"/>	
Prepared by Opracował		Date Data	Checked by Sprawdził	Date Data	Approved by Zatwierdził		Date Data	
Ł. Lubieniecki		27.07.2015	J. Duzdowski	27.07.2015	P. Dębski		27.07.2015	

ABB

ROUTINE TEST PLAN for Current Transformers

План за рутинни изпитания на Токов Трансформатор

 Number /Номер
 2GKA614153

 Page / Страница 1
 Pages / Общо 3

Type/ Тип

 Valid for order / KU
 Валидно за поръчка / КУ

-- units of Current Transformers (-- брой Токови Трансформатори)


Sl. No	Test Изпитание	Test according to: Изпитание съгл.:	Requirement according to: Изисквания съгласно:	Place of test Място на изпитанието	Remarks Забележки	Date Дата	Acceptance Приемане	Signature Подпис
1	Enclosure tightness test at ambient temperature Изпитание за херметичност при температура на околната среда Verification of terminal markings and technical parameters	IEC 61869-1	Cl. 7.3.7.2	Quality control - ABB Przasnysz Контрол на качеството				
2	Проверка на маркировката на клемите и техническите параметри	IEC 61869-1 IEC 61869-2	Cl. 6.13; 7.3.6 Cl. 6.13	Quality control - ABB Przasnysz Контрол на качеството				
3	Power-frequency voltage withstand tests on primary windings and partial discharge measurement Обявено издържано напрежение с промишлена честота за изолацията на първичната намотка и измерване на частичните разряди.	IEC 61869-1 IEC 61869-2 IEC 60270	Cl. 7.3.1; 7.3.2 Cl. 7.3.1	Quality control - ABB Przasnysz Контрол на качеството				
4	Measurement of windings' internal resistance and ambient temperature Измерване на вътрешното съпротивление на намотките и температурата	IEC 61869-2 --	Cl. 7.3.201 Order (if special requirements) Поръчка (при специални изисквания)	Quality control - ABB Przasnysz Контрол на качеството				
Prepared by Подготвено от	Date Дата	Checked by Проверено от	Date Дата	Approved by Одобрено от	Date Дата			
L. Lubieniecki	27.07.2015	J. Duzdowski	27.07.2015	P. Dębski	27.07.2015			

ABB		ROUTINE TEST PLAN for Current Transformers План за рутинни изпитания на Токове Трансформатори				Number /Номер 2GKA614153	Page / Страница 1 Pages / Общо 3	
ABB		-- units of Current Transformers (-- брой Токови Трансформатори)				Type/ Тип		
ABB		Valid for order / KU Валидно за поръчка / KU						
Sl. №	Test Изпитание	Test according to: Изпитание съгл.:	Requirement according to: Изисквания съгласно:	Place of test Място на изпитанието	Remarks Забележки	Date Дата	Acceptance Приемане	Signature Подпис
5	Power-frequency voltage withstand tests on secondary terminals and between sections (if applicable) <i>Обявено издържано напрежение с промишлена честота за изолацията на вторичните клеми и между секциите (ако е приложимо)</i>	IEC 61869-1	Cl. 7.3.3; 7.3.4	Quality control - ABB Przasnysz <i>Контрол на качеството</i>				
6	Measurement of factors: FS/ALF/Ts/Ek/Le/Kr and magnetizing characteristic <i>Измерване на фактори: FS/ALF/Ts/Ek/Le/Kr и намагнитващите характеристики</i>	IEC 61869-2 --	Cl. 7.2.6.202; 7.3.5.203; 7.3.5.205; 7.3.202; 7.3.203; 7.2.6.206 Order <i>Поръчка</i>	Quality control - ABB Przasnysz <i>Контрол на качеството</i>				
7	Inter-turn overvoltage test <i>Изпитание на пренапрежение на сътрясните навивки</i>	IEC 61869-2	Cl. 7.3.204	Quality control - ABB Przasnysz <i>Контрол на качеството</i>				
8	Capacitance and dielectric dissipation factor measurement <i>Измерване на капацитет и фактор на диелектрично разсейване</i>	IEC 61869-1 IEC 61869-2	Cl. 7.4.3 Cl. 7.4.3	Quality control - ABB Przasnysz <i>Контрол на качеството</i>				
Prepared by Подготвено от		Checked by Проверено от		Date Дата	Approved by Одобрено от		Date Дата	
Ł. Lubieniecki		J. J. Jowski		27.07.2015	Ł. Jowski		27.07.2015	

ROUTINE TEST PLAN for Current Transformers

План за рутинни изпитания на Токов Трансформатор

Number /Номер
2GKA614153

Page / Страница 1
Pages / Общо 3

Туре/ Тип

-- units of Current Transformers (-- брой Токови Трансформатори)

Valid for order / KU
Валидно за поръчка / KU

Sl. №	Test Изпитание	Test according to: Изпитание съгл.:	Requirement according to: Изисквания съгласно:	Place of test Място на изпитанието	Remarks Забележки	Date Дата	Acceptance Приемане	Signature Подпис	
9	<p>Test for accuracy of the current transformer:</p> <ul style="list-style-type: none"> Tests for ratio error and phase displacement of measuring CT; Tests for ratio error and phase displacement of class P; PR; TPX; TPY and TPZ protective CT Test for turns ratio error for class PX and PXR protective CT <p>Изпитание на точността на ТТ:</p> <p>Изпитание на грешката и фазовото отместане на ТТ за мерене ;</p> <ul style="list-style-type: none"> Изпитание на грешката и фазовото отместане на клас P; PR; TPX; TPY; TPZ на ТТ за защита Проверка за грешка в съотношението на навиците за клас PX и PXR на ТТ за защита 	IEC 61869-2	Cl. 7.3.5.201, 7.3.5.202, 7.3.5.204, 7.3.5.206	Quality control - ABB Przasnysz Контрол на качеството					
10	<p>Inspection : visual check & verification of parameters according to order</p> <p>Инспекция: Визуална проверка и проверка на параметрите по поръчка</p>	--	Order	Quality control - ABB Przasnysz Контрол на качеството					
Prepared by Подготвено от		Checked by Проверено от		Date Дата		Approved by Одобрено от		Date Дата	
E. Lubieniecki		J. Duzdowski		27.07.2015		P. Dębski		27.07.2015	

SM



ДЕКЛАРАЦИЯ

за приемане на условията в проекта на договор


Долуподписаните Екехарт Нойрайтер и Стефан Минчев в качеството ни на представляващи АББ България ЕООД участник в обществена поръчка с предмет: „Доставка на електрически апарати 110кV“, реф. № PPD 17-064 Обособена позиция 2 - Доставка на токови измервателни трансформатори 110 kV за монтаж на открито – 21 бр.

ДЕКЛАРИРАМЕ, ЧЕ:

Приемаме условията в проекта на договор, приложен в документацията за участие.

Дата: 11.07.2017

Декларатор:


.....
Екехарт Нойрайтер
Управител
АББ България ЕООД


.....
Стефан Минчев
Управител
АББ България ЕООД

ABB Bulgaria EOOD
Main Office
9, Hristofor Kolumb Blvd., fl. 3
Mladost, Sofia-grad
1592 Sofia, Bulgaria
Phone: +359 (0) 2 807 55 00
Fax: +359 (0) 2 807 55 99
Web: www.abb.bg
E-mail: office@bg.abb.com

UIC: 831133152
VAT Nr.: BG 831133152
Bank details:
ING Bank, branch Sofia
IBAN: BG13INGB91451000027317 (BGN)
IBAN: BG60INGB91451400027311 (EUR)
BIC: INGBBGSF



03.2017

SM 433



ДЕКЛАРАЦИЯ
за срока на валидност на офертата

Долуподписаните,

Екехарт Бернхард Нойрайтер, притежаващ лична карта ID N: L8XHOJRMR издадена на 11.03.2013 – Германия, адрес гр. София, бул. Христофор Колумб № 9, ет.3,
в качеството ми на Управител на АББ България ЕООД

и

Стефан Василев Минчев, притежаващ лична карта №641790843, издадена на 11.01.2011 от МВР – гр. София, адрес: гр. София, бул. Христофор Колумб № 9, ет.3,
в качеството ми на Управител на АББ България ЕООД,


участник в процедура за възлагане на обществена поръчка с предмет: „Доставка на електрически апарати 110kV“, реф. № РРД 17-064, Обособена позиция 2 - Доставка на токови измервателни трансформатори 110 kV за монтаж на открито – 21 бр.

ДЕКЛАРИРАМЕ, ЧЕ:

С подаване на настоящата оферта, направените от нас предложения и поети ангажменти са валидни за срока, посочен в обявлението, считано от крайния срок за подаване на офертите.

Дата: 11.07.2017

Декларатор:



Екехарт Нойрайтер
Управител
АББ България ЕООД


Стефан Минчев
Управител
АББ България ЕООД

ABB Bulgaria EOOD
Main Office
9, Hristofor Kolumb Blvd., fl. 3
Mladost, Sofia-grad
1592 Sofia, Bulgaria
Phone: +359 (0) 2 807 55 00
Fax: +359 (0) 2 807 55 99
Web: www.abb.bg
E-mail: office@bg.abb.com

UIC: 831133152
VAT Nr.: BG 831133152
Bank details:
ING Bank, branch Sofia
IBAN: BG13INGB91451000027317 (BGN)
IBAN: BG60INGB914514000027311 (EUR)
BIC: INGBBGSF



 435

