

## ОПИС НА ДОКУМЕНТИТЕ, СЪДЪРЖАЩИ СЕ В ОФЕРТАТА

за участие в процедура за възлагане на обществена поръчка с предмет:  
„Модернизация (ретрофит) на електрически уредби 110/20 (10) kV и въвеждането им в режим на телемеханика“

№	Наименование на документа	Форма на документа (оригинал или заверено копие) /Страница № (от .... до ... )
1.	Опис на представените документи	Оригинал Стр.1 – 2
2.	Единен европейски документ за обществени поръчки (ЕЕДОП)	Оригинал Стр. 3 – 16
3.	Предложение за изпълнение на поръчката за обособена позиция № 2	Оригинал Стр. 17 – 18
	Приложение № 1 – Срокове за изпълнение на ретрофита	Оригинал Стр. 19 – 20
	Приложение № 2	Оригинал Стр. 21 – 25
	Приложение 1.1 – каталожна информация за разединител	Заверено копие Стр. 26 – 30
	Приложение 1.2 – техническо описание, инструкции за разединител	Заверено копие Стр. 31 – 38
	Приложение 1.3 – Протоколи от типови изпитания на разединител	Заверено копие Стр. 39 – 59
	Приложение 1.4. – Сертификат на независимата лаборатория, провела типовите изпитания	Заверено копие Стр. 60 – 66
	Приложение 2.1 – Каталогна информация за токов измервателен трансформатор	Заверено копие Стр. 67 – 70
	Приложение 2.2. – Удостоверение за одобрен тип средство за измерване	Заверено копие Стр. 71 – 72
	Приложение 2.3. – Техническо описание на токовите измервателни трансформатори, инструкции и др	Заверено копие Стр. 73 – 74
	Приложение 2.4. – Протоколи от типови изпитания на токовите измервателни трансформатори	Заверено копие Стр. 75 – 159
	Приложение 2.5 – Акредитация на независимата изпитателна лаборатория, провела типовите изпитания	Заверено копие Стр. 160 – 163
	Приложение 2.6 – Информация за провежданите рутинни изпитания	Заверено копие Стр. 164 – 175
	Приложение 3 – Каталогна информация за цифрови защиты	Заверено копие Стр. 176 – 340
	Приложение 4 – каталожна информация за цифров локален контролер	Заверено копие Стр. 341 – 351
	Приложение 5.1 – Каталогна информация за вакуумни прекъсвачи	Заверено копие Стр. 352 – 404
	Приложение 5.2 – Протоколи от типови изпитания на вакуумни прекъсвачи	Заверено копие Стр. 405 – 426
	Приложение 5.3 – Акредитация на независимата изпитателна лаборатория, провела типовите изпитания	Заверено копие Стр. 427 – 440

	Приложение 6.1. – Техническа информация за токови трансформатори 20 kV за монтиране на закрито, фиксиран	Заверено копие Стр. 441 – 445
	Приложение 6.2 – Удостоверение за одобрен тип средство за измерване	Заверено копие Стр. 446 – 459
	Приложение 6.3 – Протоколи от типови изпитания на токови измервателни трансформатори	Заверено копие Стр. 460 – 482
	Приложение 6.4 – Акредитация на независимата изпитателна лаборатория, провела типовите изпитания	Заверено копие Стр. 483 – 485
	Приложение 7.1 – Техническа информация за Напреженов измервателен трансформатор 20 kV, еднополюсен, с две вторични намотки, за монтиране на закрито	Заверено копие Стр. 486 – 490
	Приложение 7.2 – Удостоверение за одобрен тип средство за измерване	Заверено копие Стр. 491 – 498
	Приложение 7.3. – Протокол от първоначална метрологична проверка	Заверено копие Стр. 499 – 521
	Приложение 7.4. – Акредитация на независимата изпитателна лаборатория, провела типовите изпитания	Заверено копие Стр. 522 – 524
	Приложение № 3 – Комуникация на цифрови устройства за RTU	Оригинал Стр. 525
4.	Декларация за конфиденциалност и извършен оглед на обект по предмета на поръчката Декларация за конфиденциалност във връзка с посещение на обект	Оригинал Стр. 526 – 527
5.	Декларация за приемане на условията в проекта на договор	Оригинал Стр. 528
6.	Декларация за срока на валидност на офертата на участника	Оригинал Стр. 529
7.	Ценово предложение за обособена позиция № 2 Представено в отделен непрозрачен и запечатан плик с надпис „Предлагани ценови параметри	Оригинал 1 бр

Дата 24.07.2017 г.

ПОДПИС И ПЕЧАТ:

Петър Терев

(име и фамилия)

Управител

(длъжност на представляващия участника)





ПРИЛОЖЕНИЕ № 1

**СРОКОВЕ ЗА ИЗПЪЛНЕНИЕ НА РЕТРОФИТА ПО ОБОСОБЕНА ПОЗИЦИЯ № 2:**

Проектирането, доставката на цялостното оборудване и изпълнението на всички необходими дейности за цялостната реализация на реконструкцията на ОРУ 110 kV и на модернизацията (ретрофита) на ЗРУ 20 kV (като демонтаж на съществуващо оборудване, строителни работи /включително доставка на необходимите строителни материали/ по подготовка на площадките в енергийния обект за извършване на монтажа на новото оборудване, монтажни работи по отношение на доставеното ново енергийно оборудване, единични функционални проби на монтираните машини и съоръжения и въвеждането им в работен режим на телемеханика, както и провеждане на обучение на персонал на възложителя за работа с новото оборудване) и настоящото техническо задание следва да се изпълнят в срок до 18 (осемнадесет) месеца, считано от датата на подписване на договора за изпълнение на поръчката.

**1. Срок за изготвяне на програмата с линейния план-график за цялостно изпълнение на модернизацията (ретрофита) и представянето ѝ на Възложителя:**

Срокът за изготвяне на програмата с линейния план-график и представянето ѝ на Възложителя за одобрение е до 14 (четирнадесет) дни, считано от датата на подписване на договора. Срокът за одобрение на предложената програма с линеен план-график от Възложителя е до 3 (три) дни, считано от датата на представяне на изработената програмата с линейния план-график на Възложителя.

**2. Изготвяне на работен проект:**

Срокът за проектирането на реконструкцията на ОРУ 110 kV и на модернизацията (ретрофита) на ЗРУ 20 kV в пълен обем е до 20 (двадесет) дни след датата на подписване на Договора с конкретния Изпълнител.

**3. Съгласуване на работния проект с „ЧЕЗ Разпределение България“ АД:**

Срокът за съгласуване на работния проект е до 10 (десет) дни след датата на предаването му на Възложителя.

**4. Доставка на цялостно оборудване, съгласно утвърдения работен проект:**

Срокът за доставка на цялостното оборудване за изпълнение на предмета на поръчката съобразно предвижданията на съгласувания работен проект, както и на всички необходими резервни части, включително и за изработката и доставката на необходимите за модернизацията (ретрофита) врати и детайли в заводски условия, е до 50 (петдесет) дни от датата на одобрена от Възложителя заявка до съответен доставчик, по количествено – стойностни сметки към договора.

В допълнение, доставките на цялостното оборудване, апарати и помощни съоръжения, съответстващи на утвърдения линеен график следва да се изпълнява планово на работната площадка.

**5. Срок за изпълнение на реконструкцията на ОРУ 110 kV и на модернизацията (ретрофита) на ЗРУ 20 kV:**

Изпълнението на реконструкцията на ОРУ 110 kV и на модернизацията (ретрофита) на ЗРУ 20 kV, включително и въвеждане на вериги за телемеханика, е до 30 (тридесет) дни от датата на първия подписан възлагателен протокол за изпълнение на реконструкцията на ОРУ 110 kV или на модернизацията (ретрофита) на ЗРУ 20 kV.

Срокът за изпълнение на дейности по реконструкцията на ОРУ 110 kV и на модернизацията (ретрофита) на ЗРУ 20 kV, като демонтаж на съществуващо оборудване, строителни работи /включително доставка на необходимите строителни материали/ по подготовка на площадките в енергийния обект за извършване на монтажа на новото оборудване и монтажни работи по отношение на доставеното ново енергийно оборудване, единични функционални проби на монтираните машини и съоръжения и въвеждането им в работен режим на телемеханика е до 30 (тридесет) дни, считано от датата на първия възлагателен протокол.

**6. Обучение на специалисти на Възложителя:**

- Срокът за изготвяне от страна на избрания Изпълнител на програма за обучение на 6-ма служители на Възложителя и предаването ѝ за одобрение на Възложителя е до 10 (десет) дни, считано от датата на съгласуване на работния проект от Възложителя и предаването му на Изпълнителя;
- Срокът за одобрение на програмата за обучение от страна на Възложителя е до 2 (два) дни, след датата на предаването ѝ на Възложителя.



000019

- Срокът за провеждане на обучението и сертифицирането на 6-ма служители на Възложителя, за работа и поддръжка на доставеното и монтирано оборудване, включително цифрови защиты и др. е до 10 (десет) дни, след датата на одобрение на програмата за обучение от страна на Възложителя.

**7. Изработване и предоставяне на екзекутивна документация:**

Срокът за изработване и предоставяне от Изпълнителя на Възложителя на екзекутивни чертежи (документация) с нанесени всички изменения в работния проект, настъпили в процеса на изпълнение на реконструкцията на ОРУ 110 kV и на модернизацията (ретрофита) на ЗРУ 20 kV, е до 15 (петнадесет) работни дни, считано от датата на последния подписан възлагателен протокол за изпълнение на ретрофит на присъединение 20 kV, с който приключва целия обем дейности в обекта, но не по-късно от датата на провеждане на 72 часовите проби под напрежение и товар.

**8. Провеждане на 72-часови проби под напрежение и товар:**

Срокът за провеждане на 72-часови проби под напрежение и товар и въвеждане на енергийния обект 110/20 kV и свързаните с нормалната му експлоатация апарати и съоръжения в работен режим е до 10 (десет) работни дни, считано от датата на протокола на приемателната комисия за приемане на цялостното изпълнение на реконструкцията на ОРУ 110 kV и на модернизацията (ретрофита) на ЗРУ 20 kV в пълен обем за целия обект.

Дата 21.07.2017 г.

ПОДПИС И ПЕЧАТ:



Петър Терев  
(име и фамилия)

управител

(длъжност на представителя на участника)



000020



**ПРИЛОЖЕНИЕ №2**

**ТАБЛИЦА 1 КЪМ ОБОСОБЕНА ПОЗИЦИЯ № 2  
СТАНДАРТ НА МАТЕРИАЛА ЗА РАЗЕДИНИТЕЛ С ЦЕНТРАЛНО РАЗДЕЛЯНЕ И С ДВА ЗАЗЕМИТЕЛНИ  
НОЖА 110 kV, 1250 kA**

Изисквания към документацията и изпитванията:

№	Документи за участие	Приложение № или текст
1.	Точно обозначение на типа, производителя и страната на производство (произход) и последно издание на каталога на производителя	Разединител тип SDF123 .Приложение 1.1
2.	Техническо описание на изделието, в т.ч. гарантирани параметри и съоръжаване	Приложение 1.2
3.	Протоколи от типови изпитвания на английски или български език съгл. съответните стандарти от серията БДС EN 62271 или еквивалентно/и, проведени от независима акредитирана изпитателна лаборатория – заверени копия (и допълнителни изпитвания, ако са проведени),	Приложение 1.3
4.	Сертификат/акредитация на независимата изпитателна лаборатория, провела типовите изпитвания – заверено копие	Приложение 1.4

Технически параметри на разединители с централно разделяне и с два заземителни ножа 110 kV, за монтаж на открито, които се ползват от Участника в графа „Гарантирано предложение“:

Наименование на материала		Разединител с централно разделяне и с два заземителни ножа 110 kV, за монтиране на открито	
Съкратено наименование на материала		РДЗН 110 kV, ОМ	
№	Параметър	Изискване	Гарантирано предложение
1.	Тип/референтен номер съгласно каталога на производителя	Да се посочи	SDF123/1600E2
2.	Производител	Да се посочи	АББ България ЕООД, България

**ТАБЛИЦА 2 КЪМ ОБОСОБЕНА ПОЗИЦИЯ № 2  
СТАНДАРТ НА МАТЕРИАЛА ЗА ТОКОВ ИЗМЕРВАТЕЛЕН ТРАНСФОРМАТОР 110 kV,  
150/300/600/5/5/5/5 A**

Изисквания към документацията и изпитванията:

№	Документи при участие	Приложение № (или текст)
1.	Точно обозначение на типа на токовите измервателни трансформатори, производителя и страната на произход и последно издание на каталога на производителя	Токови измервателни трансформатори тип PA123a Производител: ABB Sp. z o.o. Произход: Полша. Приложение 2.1
2.	Удостоверение за одобряване на типа на токовите измервателни трансформатори, издадено по реда и при условията на Закона за измерванията	Приложение 2.2
3.	Техническо описание на токовите измервателни трансформатори, гарантирани параметри и характеристики, тегло и др.	Приложение 2.3
4.	Протоколи от типови изпитвания на токовите измервателни трансформатори на английски или български език, проведени от независима изпитателна лаборатория с приложени резултати от изпитванията	Приложение 2.4
5.	Сертификат/акредитация на независимата изпитателна лаборатория, провела типовите изпитвания – заверено копие	Приложение 2.5
6.	Информация за провежданите от производителя контролни (рутинни) изпитвания	Приложение 2.6

000021

Технически параметри на токови измервателни трансформатори 110 kV, за монтаж на открито, които се попълват от Участника в графа „Гарантирано предложение“:

Наименование на материала		Токов измервателен трансформатор 110 kV, 150/300/600/5/5/5/5 A за монтиране на открито	
Съкратено наименование на материала		ТИТ 110 kV, 150/300/600/5/5/5/5 A, OM	
№	Параметър	Изискване	Гарантирано предложение
1.	Тип/референтен номер съгласно каталога на производителя	Да се посочи	PA123a
2.	Производител	Да се посочи	ABB Sp. z o.o., Полша

**ТАБЛИЦА 3 КЪМ ОБОСОБЕНА ПОЗИЦИЯ № 2  
СТАНДАРТ НА МАТЕРИАЛА ЗА ЦИФРОВИ ЗАЩИТИ ЗА СИЛОВ ДВУНАМОТЪЧНИ  
ТРАНСФОРМАТОРИ 110/20 (НАДЛЪЖНО – ДИФЕРЕНЦИАЛНА ЗАЩИТА И РЕЗЕРВНА МАКСИМАЛНО  
ТОКОВА ЗАЩИТА)**

Технически данни за основна цифрова надлъжна диференциална защита на силов двунамотъчен трансформатор, които се попълват от Участника в графа „Гарантирано предложение“:

Название на материала		Основна цифрова надлъжна диференциална защита на силов двунамотъчен трансформатор	
Съкратено название на материала		Основна ЦНДЗ СДТ	
№	Технически параметър	Изискване	Гарантирано предложение
1.	Тип	Да се посочи	MICOM P633
2.	Производител	Да се посочи	Шнайдер

Технически данни за резервна цифрова максималнотокова защита на силов двунамотъчен трансформатор, които се попълват от Участника в графа „Гарантирано предложение“:

Название на материала		Резервна цифрова максималнотокова защита на силов двунамотъчен трансформатор	
Съкратено название на материала		Резервна ЦМТЗ СДТ	
№	Технически параметър	Изискване	Гарантирано предложение
1.	Тип	Да се посочи	MICOM P132
2.	Производител	Да се посочи	Шнайдер

**ТАБЛИЦА 4 КЪМ ОБОСОБЕНА ПОЗИЦИЯ № 2  
ЦИФРОВ ЛОКАЛЕН КОНТРОЛЕР ЗА БЛОК ЛИНИЯ - ТРАНСФОРМАТОР 110 KV**

Технически данни, които се попълват от Участника в графа „Гарантирано предложение“:

№	Технически характеристики	Изискване	Гарантирано предложение
1.	Тип	Да се посочи	MiCOM C264
2.	Производител	Да се посочи	Шнайдер

**ТАБЛИЦА 5 ЗА ОБОСОБЕНА ПОЗИЦИЯ № 2  
СТАНДАРТ НА МАТЕРИАЛА ЗА ТРИПОЛЮСНИ ВАКУУМНИ ПРЕКЪСВАЧИ, 24 KV, ЗА МОНТИРАНЕ НА  
ЗАКРИТО, ФИКСИРАНИ**

Изисквания към документацията и изпитванията:

№	Документ при участие	Приложение № (или текст)
1.	Техническо описание на прекъсвача, в т.ч. гарантирани параметри и съоръжаване	Вакуумен прекъсвач, 24 kV Приложение №5.1
2.	Протоколи от типови изпитвания на английски или български език, проведени от независима акредитирана изпитвателна лаборатория – заверени копия (и допълнителни изпитвания, ако са проведени), с приложен списък на отделните изпитвания на български език.	Приложение №5.2
3.	Сертификат/акредитация на независимата изпитвателна лаборатория, провела типовите изпитвания – заверено копие	Приложение №5.3

000022

Технически данни за триполюсен вакуумен прекъсвач 24 kV/1250 A/20 kA, за монтиране на закрито, фиксиран, които се попълват от Участника в графа „Гарантирано предложение“:

Наименование на материала		Триполюсен вакуумен прекъсвач, 24 kV/800 A/20 kA, за монтиране на закрито, фиксиран	
Съкратено наименование на материала		Трип. вак. прек., 24 kV/1250 A/20 kA, 3М, Ф	
№	Технически параметър	Изискване	Гарантирано предложение
1.	Тип/референтен номер съгласно каталога на производителя	Да се посочи	3АН5283-2
2.	Производител	Да се посочи	SIEMENS AG
3.	Обявен нормален ток, I <sub>n</sub>	≥ 1250 A	1250 A

Технически данни за триполюсен вакуумен прекъсвач 24 kV/630 A/20 kA, за монтиране на закрито, фиксиран, които се попълват от Участника в графа „Гарантирано предложение“:

Наименование на материала		Триполюсен вакуумен прекъсвач, 24 kV/630 A/20 kA, за монтиране на закрито, фиксиран	
Съкратено наименование на материала		Трип. вак. прек., 24 kV/630 A/20 kA, 3М, Ф	
№	Технически параметър	Изискване	Гарантирано предложение
1.	Тип/референтен номер съгласно каталога на производителя	Да се посочи	3АН5283-2
2.	Производител	Да се посочи	SIEMENS AG
3.	Обявен нормален ток, I <sub>n</sub>	≥ 630 A	1250 A

**ТАБЛИЦА № 6 ЗА ОБОСОБЕНА ПОЗИЦИЯ № 2  
СТАНДАРТ НА МАТЕРИАЛА ЗА ТОКОВИ ТРАНСФОРМАТОРИ 20 KV ЗА МОНТИРАНЕ НА ЗАКРИТО,  
ФИКСИРАН**

Изисквания към документацията и изпитванията:

№	Документ за участие	Приложение № (или текст)
1.	Точно обозначение на типа на токовите измервателни трансформатори, производителя и страната на произход и последно издание на каталога на производителя	Тип: АТВ 20-BS Производител: ESITAS ELEKTRIKSAN. VE TIC. A.S. Страна на произход: Турция Приложение 6.1.
2.	Удостоверение за одобряване на типа на токовите измервателни трансформатори, издадено по реда и при условията на Закона за измерванията	Приложение 6.2.
3.	Протоколи от типови изпитвания на токовите измервателни трансформатори на английски или български език, проведени от независима изпитателна лаборатория с приложени резултати от изпитванията, представени при доставка	Приложение 6.3.
4.	Сертификат/акредитация на независимата изпитателна лаборатория, провела типовите изпитвания – заверено копие	Приложение 6.4.

Технически параметри на токови измервателни трансформатори 20 kV, 800/5/5 A, подпорен тип, за монтиране на закрито, които се попълват от Участника в графа „Гарантирано предложение“:

Наименование на материала		Токъв измервателен трансформатор 10 kV, 800/5/5 A за монтиране на закрито	
Съкратено наименование на материала		ТИТ 10 kV, 800/5/5 A, 3М	
№	Параметър	Изискване	Гарантирано предложение
1.	Тип/референтен номер съгласно каталога на производителя	Да се посочи	АТВ 20-BS

000023

2.	Производител	Да се посочи	ESITAS ELEKTRIKSAN. VE TIC. A.S.
----	--------------	--------------	--

Технически параметри на токови измервателни трансформатори 20 kV, 300/5/5 A, подпорен тип, за монтиране на закрито, които се попълват от Участника в графа „Гарантирано предложение“:

Наименование на материала		Токов измервателен трансформатор 10 kV, 300/5/5 A за монтиране на закрито	
Съкратено наименование на материала		ТИТ 10 kV, 300/5/5 A, 3М	
№	Параметър	Изискване	Гарантирано предложение
1.	Тип/референтен номер съгласно каталога на производителя	Да се посочи	ATB 20-BS
2.	Производител	Да се посочи	ESITAS ELEKTRIKSAN. VE TIC. A.S.

**ТАБЛИЦА № 7 ЗА ОБОСОБЕНА ПОЗИЦИЯ № 2  
СТАНДАРТ НА МАТЕРИАЛА ЗА НАПРЕЖЕНОВИ ТРАНСФОРМАТОРИ 20 kV, ЕДНОПОЛЮСЕН, С ДВЕ  
ВТОРИЧНИ НАМОТКИ, ЗА МОНТИРАНЕ НА ЗАКРИТО**

Изисквания към документацията и изпитванията:

№	Документ за участие	Приложение № (или текст)
1.	Точно обозначение на типа на напреженовия трансформатор (НИТ), производителя и страна на произход и последно издание на каталога на производителя	Тип: VTB 20-K Производител: ESITAS ELEKTRIKSAN. VE TIC. A.S. Страна на произход: Турция Приложение 7.1.
2.	Удостоверение за одобряване на типа на НИТ, издадено по реда и при условията на Закона за измерванията	Приложение 7.2.
3.	Протокол от първоначална метрологична проверка, проведена от оправомощена лаборатория, съгласно действащото в Република България законодателство в областта на измерванията (представя се при доставка за всеки НИТ)	Приложение 7.3.
4.	Сертификат/акредитация на независимата изпитателна лаборатория, провела типовите изпитвания – заверено копие	Приложение 7.4.

Технически параметри на напреженови измервателни трансформатори 20 kV, еднополюсен, с две вторични намотки, за монтиране на закрито, които се попълват от Участника в графа „Гарантирано предложение“:

Наименование на материала		Напреженов измервателен трансформатор 20 kV, еднополюсен, с две вторични намотки, за монтиране на закрито	
Съкратено наименование на материала		НИТ 20 kV, 1P, с две вторични намотки, 3М	
№	Параметър	Изискване	Гарантирано предложение
1.	Тип/референтен номер съгласно каталога на производителя	Да се посочи	VTB 20-K
2.	Производител	Да се посочи	ESITAS ELEKTRIKSAN. VE TIC. A.S.

**ТАБЛИЦА 8 КЪМ ОБОСОБЕНА ПОЗИЦИЯ № 2  
СТАНДАРТ НА МАТЕРИАЛА ЗА ЦИФРОВИ ЗАЩИТИ ЗА ВЪЗДУШНИ И КАБЕЛНИ  
ЕЛЕКТРОПРОВОДНИ ЛИНИИ СР.Н.**

060024

Технически данни за непосочна цифрова защита за въздушни и кабелни електропроводни линии СрН., които се попълват от Участника в графа „Гарантирано предложение“:

Название на материала		Непосочна цифрова защита за въздушни и кабелни електропроводни линии СрН	
Съкратено название на материала		Непосочна ЦЗ ВКЕЛ СрН	
№	Технически параметър	Изискване	Гарантирано предложение
1.	Тип	Да се посочи	VAMP 57
2.	Производител	Да се посочи	Шнайдер

Дата 21.07.2017 г.

ПОДПИС и ПЕЧАТ:

Петър Терев


(име и фамилия)

управител

(длъжност на представителя на участника)




000025



Horizontal center break disconnecter  
Type SDF, up to 550 kV  
Maximum reliability and minimal  
maintenance

ВЯРНО С  
ОРИГИНАЛА



000026



Power and productivity  
for a better world™



**Horizontal Centre Break Disconnecter – Type SDF**  
 ABB disconnectors have been in service across the world for over two decades providing maintenance-free service with the highest records of operational reliability. The worldwide experience, often under severe climatic conditions, is applied for continual product improvement.

A mechanical device for providing isolation of power equipment from the network, a disconnecter is suitable for switching very small currents or where no significant change in voltage occurs across the terminals. The option of earthing sections of power systems can be made available by providing each disconnecter pole with one or two earthing switches.

The horizontal center break disconnecters type SDF are available for rated voltages up to 550kV.

### Regulations

The SDF disconnecters are designed as per IEC 62271-102 and IEC 62271-1 standards. Other international regulations can be met on request.

Type tests on the disconnecters are carried out by accredited testing laboratories in accordance with the latest regulations. Comprehensive electrical and mechanical routine tests are carried out on the poles and operating mechanism of each disconnecter ensuring world class quality.

### Minimized contact resistance

The current carrying aluminum conductors are welded to minimize joint resistance.

No external springs in contact fingers for maximum reliability

The contact fingers of the moving contacts of disconnecter type SDF are designed from special conducting material and without external springs for increased reliability.

### Easy and quick erection

The current carrying conductors and rotary pedestals are designed for easy adjusting and alignment.

Low friction design for smooth operation Maintenance-free linkages with stainless steel rod-end bearings require less drive power for operation and provide smooth motion transmission without any disturbance in the settings.

Dead center interlocking for reliability under extreme conditions

The dead center interlocking of operating mechanisms ensures there are no inadvertent changes in the open or close switching position even under extreme external conditions such as storms, earthquakes etc. or close switching position even under extreme external conditions such as storms, earthquakes etc.

### Superior design of mechanical interlock

The mechanical interlock between the earth switch and main blade is designed such that there is no scope for malfunction.

### Ice breaking capacity

The disconnectors are capable of operating under severe ice conditions.

### Strong rotary pedestals

This ensures that the deflection remains unchanged at high static mechanical loads.


Suitable for wide range of environmental conditions The disconnectors can operate in a wide range of temperatures as well as under polluted environmental conditions.

### Minimal maintenance

Superior material and lubricant used in the encapsulation of the pedestals and rotary terminal pads makes the disconnectors practically maintenance-free.

Design based on cutting-edge technology and experience The horizontal center break disconnecters type SDF consist of a steel base frame with two rotary pedestals, insulators, current carrying conductors (current path) and driving mechanisms. Steel components are hot dip galvanized to protect against atmospheric influences.

Each of the three phases of the disconnecter consists of two insulators mounted on maintenance free, sealed rotary pedestals which are carried by the steel base frame. The support post insulators carry the current paths consisting of two halves, with finger contacts and fist contacts. The current transfer takes place at the rotary heads of the two current paths via tulip-type contact fingers. The rotary heads can be turned 360° and therefore the installation of a pipe connection or the straining of connection cable is possible in any direction. Flat terminal plates can be provided as per DIN standard 46203, NEMA or any other standards.



Tulip contacts of 1600 A current path terminal head

Flat blade current path rated for 1600 A

Finger blade rated for 1600 A with earthing fixed contact mounted.



# Technical data


Voltage	72.5 kV*	125 kV	145 kV	170 kV	245 kV	300 kV	382 kV	420 kV	550 kV	
Type designation	SDF72.5	SDF123	SDF145	SDF170	SDF245	SDF300	SDF382	SDF420	SDF550	
Rated voltage (U <sub>n</sub> )	kV	72.5	123	145	170	245	300	382	420	
Rated frequency (f <sub>n</sub> )	Hz	50/60								
Rated normal current (I <sub>n</sub> )	A	1600, 2500, 3150, 4000**								
Rated short-withstand current, rated duration of short circuit (I <sub>sc</sub> , t <sub>sc</sub> )	kA, s	40/50/63, t***								
Rated peak withstand current (I <sub>p</sub> )	kA	2.5x I <sub>n</sub> (for 60 Hz) / 2.8x I <sub>n</sub> (for 60 Hz)								
Basic insulation level	kVp	2.5x I <sub>n</sub> (for 60 Hz) / 2.8x I <sub>n</sub> (for 60 Hz)								
Power frequency withstand voltage for 1 minute	kV	140	230	275	325	480	380	450	520	27
To earth and between poles	kV	160	265	315	375	530	435	520	610	315
Across the isolating distance										
Lightning impulse withstand voltage	kVp	325	550	650	750	1050	1050	1175	1425	650
To earth and between poles	kVp	375	650	750	880	1200	1050(+170)	1175(+205)	1425(+240)	750
Across the isolating distance										
Switching impulse withstand voltage	kVp	-	-	-	-	-	850	950	1050	1175
To earth and between poles	kVp	-	-	-	-	-	700(+245)	800(+285)	900(+325)	900(+450)
Across the isolating distance										

\* 35 kV on demand  
 \*\* Higher currents on demand  
 \*\*\* 3s for 40 kA

# Mode of operation

The disconnect and earthing switch are operated via independent operating mechanisms. The operating energy from the operating mechanism of the disconnecter is transmitted to one of the rotary pedestals of one phase. A diagonal rod connects both the rotary pedestals of each column ensuring simultaneous operation of both columns. The three phases of the disconnecter are connected by gang operating linkages for three phase operation. During opening and closing operation both the current paths rotate through an angle of 90°. The current paths will be at right angles to the base frame in open position.


**Operating mechanism**  
 All disconnecters can be supplied by manual or motor operated mechanism, as required by the customer. Each three-pole disconnect or earthing switch group requires only one operating mechanism. The coupling rods between the individual poles can be continuously adapted. Operating mechanisms contain auxiliary switches for control and signaling as well as provisions for electrical interlocks.



Linkages with spherical bearings

Three phase operation is conducted via mechanical or electrical gang operation. For maximum reliability the main contacts of the disconnecter and earthing switch pass through the dead center positions shortly before they reach the end positions. This prevents accidental opening or closing of the units due to external influences (e.g. short-circuits, storm, earthquake).


**Interlocks**  
 The disconnect and earthing switch (when supplied) are mechanically interlocked. In operating mechanisms a blocking magnet can be installed as an additional interlocking facility, which in disconnected condition, makes operation of the operating mechanism impossible.




Bearing on frame assembly

**Earthing switch unit**  
 The earthing switch unit, an optional assembly, consists of a hinged earthing switch fixed at the base frame. The unit can be mounted on either of the contact sides or on both sides as required.

In case of the earthing switch, the operating energy is transmitted to the earthing switch shaft. The tubular contact arm swings upwards when the unit is closing.



ВЯРНО С  
 СРТИГАНАТА



000023




# Easy installation

The disconnectors are delivered in following assemblies - lower part with rotary pedestals and diagonal rod, current path halves, support insulators and operating mechanism. As all mechanical adjustments are carried out in the factory, only mounting of the assemblies, installation of the coupling rods between the poles, connection of the high-tension leads and


the electrical connection leading to the operating mechanisms is required at the site.

Stud bolts are provided to compensate rapidly and exactly any inaccuracies in insulator position caused due to tensile forces.



Earthing switch contact side

Earthing switch finger side




Main dimensions as in drawing (mm)


	SDF27.5	SDF123	SDF145	SDF170	SDF245	SDF300	SDF362	SDF420	SDF550
A Support insulator distance	1000	1400	1650	1830	2620	2820	3200	3800	4200
B Base frame length	1300	1300	1950	2130	2920	2920	3500	4036	4466
C Disconnecter height	1600 A	1325	1775	2055	2255	2855	3205	3255	-
	2500 A	1375	1825	2105	2305	2905	3255	3255	4090
	3150 A	1425	1875	2155	2355	2955	3305	3305	4140
	4000 A	1425	1875	2155	2355	2955	3305	3305	4140
D Support insulator height	770	1220	1500	1700	2300	2650	2850	3350	4000
E Disconnecter width (open)	560	760	925	1080	1370	1370	1725	2100	2380
F Isolating distance	800	1200	1450	1630	2420	2300	2700	3385	3810
G Length of earthing switch segment	450	450	450	450	450	450	450	1050	1050

Type	Installation (with or without earthing switch)	In series Pmin(mm)	In parallel Pmin(mm)
SDF27.5		1790	1420
SDF123		2700	1970
SDF145		3150	2390
SDF170		3530	2640
SDF245		4920	3620
SDF300		5350	4070
SDF360		6925	4755
SDF420		On request	
SDF550		On request	

Series Installation



Parallel Installation



## Contact us




ABB Bulgaria  
High Voltage products  
32, Nikola Petkov Str, 5400,  
Sevlievo, Bulgaria  
Phone: +359-675-33630  
Email: [office@bg.abb.com](mailto:office@bg.abb.com)

[www.abb.com/highvoltage](http://www.abb.com/highvoltage)

Note: ABB is working continuously to improve the products. We therefore reserve the right to change designs, dimensions and data without prior notice.


Publcon1HYD0000a4E Rev.B 2012 0412 Horizontal center break disconnectors Type SDF up to 550 © Copyright 2012 ABB. All rights reserved.



Техническо описание на разединител с централно разделяне и един заземителен нож 110kV, за монтиране на открито тип SDF123 E1 производство на АББ България ЕООД – бранч Севлиево.

	Характеристика	Минимални технически изисквания	
1.	Брой на полюсите (фазите)	3	3
2.	Място на експлоатация	За монтиране на открито	За монтиране на открито
3.	Обявени изолационни разстояния:		
-	между осите на полюсите (фазите)	$\geq 1000 \text{ mm}$	$\geq 1000 \text{ mm}$
4.	Главна контактна система:		
-	тип	С централно разединяване	$\geq 1000 \text{ mm}$
-	материал на клемовите съединения за свързване към външната верига	Мед или алуминий с подходящо покритие непредизвикващо електрохимична корозия	Cu+Ag – main contacts; Cu- ES contacts
-	време за (включване/изключване)	$\leq (10/10) \text{ s}$	$\leq 7 \text{ s}$
5.	Заземителни ножове:	един комплект	един комплект
-	движение	Вертикално	Вертикално
-	оцветяване	Тип зebra – бяло (RAL 9016) и червено (RAL 3020) или еквивалентно/и (през 100 mm)	Тип зebra – бяло (RAL 9016) и червено (RAL 3020) или еквивалентно/и (през 100 mm)
6.	Тип на изолаторите	Порцелан/полимер	Порцелан С6
7.	Блокировки	Механична, електрическа	Механична, електрическа
8.	Задвижване:		
-	вид	Моторно	Моторно
-	номинално напрежение на електродвигателя	220 V DC $\pm$ 20 %	220 V DC -20/+20% according to IEC
9.	Статични натоварвания		
-	хоризонтално	$\geq 500 \text{ N}$	$\geq 500 \text{ N}$
-	вертикално	$\geq 1000 \text{ N}$	$\geq 1000 \text{ N}$
-	комбинирано	$\geq 750 \text{ N}$	$\geq 750 \text{ N}$
10.	Динамично натоварване	$\geq 2000 \text{ N}$	$\geq 2000 \text{ N}$
11.	Клас на механична комутационна възможност	$\geq \text{M1}$	
12.	Сеизмична устойчивост	$\geq 0,3 \text{ g}$	$\geq 0,3 \text{ g}$
13.	Оцветяване	RAL 6021 или еквивалентно/и	RAL 6021
14.	Период на необслужваемост на повърхностите на всички метални части	$\geq 15 \text{ год.}$	$\geq 15 \text{ год.}$
15.	Табелка за техническите характеристики и надписи	Съгласно БДС EN 62271-102 или еквивалентно/и на български език	Съгласно БДС EN 62271-102 на български език
16.	Допълнителни аксесоари		
17.	Манивела за ръчно включване/изключване	$\geq 2 \text{ бр.}$	2 бр.


ВЯРНО С  
ОРИГИНАЛА





0300331

№	Параметър	Минимални технически изисквания	
1.	Обявено напрежение ( $U_r$ )	123 kV	123 kV
2.	Обявено изолационно ниво между части под напрежение и земя		
-	Обявено издържано мълниев импулсно напрежение ( $U_p$ ) (върхова стойност): спрямо земя, между полюси и между отворени контакти	550 kV	550 kV
-	Обявено краткотрайно (1 min) издържано напрежение с промишлена честота (50 Hz) ( $U_d$ ) (ефективна стойност): спрямо земя, между полюси и между отворени контакти	230 kV	230 kV
3.	Обявено изолационно ниво между разделящо разстояние		
-	Обявено издържано мълниев импулсно напрежение ( $U_p$ ) (върхова стойност): спрямо земя, между полюси и между отворени контакти	550 kV	550 kV
-	Обявено краткотрайно (1 min) издържано напрежение с промишлена честота (50 Hz) ( $U_d$ ) (ефективна стойност): спрямо земя, между полюси и между отворени контакти	230 kV	230 kV
4.	Обявена честота ( $f_r$ )	50 Hz	50 Hz
5.	Обявени стойности на тока		
-	Обявен номинален ток	1250 A	1250 A (up to 1600A)
-	Обявен краткотраен издържан ток ( $I_k$ )	$\geq 31.5$ kA	$\geq 31.5$ kA up to 40kA)
-	Обявен върхов издържан ток ( $I_p$ )	$\geq 78.8$ kA	$\geq 78.8$ kA (up to 100kA)
6.	Обявена продължителност на късо съединение ( $t_k$ )	$\geq 1$ s	$\geq 1$ s (up to 3s)
7.	Способност за изключване на:		
-	Индуктивен ток	$\geq 3$ A	3 A
-	Капацитивен ток	$\geq 1$ A	2 A
8.	Ниво на радио смущения	$\leq 2500$ $\mu$ V	$\leq 2500$ $\mu$ V
9.	Път на пропъзляване по повърхността на изолятора	$\geq 31$ mm/kV	31 mm/kV


ВЪРНО С  
ОРИГИНАЛА




000032



ВЯРНО С  
ОРИГИНАЛА



000033



**Mounting Dimensions 1 phase**


- ① Operating mechanism of Disconnector
  - ② Operating mechanism of Earthing switch
- Operating mechanism is to be mounted at either phase a, b or c

Rated Current	Terminal pad	A	B	C	D	E
1600A	DIN	1790	280	14	50	-
	NEMA			14.3	44.4	-
	GOST			14	45	-
2500A	DIN	1840	330	14	50	50
	NEMA			14.3	44.4	55.6

Техническо описание на разединител с централно разделяне и два заземителни ножа 110kV, за монтиране на открито тип SDF123 E2 производство на АББ България ЕООД – бранч Севлиево.

	Характеристика	Минимални технически изисквания	
18.	Брой на полюсите (фазите)	3	3
19.	Място на експлоатация	За монтиране на открито	За монтиране на открито
20.	Обявени изолационни разстояния:		
-	между осите на полюсите (фазите)	≥ 1000 mm	≥ 1000 mm

ВЕРНО С  
ОРИГИНАЛА




030034

	Характеристика	Минимални технически изисквания	
21.	Главна контактна система:		
-	тип	С централно разединяване	$\geq 1000$ mm
-	материал на клемовите съединения за свързване към външната верига	Мед или алуминий с подходящо покритие непродизвикващо електрохимична корозия	Cu+Ag – main contacts; Cu- ES contacts
-	време за (включване/изключване)	$\leq (10/10)$ s	$\leq 7$ s
22.	Заземителни ножове:	два комплект	два комплект
-	движение	Вертикално	Вертикално
-	оцветяване	Тип зебра – бяло (RAL 9016) и червено (RAL 3020) или еквивалентно/и (през 100 mm)	Тип зебра – бяло (RAL 9016) и червено (RAL 3020) или еквивалентно/и (през 100 mm)
23.	Тип на изолаторите	Порцелан/полимер	Порцелан С6
24.	Блокировки	Механична, електрическа	Механична, електрическа
25.	Задвижване		
-	вид	Моторно	Моторно
-	номинално напрежение на електродвигателя	220 V DC $\pm$ 20 %	220 V DC -20/+20% according to IEC
26.	Статични натоварвания		
-	хоризонтално	$\geq 500$ N	$\geq 500$ N
-	вертикално	$\geq 1000$ N	$\geq 1000$ N
-	комбинирано	$\geq 750$ N	$\geq 750$ N
27.	Динамично натоварване	$\geq 2000$ N	$\geq 2000$ N
28.	Клас на механична комутационна възможност	$\geq$ M1	
29.	Сеизмична устойчивост	$\geq 0,3$ g	$\geq 0,3$ g
30.	Оцветяване	RAL 6021 или еквивалентно/и	RAL 6021
31.	Период на необслужваемост на повърхностите на всички метални части	$\geq 15$ год.	$\geq 15$ год.
32.	Табелка за техническите характеристики и надписи	Съгласно БДС EN 62271-102 или еквивалентно/и на български език	Съгласно БДС EN 62271-102 на български език
33.	Допълнителни аксесоари		
34.	Манивела за ръчно включване/изключване	$\geq 2$ бр.	2 бр.

№	Параметър	Минимални технически изисквания	
10.	Обявено напрежение ( $U_r$ )	123 kV	123 kV
11.	Обявено изолационно ниво между части под напрежение и земя:		
-	Обявено издържано мълниеве импулсно напрежение ( $U_p$ ) (върхова стойност): спрямо земя, между полюси и между отворени контакти	550 kV	550 kV
-	Обявено краткотрайно (1 min) издържано напрежение с промишлена честота (50 Hz) ( $U_d$ ) (ефективна стойност): спрямо земя, между полюси и между отворени контакти	230 kV	230 kV
12.	Обявено изолационно ниво между разделящо разстояние		
-	Обявено издържано мълниеве импулсно напрежение ( $U_p$ ) (върхова стойност): спрямо земя, между полюси и между отворени контакти	550 kV	550 kV


ВАРНО С  
СЕРТИФИКАТА



030035

L 20


№	Параметър	Минимални технически изисквания	
-	Обявено краткотрайно (1 min) издържано напрежение с промишлена честота (50 Hz) ( $U_d$ ) (ефективна стойност): спрямо земя, между полюси и между отворени контакти	230 kV	230 kV
13.	Обявена честота ( $f_r$ )	50 Hz	50 Hz
14.	Обявени стойности на тока		
-	Обявен номинален ток	1250 A	1250 A (up to 1600A)
-	Обявен краткотраен издържан ток ( $I_k$ )	$\geq 31.5$ kA	$\geq 31.5$ kA up to 40kA
-	Обявен върхов издържан ток ( $I_p$ )	$\geq 78.8$ kA	$\geq 78.8$ kA (up to 100kA)
15.	Обявена продължителност на късо съединение ( $t_k$ )	$\geq 1$ s	$\geq 1$ s (up to 3s)
16.	Способност за изключване на:		
-	Индуктивен ток	$\geq 3$ A	3 A
-	Капацитивен ток	$\geq 1$ A	2 A
17.	Ниво на радио смущения	$\leq 2500$ $\mu$ V	$\leq 2500$ $\mu$ V
18.	Път на пропълзяване по повърхността на изолятора	$\geq 31$ mm/kV	31 mm/kV



D

H


ВЪВЕНО С  
ОРИГИНАЛА



000036




*See*




*[Handwritten signature]*

ВЯРНО С  
ОРИГИНАЛА



*[Handwritten signature]*

000037



Rated voltage (kV)	123
Rated current (A)	1600 2500
Short-time withstand current (kA/s)	up 40/3
Weight of disconnector without insulator and drive(1 Phase) (kg)	105 115
Weight of earthing switch (1 Phase) (kg)	40 40

Minimum falling load of insulator (kN)	4	6
Mechanical terminal load:		
Static+dynamic (kN)	3	4,5
Static portion load (kN)	1,2	1,5
Weight of insulator(approx.) (kg)	50	60


Mounting Dimensions 1 phase

- ① Operating mechanism of Disconnector
  - ② Operating mechanism of Earthing switch
- Operating mechanism is to be mounted at either phase a, b or c

Rated Current	Terminal pad	A	B	C	D	E
1600A	DIN	1790	280	14	50	-
	NEMA			14.3	44.4	-
	GOST			14	45	-
2500A	DIN	1840	330	14	50	50
	NEMA			14.3	44.4	55.6

H - vary with structure height - (Hmin=2400 mm)  
H1 - standard height 1350 mm.

КОПИО С  
ОРИГИНАЛА



000038



## Обобщение на типови изпитания за разединител тип SDF 123kV

Производител: АББ България, клон Севлиево  
Разединител тип: Разединител, тип Централно отваряне SDF 123 kV 1600 A EI

Спецификация:	Номинално напрежение:	123 kV
	Номинално импулсно напрежение:	
	-фаза към земя и между фазите;	550 kV peak
	-през изолационното разстояние.	630 kV peak
	Номинално напрежение с промишлена честота:	
	-фаза към земя и между фазите;	230 kV r.m.s.
	-през изолационното разстояние;	265 kV r.m.s.
	-в най-неблагоприятната позиция на земния нож.	142 kV r.m.s.
	Номинален ток:	1600 A
	Номинална честота:	50/60 Hz
	Номинален ток на късо съединение - главен нож:	
	-върхова стойност;	104 kA
	-ефективна стойност;	40 kA
	-продължителност на късото съединение.	3 sec
	Номинален ток на късо съединение – земен нож:	
	-върхова стойност;	104 kA
	-ефективна стойност;	40 kA
	-продължителност на късото съединение.	3 sec
	Ниво на радио-смущения	<2500 μV
	Максимална температура на околната среда	+50 °C

Приложените протоколи от изпитването, документират типови изпитания, извършени съгласно посочените по-долу стандарти:

Проведени тестове	Проведен тест съгласно:	Тестови протоколи	
		No.	Издател:
Измерване на съпротивление	IEC 62271-102 clause 6.4	12329	ICMET-Craiova
Типово изпитание - нагрев	IEC 62271-102 clause 6.5	12329	ICMET-Craiova
Номинален ток на късо съединение, максимален ток на късо съединение	IEC 62271-102 clause 6.6	12329	ICMET-Craiova
Импулсно напрежение	IEC 62271-102 clause 6.2	45229	ICMET-Craiova
Напрежение с промишлена честота	IEC 62271-102 clause 6.2.6	45229	ICMET-Craiova
Напрежение с промишлена честота, в най-неблагоприятната позиция на земния нож	IEC 62271-102 clause 4.2	45229	ICMET-Craiova
Ниво на радио-смущения	IEC 62271-102 clause 6.3	45229	ICMET-Craiova
Работа при максимална температура на околната среда	IEC 62271-102 clause 6.104.2	NR31-805T-1	URBAN-INCERC


ABB Bulgaria EOOD  
Main office:  
9 Hristofor Kolumb Blvd, fl.3  
1592 Sofia, Bulgaria  
Tel.: (+359 2) 8075500, 8075600, 8075700  
Fax: (+359 2) 8075599 (8,7,6)  
Web: www.abb.bg

UIC: 831133152  
VAT Nr.: BG 831133152  
Bank details:  
ING Bank, branch Sofia  
IBAN: BG131INGB91451000027317 (BGN)  
IBAN: EUR: BG60INGB91451400027317 (EUR)  
BIC: INGBBG33

Branch Sevlievo  
Production and office  
32, Nikola Petkov Str.  
5400 Sevlievo, Bulgaria  
Tel.: (+359 675) 39222  
Fax: (+359 675) 30043  
e-mail: abb.sevlievo-branch@bg.abb.com



ВЪРХО С  
ОРИГИНАЛА



000039



Str. Parteniului 161, 011162, Sector 2, Bucuresti, Tel: 021 621 27 40; Fax: 021 255 11 54; e-mail:urban-incerc@incerc.ro, urban@incerc.ro


**IASI Branch**  
 Laboratory for Climatic - Hygrothermal, Mechanical and Seismic Tests for Buildings, Installations and Equipment (IHS)  
 Address: Str. Prof. Aron Sesan, nr. 37, Iasi  
 1<sup>st</sup> degree laboratory certification no. 2972 / 18.12.2014 issued by I.S.C

INCERC  
 INCERCARE



SR EN ISO/IEC 17025:2005  
 CERTIFICAT DE ACREDITARE  
 II 300

APPROVED BY GENERAL MANAGER  
 INCDC - URBAN - INCERC  
 Associate Professors dr. arh. **Steluta Mitea**



**TEST REPORT NR 31-805T - 1 / 15.03.2016**  
 FOR CLIMATIC TEST ACCORDING TO EN 62271-102,  
 CLAUSE 6.104.2 - OPERATION AT MAXIMUM AMBIENT AIR TEMPERATURE (+50°C)

- Customer order/contract: 61/17.02.2016/ contract no.805T/2016
- Name of test object:  
 Three pole disconnector SDF 123kV 40kA 1600A with earthing switch operated by Motor Drive MD 60
- Customer name: NATIONAL INSTITUTE FOR RESEARCH, DEVELOPMENT AND TESTING IN ELECTRICAL ENGINEERING - ICMET Craiova  
 Customer address: B-dul Decebal no. 118A Craiova, Calea Bucuresti no. 144 Tel. 0351 404888 , 0351 404 889, Fax: 0351 404 890, 0251 415 482
- Manufacturer: ABB BULGARIA BRANCH SEVLIEVO BULGARIA  
 Manufacturer address: 32 N. PETROV STR. 5400 SEVLIEVO, Bulgaria
- Identification of the test specification or procedure:
  - EN 62271-102:2002 - High-voltage switchgear and controlgear. Part 102: High-voltage alternating current disconnectors and earthing switches, clause 6.104.2 - Operation at maximum ambient air temperature
  - PTE IHS - 19 / 12.08 - URBAN INCERC Iasi
- Description and identification of tested object:  
 Three pole Disconnector SDF 123/1600 with one Earthing Switch serial number 2GPA45040000654, operated by Motor Drive MD 60 serial number 2GPA45010023372, 2GPA45010023376
- Date when tested object was received: FVPP no. 24IHS from 22.02.2016 and expedition note ABB Bulgaria Branch Serievo / 19.02.2016 Laboratory code IHS 486/E1-02.16
- Test date: 22.02.2016 - 28.02.2016

- Description of sampling procedure: Sampling of the test object was performed by the customer at their own risk.
- Obtained results:  
 Equipment and materials used: clima5c room with thermal adjustment, 600m<sup>3</sup>

10.1. The resistance of the circuit:

Resistance of the circuit (µΩ) - measurement at 100A			
Resistance of the main circuit (µΩ)			
Moment of measurements	Pole A	Pole B	Pole C
Initial	60.7	51.1	50.3
final	54.5	53.7	51.3
Percentage Increase	4.97 %	4.84 %	1.95 %
Resistance of the earthing switch circuit (µΩ)			
Initial	64.3	60.9	62.8
final	67.9	64.5	68.7
Percentage Increase	5.30%	5.58%	6.69%

10.2. The drive time cycles of closing and opening of the contact of main circuit:

	Initial drive time of cycles Minimum Voltage - Normal temperature (s)	Drive time of cycles Maximum Voltage (s)	Drive time of cycles Minimum Voltage (s)	Final drive time of cycles Minimum Voltage - Normal temperature (s)
Cycles Open - Close	extreme positive + 50°C temperature			
	4.459	4.321	4.335	4.697
	4.461	4.330	4.334	4.659
	4.456	4.321	4.340	4.478
	4.453	Medium value - 4.324	Medium value - 4.335	4.504
Medium value	4.460			4.673
Percentage Increase:				
				1.8%
Cycles Close - open	extreme positive + 50°C temperature			
	4.378	4.253	4.318	4.380
	4.383	4.250	4.348	4.426
	4.371	4.252	4.354	4.408
	4.321	Medium value - 4.452	Medium value - 4.344	4.516
Medium value	4.376			4.512
4.380				4.448
Percentage Increase				
				1.63%

10.3. The drive time cycles of closing and opening of the contact of earthing switch circuit:

	Initial drive time of cycles Minimum Voltage - Normal temperature (s)	Drive time of cycles Maximum Voltage (s)	Drive time of cycles Minimum Voltage (s)	Final drive time of cycles Minimum Voltage - Normal temperature (s)
Cycles Open - Close	Extreme positive + 50°C temperature			
	4.487	4.404	4.355	4.613
	4.484	4.388	4.382	4.608
	4.476	4.389	4.389	4.615
	4.483	Medium value - 4.388	Medium value - 4.389	4.657
Medium value	4.480			4.605
Percentage Increase:				
				1.11%
Cycles Close - open	Extreme positive + 50°C temperature			
	4.059	3.958	3.942	4.049
	4.047	3.961	3.955	4.129
	4.051	3.959	3.967	4.131
	4.050	Medium value - 3.959	Medium value - 3.951	4.128
Medium value	4.039			4.120
4.049				4.111
Percentage Increase				
				1.76%


- Uncertainty of measurement: Was not requested by the customer.
- Opinions and Interpretations: \* Item 12 is not covered by the RENAR accreditation

Three pole Disconnector SDF 123/1600 with one Earthing Switch serial number 2GPA45040000654, operated by Motor Drive MD 60 serial number 2GPA45010023372, 2GPA45010023376  
**HAS FULFILLED THE TECHNICAL CONDITIONS REQUIRED FOR:**  
 • functioning to AT MAXIMUM AMBIENT AIR TEMPERATURE +50°C, according to EN 62271-102, clause 6.104.2. The equipment (the main circuits and earthing switch) may be maneuvered, performing the closed-open drive cycles imposed by the standard (three cycles close-open), by means of the motor drive mechanism. No malfunctions of the contact and drive elements, and support insulators, were detected, as well as no deformations or permanent blocking that might hinder the mechanical or electrical performance of the disconnector with earthing switch.

NOTES:

- The result of the test refers only to the tested object.
- The test report cannot be partially reproduced without the approval of the laboratory which performed the test
- The test report is accompanied by Annex 1 to Test Report No. 31-805T-1/15.03.2016, 6 pages.

Approved by Branch Manager  
 eng. Constantin Miron, PhD



Prepared by Contract holder  
 eng. Adrian Ciobanu, PhD

Verified by Head of HT Laboratory  
 eng. Livia Miron, PhD

*Livia Miron*

BRB INCDC  
 OPTICIANA



030040

**ANNEX TO TEST REPORT No. 31-805T -1/ 15.03.2016**

1. PRODUCT PRESENTATION

Three pole Disconnector SDF 123/1600 with one Earthing Switch serial number 2GPA45040000654, operated by Motor Drive MD 60 serial number 2GPA45010023372, 2GPA45010023376 has been assembled in the climatic chamber of the Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of the National Institute for Research and Development in Constructions, Urban Planning and Sustainable Territorial Development "URBAN - INCERC", Iasi Branch and has been verified by experimental means, through tests on its functional behavior when subjected to severe climatic conditions:

- at maximum ambient air temperature + 50°C temperature, according to EN 62271-102, clause 6.104.2.

1.1 Product Identification (components)

- Three pole Disconnector with Earthing Switch SDF 123/1600, operated by Motor Drive MD 60
- supporting meta5c frame.

Producer: ABB BULGARIA BRANCH SEVLIEVO BULGARIA, 32 N. PETROV STR. 5400 SEVLIEVO, Bulgaria

1.2 Installation in the climatic chamber of the Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of URBAN - INCERC Iasi Branch

Three pole Disconnector SDF 123/1600 with one Earthing Switch serial number 2GPA45040000654, operated by Motor Drive MD 60 serial number 2GPA45010023372, 2GPA45010023376 has been assembled for tests in the climatic chamber of the Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of the "URBAN - INCERC", Iasi Branch, according to the reference technical documentation.

During installation, the following has been verified:

- Overall dimensions;
- dimensions and types of the component subsystems;
- elevations at which the subsystems may be mounted;
- product subassemblies;
- product integrity and recording of possible fissures, deformations or other damages caused by transportation, manipulation, and installation, in order to differentiate between original defects and the ones that have appeared following tests.

The installation and mounting of the Three pole Disconnector SDF 123/1600 with one Earthing Switch serial number 2GPA45040000654, operated by Motor Drive MD 60 serial number 2GPA45010023372, 2GPA45010023376 in the climatic chamber has been performed according to the normal installation procedures specified by the producers (according to 10142), and electrical connection diagram for Motor Drive MD 60 (2GPA4543235-FM), fig. 1.1a, 1.2 and picture no 1)  
 The pictures no. 2 through 6 show Three pole Disconnector SDF 123/1600 with one Earthing Switch serial number 2GPA45040000654, operated by Motor Drive MD 60 serial number 2GPA45010023372, 2GPA45010023376 assembled in the climatic chamber and during various stages of the test performed.




Fig. 1.1 - Three pole Disconnector with one Earthing Switch SDF 123/1600, operated by Motor Drive MD 50







Fig. 1.2- Electrical connection diagram - Motor drive MD 50




Picture no. 1 - Installation details




Picture no. 2 - The disconnector in open position at +50°C



Picture no. 3,4 - The disconnector in close position at +50°C



Picture 5 - The controls of close position of circuit of the disconnector.



2. Installation conditions:

The device has been assembled according to the details from draw no. 10142, and electrical connection diagram for Motor drive MD 50 (200A/543235-FM), fig. 1.1, 1.2 and picture no.1, in climatic chamber of the Research and Hydrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of "URBAN - INCERC", Iasi Branch, which has the following characteristics:

- chamber volume 600 m<sup>3</sup>;
- heating capacity 11500 W;
- available temperatures: - 60°C...+70°C;
- ice layer of 0...20 mm measured on a witness tube.

The device has been connected to its own drive mechanism.

ВЪРНО С  
ОРИГИНАЛА

Степа Зарова  
Степа Зарова

000041

3. Measuring equipment and technical means:

The climatic parameters have been measured in the following way:  
 - Digital thermohygrograph KIMO Instruments, CE METROMAT no. 2372 - 09.14/18.09.2014;  
 - Digital thermometer Thermo Loger R Digi.Sense - 50... +100°C, CE report INM BC-308-1165/2013  
 - Micro - ohmmetru RIKO 500; 20pΩ /1mΩ /100mΩ/200mΩ, CE report INM 02-01-368/2013  
 - Programmable counter PTE-30-CH, 0 + 99 999 s, CE BC -304-2965/2012  
 - Regulation of the temperature in the climatic chamber - automatically by means of Dixell temperature and humidity regulators, Btzer compressor group and Dixell system for the monitoring and automatic recording of parameters XWEB 500, Calibration Report INM BC - 308-1045/2011;

4. Functional requirements during and after the climatic test. Acceptance criteria

- Throughout the climatic test, the disconnector with earthing switch has been fulfilling the conditions in fig.1.1 as well as the specifications at point 2, with no voltage applied to its terminals.  
 The disconnector with earthing switch fulfill the acceptance criteria of the climatic sequence imposed for maximum ambient air temperature +50°C, according to EN 62271-102, clause 6.104.2, if:
- 1) prior to the operation under extreme positive +50°C temperature conditions, the disconnector and the earthing switch fulfill the routine mechanical operating test according to EN 62271-102, clause 6.103.3 - g;
  - 2) it is possible to perform the complete drive cycles of closing and opening of the disconnector and the earthing switch, imposed by the standard (complete three operating cycles, at a minimum and maximum supply energy), using the equipment's own drive mechanism powered by maximum and minimum voltage, respectively;
  - 3) no sudden maneuvers are performed on the disconnector's and the earthing switch's contacts and the continuity of the circuit is maintained during the test, in the closed and open positions of the disconnector and the earthing switch;
  - 4) no damages are inflicted which can hinder the mechanical or electrical performance of the disconnector and the earthing switch;
  - 5) the position of the contacts is maintained - closed/open;
  - 6) the functioning of the kinematic system is maintained;
  - 7) the dielectric properties of the components of the drive mechanism's electric diagram are maintained

5. Conditioning of the equipment

The device has been kept at the parameters of the environment in the climatic chamber (cca 20°C) for a minimum of 24 hours. During this period, the routine mechanical operating test has been performed.

6. Test phases


Test phases for severe climatic conditions to extreme positive +50°C temperature, according to EN 62271-102, clause 6.104.2- according to the table and the diagram no. 2 below

Phases	Initial	Heating	Maintenance	Steady-state regime	C-O Maneuvers	Reversion	Final
Nr.	1	2	3	4	5	6	7
T <sub>amb</sub>	+17,5	+50	+50	+51	+50	+50	+22
ΔT <sub>st</sub>	±1,4		±2,1	±2,1	±2,1		
ΔT/Δt		+5,7			8,7		
φ <sub>rel</sub>	62		31	31	31		55
Δt		7	3	4	1	4	

Legend:

T<sub>amb</sub> - average temperature in the climatic chamber  
 ΔT<sub>st</sub> - maximum deviation of temperature on the chamber's height  
 ΔT/Δt - speed of temperature variation (°C/h)  
 φ<sub>rel</sub> - relative humidity of the air (%)  
 Δt - phase duration (h)

Diagram of the climatic test under the circumstances of the extreme positive +50°C temperature, according to EN 62271-102, clause 6.104.2.



Phase 1 - initial phase of maintaining the equipment at a temperature of 18 °C ± 1°C, for cca 6 hours. During this period, the routine mechanical operating test has been performed.  
 Phase 2, 3 - heating the climatic chamber up to +50 °C ± 2,1°C cca 7 hours and keeping of the equipment inside for at least 2 hours.  
 Phase 4 - steady-state regime at an extreme positive temperature of +50°C according to EN 62271-102, clause 6.104.2, cca 4 hours  
 Phase 5  
 a. Performing the complete drive cycles of closing and opening of the main circuit of disconnector and the earthing switch, imposed by the standard, using the equipment's own drive mechanism powered by maximum and minimum voltage, respectively, at the same extreme positive temperature of +50°C ± 2,1°C, cca 1 hour;  
 b. Verifying the values of the drive time.  
 Phase 6 - Reversion of the chamber temperature to 22 °C for cca 4 hours and verification the contact resistance of main circuit and the values of the drive time

Three pole Disconnector SDF 123/1600 with one Earthing Switch serial number 2GPA4504000554, operated by Motor Drive MD 60 serial number 2GPA45010023372, 2GPA45010023376.

Experimental results  
 In order to verify the integrity of the equipments before the beginning of the climatic test, we have performed a general inspection to confirm that the equipment had been assembled according to the requirements of the company standard (positions, dimensions, connections, gauging) and that no damage had been caused during assembling (insulator breaking, remaining deformations), and to ensure a complete maneuvering Closed - Open cycle.  
 Throughout the experimental program, we have observed the general state, structural integrity and functional behavior of the products in order to be able to identify possible defects or malfunctions. Consequently, at the end of each experimental phase, we have inspected the equipment's state and we have performed the necessary maneuvers according to the verification procedures. Our observations of the general state, structural integrity and functional behavior of the products

during the program of experimental testing under extreme positive temperature of +50°C, prove that the device fulfills the acceptance criteria according to EN 62271-102, clause 6.104.2, as follows:

- 1) we have been able to perform the complete three drive cycles of closing and opening of the disconnector with earthing switch imposed by the standard, using the equipment's own drive mechanism powered by maximum and minimum voltage, respectively;  
 Unominal = 110VDC  
 Umax = Unom + 15% = 127VDC  
 Umin = Unom - 20% = 88VDC
- 2) the drive time is within the limits value 4.3 - 4.8 s;
- 3) no sudden maneuvers were performed on the earthing switch's contacts and the continuity of the circuit was maintained during the test, in the closed and open positions of the disconnector with earthing switch;
- 4) no damages were inflicted which could have hindered the mechanical or electrical performance of the disconnector with earthing switch;
- 5) the position of the contacts was maintained - closed/open;
- 6) the functioning of the kinematic system was maintained;
- 7) the dielectric properties of the components of the drive mechanism's electric diagram were maintained.
- 8) The value of contact resistance - The increased resistance after the environmental test is in keeping with the max limit of 20% imposed by SR EN 62271-102, clause 6.102.3.2

All test phases have been carried out in the presence and with the technical assistance of the producer ABB BULGARIA Branch Sevişev and ICWET Craiova.

Laboratory for Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment, Iasi Branch, Romania


Head of laboratory: eng Livia Miron, PhD

Test responsible person: eng. Adrian Alexandru Ciobanu, PhD

Chief of test division: eng Livia Miron, PhD

Laboratory A-Q responsible person: eng Alina Cobzaru

БЪРНО С  
ОПТИМАЛА



000042



NATIONAL INSTITUTE FOR RESEARCH-DEVELOPMENT  
AND TESTING IN ELECTRICAL ENGINEERING  
**ICMET CRAIOVA**  
**HIGH POWER DIVISION**  
**HIGH POWER TESTING LABORATORY FOR**  
**ELECTRICAL EQUIPMENT (HPL)**  
"Ovidiu Rarincea"  
200746 CRAIOVA, Blvd. DECEBAL, No.118A, ROMANIA  
Mandatory certificate: J16/012/1999, VAT number RO3871599  
Phone: (351) 402 427; Fax: (351) 404 890;  
E-mail: hpl@icmet.ro, hpl@icmet.ro



Copy 2/4

**TEST REPORT**  
**No. 12329**

**CUSTOMER:** ABB Bulgaria EOOD - Branch Sevlivo  
32, Nikola Petkov Str., 5400 Sevlivo - Bulgaria

**MANUFACTURER:** ABB Bulgaria EOOD - Branch Sevlivo  
32, Nikola Petkov Str., 5400 Sevlivo - Bulgaria

**TESTED PRODUCT:** 123 kV, 1600 A, 40 kA/3 s Three-pole disconnector type SDF  
with earthing switch

**REFERENCE STANDARD:** IEC 62271-102:2013

**TEST PERFORMED:** Measurement of the resistance  
Temperature-rise test  
Short-time withstand current and peak withstand current test


**TEST DATE:** 01-02.03.2016

**TEST RESULT:** Passed the tests

Test Report has 15 pages and it is edited in 4 copies from which copy 1 for laboratory and copies 2, 3 and 4 for customer.

**TECHNICAL MANAGER OF HIGH POWER LABORATORY:**  
Eng. Ilie Stoian

**HEAD OF HIGH POWER LABORATORY:**  
Phys. Daniel Truta



**DATE OF ISSUE:** 26.04.2016

1. Results refer to test product only.  
2. Publication or reproduction of the contents of this report in any other form without the complete photocopying is not allowed  
without written approval of Division in which laboratory belongs to.  
© ICMET Craiova 2016/BC+IM+TD  
Code: F-03.19.04 eng

TEST REPORT No. 12329

Copy 2/4  
Page 2

Content	Page
1. Identification of the test product	3
2. Technical characteristics established by producer	3
3. Tests program	3
4. Responsible for tests	3
5. Present at the tests	3
6. Test report documentation	3
7. Measurement of the resistance	4
8. Temperature-rise test	4
9. Short-time withstand current and peak withstand current test	6
10. Test result	8
Photos	9
Drawings	11
Oscillograms	12

© ICMET Craiova 2016/BC+IM+TD  
Code: F-03.19.04 eng

TEST REPORT No. 12329

Copy 2/4  
Page 3

**1. IDENTIFICATION OF APPARATUS**

	Disconnector	Main mechanism	ES mechanism
Type	SDF 123/1600	MD 50	MD 50
Serial number/Year	2GPA45040000654	2GPA45010023375	2GPA45010023372
Contract No.	705.2 / 682 / 22.01.2016		
Product receiving date	01.03.2016		
Product condition at receiving	New		
Drawings	See page 11		

The manufacturer confirms that the test object has been manufactured in compliance with these drawings that were retained in HPL archive.  
This test report contains only representative drawings chosen by HPL.

**2. TECHNICAL CHARACTERISTICS ESTABLISHED BY PRODUCER**

	Disconnector	Earthing switch
Rated voltage:	123 kV	123 kV
Rated normal current:	1600 A	-
Rated frequency:	50 Hz	50 Hz
Rated short-time withstand current:		
- peak value:	104 kA	104 kA
- r.m.s. value:	40 kA	40 kA
Rated duration of short-circuit:	3 s	3 s

**3. TESTS PROGRAM**

3.1. Measurement of the resistance according to clause 6.4.  
3.2. Temperature-rise test at I = 1600 A, f = 50 Hz on one pole of the disconnector, according to clause 6.5.  
3.3. Short-time withstand current and peak withstand current test:  
3.3.1. Single-phase short-time withstand current and peak withstand current test on main circuit at parameters: I<sub>p</sub> = 104 kA, I<sub>k</sub> = 40 kA, t<sub>k</sub> = 3 s, according to clause 6.6.  
Supply was made with 80x10 mm cross section aluminium tube and short-circuit was made with 80 mm diameter aluminium tube and disconnector in close position.  
The test circuit is presented in figure 3.  
3.3.2. Single-phase short-time withstand current and peak withstand current test on earthing switch at the parameters I<sub>p</sub> = 104 kA, I<sub>k</sub> = 40 kA, t<sub>k</sub> = 3 s, according to clause 6.6.  
Supply was made with 80x10 mm cross section aluminium tube and by 2x340 mm<sup>2</sup> copper cables with earthing switch in close position as in test circuit presented in figure 4.

NOTE: Short-time withstand current and peak withstand current tests are performed with a current factor of 2.6.

**4. RESPONSIBLE FOR TESTS:** Eng. Catalin Dobre

**5. PRESENT AT THE TESTS:** Eng. Delyan Stoev and Eng. Plamen Sharkov  
from ABB Bulgaria

**6. TEST REPORT DOCUMENTATION:** Oscillograms 4; Tables 4;  
Photos 6; Drawings 1.

© ICMET Craiova 2016/BC+IM+TD  
Code: F-03.19.04 eng

ICMET CRAIOVA  
OPINTUNAJA

TEST REPORT No. 12329

Copy 2/4  
Page 4

**7. MEASUREMENT OF THE RESISTANCE**

The resistance of the main circuit before and after test was measured with digital micro ohmmeter type OMICRON CPM500. The results are presented in table 1.

	Before test (R1)	After test (R2)	Remarks
R [μΩ]	71.4	70.2	Temperature-rise test
ΔR % = (R2-R1)/R1x100	-	-1.7	
R [μΩ]	69.1	68.8	Short-time withstand current and peak withstand current test
ΔR % = (R2-R1)/R1x100	-	-0.4	

Measurements were performed with extended uncertainty of 2.2% for resistances and the confidence level P = 93%.

**8. TEMPERATURE-RISE TEST**

**8.1. Data of testing and measuring circuit**

Data of testing and measuring circuit are presented in Fig. 1.




Fig. 1 - Test diagram for current paths temperature-rise test

- S - Power supply
- IUT - Low voltage circuit breaker
- AT - Single-phase autotransformer 230 V; 70 kVA.
- TC - Current transformer
- PA - Power analyzer
- SAT - Automatic system type Keithley for temperatures measurements with thermocouples
- TO - Tested object

**8.2. Values obtained at test**

Temperature-rise test was performed by passing a current of 1600 A / 50 Hz through the main circuit until the temperature variation did not exceed 1°K per hour.  
Supply was made with flexible copper cables of 1000 mm<sup>2</sup> cross-section.  
Temperatures were measured using the temperatures measurement computerized system Keithley Multimeter Integra 2700 with type J thermocouple.  
Environment temperature was measured in three points equally distributed around Disconnector, at half height and approximately 1 m distance of it.

© ICMET Craiova 2016/BC+IM+TD  
Code: F-03.19.04 eng

030043




Fig. 2 - Location of the temperature-rise test measuring points

Values of the measured temperatures are presented in table 2.

No. of MP	Location of the measuring points MP	Nature of the part	Material	Maxin value of temperature rise [°C]	Final temperature [°C]	Temperature rise [K]
MP1	Input terminal	Connection	Cu/Al	50	52.97	38.02
MP2	Male arm	Connection	Al/Al	50	51.46	36.51
MP3	Male arm	Connection	Al/Cu-Ag	75	52.33	37.38
MP4	Male arm	Contact	Cu-Ag/Cu-Ag	65	54.29	39.34
MP5	Female arm	Contact	Cu-Ag/Cu-Ag	65	53.68	38.73
MP6	Female arm	Connection	Cu-Ag/Al	75	52.49	37.54
MP7	Female arm	Connection	Al/Al	50	51.83	36.88
MP8	Output terminal	Connection	Al/Cu	50	53.02	38.07
MP9	Insulated support	Insulator	Porcelain	140	17.57	2.62
MP10	Environment	Environment	-	-	14.95 <sup>b)</sup>	-

Measurements were performed with expanded uncertainty of: 1.1% for (temperature) and 2.1% for current the confidence level P = 95%. Measurement points are presented in fig. 2.


1) Average value of 3 measurement points

The temperature-rise on supply bars at 1m distance from terminals was 36.29 K, 36.80 K.


Note: Aspect of the Disconnector during temperature-rise test is presented in photo 1.

9. SHORT-TIME WITHSTAND CURRENT AND PEAK WITHSTAND CURRENT TEST

9.1. Data of testing and measuring circuit




Number of phases	2	
Power supply / Connection	G3/Y	
Transformer / Ratio	TC 7, 8, 9 / 6,67	
Earthing	Power supply	600 Ω
	Apparatus	Net earthing connection
Reactor [Ω]	0.4	
Power factor	<0,15	
M1 - Test current - Shunt	70 kA / 1.75 V	
M4 - Power supply voltage - Voltage transformer	15000 V/100 V	
M8 - Data acquisition system	TRAS 2 - 16 bit, 16 channels	



1 - Aluminium tube 80x10 mm

Fig. 3 - Testing circuit for main circuit



1 - Aluminium tube 80x10 mm  
2 - Copper table 2x240 mm<sup>2</sup>

Fig. 4 - Testing circuit for earthing switch

9.2. Values obtained at tests

Oscillogram No.	$I_p$ [kA]	$I_1$ [kA]	$t_1$ [s]	$I_{L,equiv,t_1}$ [kA]	$\Delta U$ [V]	Remarks
91579/2016	105.7	-	0.24	-	19.3	Dynamic test on main circuit
91580/2016	-	40.8	2.9	40.1	19	Thermal test on main circuit
91582/2016	104.8	-	0.23	-	-	Dynamic test on earthing switch
91583/2016	-	40.3	3	-	-	Thermal test on earthing switch

Measurements were performed with extended uncertainty of: 3% for voltages; 2.5% for currents; 0.2% for time and the confidence level P = 95%.

Symbols used in tables and oscillograms

- $I$  = Short-circuit current
- $I_p$  = Peak values of short-time withstand currents on the phases R, S, T.
- $I_1$  = R.m.s. values of short - time withstand currents on the phases R, S, T.
- $\Delta U$  = Voltage drop on the main circuit
- $t_1$  = Duration of short - circuit
- $I_{L,equiv,t_1}$  = Equivalent value of short-time withstand current on  $t_1 = 3$  s calculated as follows:

$$I_{L,equiv,t_1} = I_{1, end} \cdot \sqrt{\frac{t_1}{t_1}}$$

Notes:


- The environment temperature was 14°C.
- Aspect of the disconnector and earthing switch in the test circuit and of their contacts after tests are presented in photos 2 to 6.

10. TEST RESULT

- The specified limits of temperature-rise according to IEC standard were not exceeded in all the measuring points.
- After short-time withstand current and peak withstand current tests Disconnector and Earthing Switch opened at first attempt and presented no visible damages.
- The resistance of the disconnector measured after tests did not exceed with more than -0.4 % from the resistance measured before tests.

123 kV, 1600 A, 40 kA/3 s Three-pole disconnector type SDF with earthing switch passed the tests.

- END OF DOCUMENT -








Photo 1 - Aspect of three-pole disconnector type SDF with earthing switch during the temperature-rise test




Photo 2 - Aspect of three-pole disconnector type SDF with earthing switch at test on main circuit







Photo 3 - Aspect three-pole disconnector type SDF with earthing switch at test on earthing switch




Photos 4, 5, 6 - Aspect of the main contacts and the earthing switch contact after tests



BRNO C  
CRAIOVA




000045




© ICMET Csaova 2016/BC+M+TD  
Code: F-03.19.04 eng

Oscillogram No. 91583 / 2016



© ICMET Csaova 2016/BC+M+TD  
Code: F-03.19.04 eng


Oscillogram No. 91583 / 2016



© ICMET Csaova 2016/BC+M+TD  
Code: F-03.19.04 eng

Oscillogram No. 91583 / 2016

ВЯРНО С  
ОРИГИНАЛА



000046



NATIONAL INSTITUTE FOR RESEARCH, DEVELOPMENT AND TESTING IN ELECTRICAL ENGINEERING

**ICMET CRAIOVA  
HIGH VOLTAGE DIVISION**

Low and High Voltage Testing Laboratory  
200746 CRAIOVA, Blvd. DECEBAL, No.118A, ROMANIA  
Matriculation certificate: J16/312/1999, VAT number RO3871599  
Phone: + 40 0351 402425, 404888; Fax: + 40 0351 404890  
www.icmet.ro; E-mail: market@icmet.ro



**TEST REPORT  
No. 45229 / 09.03.2016**

- 1. CUSTOMER: **ABB Bulgaria EOOD – Branch Sevlievo**  
Address: 32, Nikola Petkov Str., 6400 Sevlievo - BULGARIA
- 2. MANUFACTURER: **ABB Bulgaria EOOD – Branch Sevlievo**  
Address: 32, Nikola Petkov Str., 6400 Sevlievo - BULGARIA
- 3. TESTED PRODUCT: 3-pole disconnector SDF 123 / 1600 with one earthing switch  
Serial no. 2GPA45040000654
- 4. REFERENCE STANDARDS: IEC 62271-102:2013; IEC 62271-1:2011; IEC 60060-1:2010
- 5. PERFORMED TESTS:
  - I – Radio interference voltage (RIV) test
  - II – Dry lightning impulse withstand voltage test
  - III – Dry power frequency withstand voltage test
  - IV – Wet power frequency withstand voltage test
  - V – Dry power frequency withstand voltage test in the most unfavourable position of the earthing blade
  - VI – Wet power frequency withstand voltage test in the most unfavourable position of the earthing blade
- 6. TESTS DATE: (04 + 08).03.2016
- 7. TESTS RESULTS: The product passed the tests.  
The test report contains 23 pages and is edited in 4 copies, copy no.1 remain in laboratory and copies 2+ 4 are sent to the customer.

HEAD OF HVD – TECHNICAL MANAGER,  
Dipl. Eng. BURCIU Ion

HEAD OF TESTING TEAM,  
Dipl. Eng. BADEA Ion

Warnings:

- a. The results refer only to the tested product.
- b. Publication and reproduction of the contents of this report in any other form unless its complete photocopying is not allowed without writing approval of ICMET for such laboratory bookings.
- c. All signatures of the present report are original ones.



Content

	Page
> Identification of the test product.....	3
> The main technical characteristics established by manufacturer.....	3
> Tests program.....	3
> Responsible for tests.....	3
> Present at the test.....	3
> Radio interference voltage test .....	4, 5, 6, 7
> Photos for RIV test.....	8, 9
> Dry lightning impulse withstand voltage test .....	10+12
> Oscillograms.....	13, 14
> Dry power frequency withstand voltage test.....	15, 16
> Wet power frequency withstand voltage test.....	17 + 19
> Dry power frequency withstand voltage test in the most unfavourable position of the earthing blade.....	20
> Wet power frequency withstand voltage test in the most unfavourable position of the earthing blade.....	21, 22
> Drawing.....	23



- 1. IDENTIFICATION OF THE TEST PRODUCT: 3-pole disconnector SDF 123 / 1600 with one earthing switch  
Type: SDF 123 / 1600  
Serial / year: 2GPA45040000654 / 2016  
Technical Specification / Drawing: - / see page 22  
Client test order: 705.2 / 682 / 22.01.2016  
Internal test order: 22938 / 18.02.2016  
Product receiving date: 02.03.2016  
Product condition at receiving: New

- 2. THE MAIN TECHNICAL CHARACTERISTICS ESTABLISHED BY MANUFACTURER:
  - Rated voltage: 123 kV
  - Rated normal current: 1600 A
  - Rated frequency: 50 Hz
  - Rated lightning impulse withstand voltage:
    - a) Phase – to – earth and between phases.....550 kV<sub>peak</sub>
    - b) Across the isolating distance.....630 kV<sub>peak</sub>
  - Rated power frequency withstand voltage:
    - a) Phase – to – earth and between phases..... 230 kV<sub>r.m.s.</sub>
    - b) Across the isolating distance..... 265 kV<sub>r.m.s.</sub>
    - In the most unfavourable position of earthing blade.....142 kV<sub>r.m.s.</sub>
  - Note: For solidly earthed neutral systems.
  - Max. radio interference level.....< 2500 µV

Note: During the tests, the disconnector was mounted above earth on an insulated base.

3. TESTS PROGRAM:

- I – Radio interference voltage (RIV) test
- II – Dry lightning impulse withstand voltage test
- III – Dry power frequency withstand voltage test
- IV – Wet power frequency withstand voltage test
- V – Dry power frequency withstand voltage test in the most unfavourable position of the earthing blade
- VI – Wet power frequency withstand voltage test in the most unfavourable position of the earthing blade

4. RESPONSIBLE FOR TESTS: Eng. T. Nicoraş (I)  
Eng. L. Vişoi (II)  
Eng. V. Telea (III, IV, V, VI)

5. PRESENT AT THE TESTS: Dipl.Eng. Delyan Stoev – ABB Bulgaria  
Dipl.Eng. Pliarsh Sharikov – ABB Bulgaria  
Dipl.Eng. Yavor Yankov – ABB Bulgaria




**I – RADIO INTERFERENCE VOLTAGE TEST**

- 1. Test date: 07.03.2016
- 2. Test standard: IEC 62271 – 102: 2013, clause 6.3; IEC 62271 – 1 : 2011, clause 6.3; 6.9.1.1; TR CISPR 18-2 : 2010, clause 4.5.
- 3. Atmospheric conditions: p = 990 mbar, t = 11.5°C, h<sub>v</sub> = 74.8 %
- 4. Equipment used (see also the test circuit diagram from the point 5):
  - Test transformer 350 kVA / 350 kV, no.3 - 1993
  - Measuring systems:
    - AC measuring system 350 kV consists of: high voltage compressed gas capacitor type MCF 75/350P, no.853839 and low voltage arm type H90, no.859399 + digital peak voltmeter type MU-17, no. 910396.

(Calibration Certificate no. 41 / 04.2015).  
Measuring uncertainty is 1.8 %.  
The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2 providing a level of confidence of approximately 95 %.

- RIV measuring system:
  - Measuring Impedance:
    - coupling capacitor C<sub>1</sub> (1nF / 600 kV), no.73H297;
    - resistor R<sub>2</sub> (275Ω), matching resistor R<sub>1</sub> (50Ω);
  - Measuring instrument – electromagnetic interference receiver type SMV-42 (M), no.007 with internal resistor R<sub>3</sub> (50Ω).

5. Test circuit diagram:



Legend: F – rejection filter;  
EUT – equipment under test.

Fig. 1

- 6. Measuring results:  
Note: The presented results were obtained during the last series of voltage reductions.  
Pol Ag - Closed Position (see photo 1, page 8)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dBµV/500]	V <sub>0</sub> [dBµV/3000]	V <sub>0</sub> [µV]
1.1 x 123 / √3 = 78	28.6	57.1	718
71	25.1	53.7	484
64	20.3	48.8	279
57	12.7	41.3	116
50	0	28.6	27
43	0	28.6	27
36	0	28.6	27
28	0	28.6	27
21	0	28.6	27

000047



Open Position  
Voltage applied to "a" the female contact (contact without earthing blade)  
(see photo 2, page 8)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	35.6	64.2	1622
71	33.5	62.1	1274
64	26.9	55.5	596
57	0	28.6	27
50	0	28.6	27
43	0	28.6	27
36	0	28.6	27
28	0	28.6	27
21	0	28.6	27

Open Position  
Voltage applied to "A" the male contact (contact with earthing blade)  
(see photo 3, page 8)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	22.6	51.2	363
71	13.8	42.5	132
64	7.6	35.2	65
57	3.9	32.5	42
50	3.7	32.3	41
43	3.5	32.1	40
36	3.2	31.8	39
28	3	31.6	38
21	2.5	31.1	36

Pol Bb - Closed Position (see photo 4, page 8)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	29.2	57.8	776
71	27.3	55.9	624
64	24.2	52.8	437
57	4.3	32.9	44
50	0	28.6	27
43	0	28.6	27
36	0	28.6	27
28	0	28.6	27
21	0	28.6	27



Open Position  
Voltage applied to "b" the female contact (contact without earthing blade)  
(see photo 5, page 8)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	39	67.6	2399
71	33.8	62.2	1288
64	30	58.6	851
57	6	36.6	68
50	7	35.6	60
43	3.5	32.1	40
36	0	28.6	27
28	0	28.6	27
21	0	28.6	27

Open Position  
Voltage applied to "B" the male contact (contact with earthing blade)  
(see photo 6, page 9)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	22.8	51.4	372
71	6.5	35.1	67
64	2.4	31	35
57	2.2	30.8	35
50	1.6	30.2	32
43	1.2	29.8	31
36	0	28.6	27
28	0	28.6	27
21	0	28.6	27

Pol Cc - Closed Position (see photo 7, page 9)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	28.5	57.1	716
71	24.8	53.4	468
64	18.7	47.3	232
57	10.2	38.8	87
50	8.7	37.8	73
43	8.5	37.1	72
36	8.5	37.1	72
28	8.2	36.8	69
21	7.4	36	63



Open Position  
Voltage applied to "c" the female contact (contact without earthing blade)  
(see photo 8, page 9)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	38.6	67.2	2291
71	34	62.6	1349
64	31	59.8	955
57	9	37.8	76
50	8	36.6	68
43	7.4	36	63
36	7.3	35.9	62
28	7.3	35.9	62
21	7.1	35.7	61

Open Position  
Voltage applied to "C" the male contact (contact with earthing blade)  
(see photo 9, page 9)

Measuring voltage [kV]	RIV level		
	V <sub>m</sub> [dB/1µV/500]	V <sup>0</sup> [dB/1µV/3000]	V <sup>90</sup> [µV]
1.1 x 123 / √3 ≈ 78	18.7	47.3	232
71	13.1	41.7	122
64	9.2	37.8	78
57	3.9	32.5	42
50	1.8	30.4	33
43	0	28.6	27
36	0	28.6	27
28	0	28.6	27
21	0	28.6	27

General notes for to the tables:

- <sup>1</sup> The corrected value of the instrument reading:  
 $V = V_m + A + R$ , where:  
V<sub>m</sub> - instrument reading;  
A - attenuation of the measuring circuit determined at the calibration of the test circuit with 1V<sub>max</sub> 1MHz sine wave voltage:  
 $A = A_2 - A_1 = 67.6 \text{ dB} - 60.6 \text{ dB} = 7 \text{ dB}$ ;  
A<sub>1</sub> - attenuation of the complete measuring circuit = 60.6 dB;  
A<sub>2</sub> - attenuation of the test object = 67.6 dB;  
R - resistance network factor;  
 $R = 20 \text{ lg} (600/50) \approx 21.6 \text{ dB}$ .
- <sup>2</sup> The reported value of the RIV level expressed in µV.

The radio interference voltage level don't exceed 2500µV at 1.1 x 123/√3 ≈ 78 kV.  
The product passed the test.



Pol Aa



Photo 1



Photo 2




Photo 3

Pol Bb




Photo 4



Photo 5

030048




Photo 6

Pol Cc




Photo 7



Photo 8




Photo 9



### II - DRY LIGHTNING IMPULSE WITHSTAND VOLTAGE TEST

- 1. Test date: 04.03.2018
- 2. Test standard: IEC 62271-102: 2013, subclause 6.2; IEC 62271-1: 2011, subclause 8.2
- 3. Atmospheric conditions: p = 887 mbar; t = 11 °C; h = 65 %

4. Equipments used:

- Impulse generator 4.2 MV, no. 5 - 1187; connection 1.5 x 1;
- C<sub>1</sub> = 0.115 [μF]; R<sub>1</sub> = 178.25 [Ω]; R<sub>2</sub> = 578 [Ω]

Addenda: C<sub>1</sub> - equivalent capacity of impulse generator; R<sub>1</sub> - equivalent serial resistance of impulse generator; R<sub>2</sub> - equivalent parallel resistance of impulse generator;

HV measuring systems:

- for lightning impulse voltage:

- Capacitive voltage divider serial no.5 - 1197, k<sub>0</sub> = 1731.8

- Digital measuring system type TR- AS-RC 100 - 10/4, serial no. 241, channel 2 for recorded lightning impulse voltage test. (Calibration Certificate DKD-K- 18701, no. 292 / 12.2011)

The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 85 % equal with 1.8 % for peak value, 8.4 % and 4.2 % for front and tail times.

6. Test procedure / Test set-up:

	Tested insulation	
	phase to earth and between phases (acc. to IEC 62271-1, scl.6.2.5.1 and scl.6.2.8.2)	across the isolating distance (acc. to IEC 62271-1, scl.6.2.5.2, method (b) and 6.2.6.2)
	C & O	O
Arcing distance [mm]	1110	1260
Correction factors:	k <sub>1</sub>	1.0052
	k <sub>2</sub>	0.8546
	k <sub>3</sub> = k <sub>1</sub> · k <sub>2</sub>	0.8596
U <sub>red</sub> (p, l, h) (°) and (°) [kV <sub>red</sub> ]	659	639
U <sub>red</sub> (p, l, h) = k <sub>3</sub> · U <sub>red</sub> (p, l, h)	627.8	601.6

Symbols used: - U<sub>red</sub> (p, l, h) - rated withstand voltage value; U<sub>red</sub> (p, l, h) - test voltage corrected to atmospheric conditions  
- O, C - open and respectively closed position of disconnector.

Note: The test was performed with standard lightning impulse wave: 1.2 / 50 μs. For wave parameters see oscilograms 302544 and 302649 from page 13 for testing the insulation phase-to-earth and oscilograms 302733 and 302755 from page 14 for testing across the isolating distance.



#### Lightning impulse voltage withstand test - phase-to-earth and between phases

Disconnector position	Voltage applied to	Earthed to	Free terminals	U <sub>red</sub> (p, l, h) [kV]	Pol	Number of impulses / disruptive discharges
Closed	A, a	B, b, C, c, F	-	550	(+)	15/0
				550	(-)	15/0
	B, b	A, a, C, c, F	-	550	(+)	15/0
				550	(-)	15/0
	C, c	A, a, B, b, F	-	550	(+)	15/0
			550	(-)	15/0	
Open	A	a, b, c, B, C, F	-	550	(+)	15/0
				550	(-)	15/0
	a	A, B, C, b, c, F	-	550	(+)	15/0
				550	(-)	15/0
	B	A, C, a, b, c, F	-	550	(+)	15/0
				550	(-)	15/0
	b	A, B, C, a, c, F	-	550	(+)	15/0
				550	(-)	15/0
C	A, B, a, b, c, F	-	550	(+)	15/0	
			550	(-)	15/0	
c	A, B, C, a, b, F	-	550	(+)	15/0	
			550	(-)	15/0	

#### Lightning impulse across isolating distance

Disconnector position	Voltage applied to	Earthed to	Free terminals	U <sub>red</sub> (p, l, h) [kV]	Pol	Number of impulses / disruptive discharges
open	A	a	B, b, C, c, F	630	(+)	15/0
				630	(-)	15/0
	a	A	B, b, C, c, F	630	(+)	15/0
				630	(-)	15/0
	B	b	A, a, C, c, F	630	(+)	15/0
				630	(-)	15/0
	b	B	A, a, C, c, F	630	(+)	15/0
				630	(-)	15/0
	C	c	A, a, B, b, F	630	(+)	15/0
				630	(-)	15/0
o	C	A, a, B, b, F	630	(+)	15/0	
			630	(-)	15/0	

Notes: 1. A -- male contact (contact without earthing blade); a -- female contact (contact with earthing blade); F -- frame.  
2. The standard 1.2 / 50 μs lightning impulse withstand test was carried out in accordance with IEC 60060 - 1: 2010, Procedure B by applying 15 consecutive impulses for each polarity.

ICMET Craiova



#### Impulse test circuit




Fig. 2

- Legend: 1 - Impulse generator 4.2 MV
- 2 - Capacitive voltage divider
- 3 - Equipment under test
- 4 - Transient recorder TR - AS 100 - 10/4






Photo 10

6. Test result: The product passed the test.

000049




No.: 302544  
 CHZ No. 302544  
 DATE 04.03.2016  
 TIME 10:24:45  
 Up= -539kV  
 T1= 1.35µs  
 T2= 44.3µs




No.: 302549  
 CHZ No. 302549  
 DATE 04.03.2016  
 TIME 11:08:30  
 Up= 541kV  
 T1= 1.37µs  
 T2= 44.4µs

Cod F-01.22.01(e)  
 © ICAMET Čreva – 2016



No.: 302733  
 CHZ No. 302733  
 DATE 04.03.2016  
 TIME 12:52:31  
 Up= 616kV  
 T1= 1.43µs  
 T2= 44.2µs



No.: 302755  
 CHZ No. 302755  
 DATE 04.03.2016  
 TIME 13:07:45  
 Up= -617kV  
 T1= 1.38µs  
 T2= 44.2µs

Cod F-01.22.01(e)  
 © ICAMET Čreva – 2016



III – DRY POWER FREQUENCY WITHSTAND VOLTAGE TEST

- Test date: 04.03.2016
- Test standards: IEC 62271-102:2013, subclause 6.2.6, IEC 62271-1:2011, sol. 6.2
- Atmospheric conditions: p = 987 mbar, (t = 11 °C), h = 64.6 %
- Equipment used:
  - Test transformer: 350 kVA / 350 kV, no. 3 – 1963.
  - Measuring systems used:
    - AC measuring system 350 kV consists of: high voltage compressed gas capacitor type MCF 75/350P, no. 653389 and low voltage arm type H90, no. 898939 + digital peak voltmeter type MU-17, no. 910396.

(Calibration Certificate no. 41 / 04.2015).  
 Measuring uncertainty is ± 1.6 %.  
 The reported uncertainty is an expanded uncertainty, based on a standard uncertainty multiplied by a coverage factor k = 2, providing a level of confidence of approximately 95 %.

5. Test procedure:

Description	Tested insulation	
	phase-to-earth and between phases (acc. to IEC 62271-1:2011, sol.6.2.6.1 and IEC 62271-102:2013, sol.6.2.6.1)	across the isolating distance (acc. to IEC 62271-1:2011, sol.6.2.5.2 method b) and IEC 62271-102:2013, sol.6.2.8.1)
Arcing distance [mm]:	1110	1260
Correction factors:	1.0023	1.0023
A	0.9767	0.9759
B	0.9789	0.9782
$U_{m}(p, t, h)$ [kV <sub>ms</sub> ]:	230	265
$U_{m}(p, t, h) \cdot k_1 \cdot k_2$ [kV <sub>ms</sub> ]:	225.14	259.22
Frequency [Hz]:	50	50
Time [s]:	60	60

Symbols used: -  $U_{m}(p, t, h)$  – rated withstand voltage value;  
 -  $U_{m}(p, t, h)$  – test voltage corrected to atmospheric conditions;  
 - O, C – open or respectively closed position of disconnector.

Dry power frequency withstand voltage test: phase – to – earth and between phases

Disconnector position	Voltage applied to	Earthed to	Free terminals	$U_{m}(p, t, h)$ [kV]	Time [s]
Closed	A, B	B, b, C, C, F	–	230	60
	B, b	A, a, C, C, F	–	230	60
	C, c	A, a, B, b, F	–	230	60
Open	A	a, b, c, B, C, F	–	230	60
	a	A, B, C, b, C, F	–	230	60
	B	A, C, a, b, C, F	–	230	60
	b	A, B, C, a, C, F	–	230	60
	C	A, B, a, b, C, F	–	230	60
	c	A, B, C, a, b, F	–	230	60

Cod F-01.22.01(e)  
 © ICAMET Čreva – 2016



Dry power frequency withstand voltage test: across Isolating distance

Disconnector position	Voltage applied to	Earthed to	Free terminals	$U_{m}(p, t, h)$ [kV]	Time [s]
Open	A	a	B, b, C, C, F	265	60
	a	A	B, b, C, C, F	265	60
	B	b	A, a, C, C, F	265	60
	b	B	A, a, C, C, F	265	60
	C	c	A, a, B, b, F	265	60
	c	C	A, a, B, b, F	265	60

Symbols used: A – male contact (contact with earthing blade); a – female contact (contact without earthing blade); F – frame.

6. Test set-up:




Fig. 3

Legend: EUT – Equipment under test

7. Test result: During the test no flashover or disruptive discharge occurred.  
 The product passed the test.

Cod F-01.22.01(e)  
 © ICAMET Čreva – 2016



IV. WET POWER - FREQUENCY VOLTAGE TEST

1. Test date: 04.03.2016
  2. Test standard: IEC 62271-102:2013, subclause 6.2.6; IEC 62271-1:2011, scl. 6.2
  3. Atmospheric conditions: p = 997 mbar; t = 11 °C; h = 64.5 %
  4. Equipment used:
    - for power frequency voltage:
      - Test transformer: 350 kVA / 350 kV, no. 3 - 1963.
    - for rain:
      - Artificial rain installation, serial no. 3 - 29.
- Measuring systems used:
- for power frequency voltage:
    - AC measuring system 350 kV consists of: high voltage compressed gas capacitor type MCF 75/350P, no. 853889 and low voltage arm type H90, no.898939 + digital peak voltmeter type MU-17, no. 910396. (Calibration Certificate no. 41 / 04.2015).
- The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 % equal with 1.8 %.
- for measuring the parameters of the water have been used:
    - liquid glass thermometer series 41; (Calibrate Certificate no. DJ 013.141 - 552 / 2012 - BRML Craiova)
- The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 % equal with 0.4 % / °C.
- conductivity meter type 3210 serial no. 15440615 encompassing conductivity cell type TetraCon 325, series 15440175; (Calibrate Certificate no. 132.05 - 03.2016)
- The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 % equal with 3.5 µS/cm.

6. Test procedure:

Description	Tested insulation	
	phase-to-earth and between phases (acc. to IEC 62271-1: 2011, scl.6.2.6.1 and IEC 62271-102:2013, scl.8.2.6.1)	across the isolating distance (acc. to IEC 62271-1: 2011, scl.6.2.6.2 method b) and IEC 62271-102:2013, scl.6.2.6.1)
Arching distance [mm]	C & O	O
Correction factors:		
$k_1$	1.0023	1.0023
$k_2$	1	1
$k_3 = k_1 \cdot k_2$	1.0023	1.0023
Temperature [°C]	16	15
Precipitation conditions:		
Temp [mm/min]	1.5	1.5
Temp [mm/min]	1.6	1.5
Water conductivity [µS/cm]	96	68
$U_{wet}(p, l, h)$ [kV <sub>eff</sub> ]	230	265
$U_{wet}(p, l, h) \cdot k_3$ [kV <sub>eff</sub> ]	230.52	265.8

Symbols used: -  $U_{wet}(p, l, h)$  - rated withstand voltage value;  
 -  $U_{wet}(p, l, h)$  - test voltage connected to atmospheric conditions;  
 - O/C - open or respectively closed position of disconnector.



Wet power/frequency with stand voltage test: phase-to-earth and between phases

Disconnector position	Voltage applied to	Earthed to	Free terminals	$U_{wet}(p, l, h)$ [kV]	Time [s]
Closed	A, a	B, b, C, c, F	-	230	60
	B, b	A, a, C, c, F	-	230	60
	C, c	A, a, B, b, F	-	230	60
Open	A	a, b, c, B, C, F	-	230	60
	B	A, B, C, c, F	-	230	60
	C	A, B, C, a, c, F	-	230	60

Wet power-frequency withstand voltage test: across isolating distance

Disconnector position	Voltage applied to	Earthed to	Free terminals	$U_{wet}(p, l, h)$ [kV]	Time [s]
Open	A	a	B, b, C, c, F	265	60
	a	A	B, b, C, c, F	265	60
	B	b	A, a, C, c, F	265	60
	b	B	A, a, C, c, F	265	60

Symbols used: A - male contact (contact with earthing blade); a - female contact (contact without earthing blade); F - frame.

6. Test set-up:





Fig. 4 Legend: EUT - Equipment under test



7. Test result: During the test no flashover or disruptive discharge occurred. The product passed the test.



V - DRY POWER FREQUENCY WITHSTAND VOLTAGE TEST IN THE MOST UNFAVOURABLE POSITION OF THE EARTHING BLADE

1. Test date: 04.03.2016
  2. Test standard: IEC 62271-102: 2013, subclause 4.2; 6.2.5 and Table 5.
  3. Atmospheric conditions: p = 997 mbar; t = 11 °C; h = 64.5 %
  4. Equipment used:
    - Test transformer; 350 kVA / 350 kV, no. 3 - 1963.
- Measuring systems used:
- AC measuring system 350 kV consists of: high voltage compressed gas capacitor type MCF 75/350P, no. 853889 and low voltage arm type H90, no.898939 + digital peak voltmeter type MU-17, no. 910396. (Calibration Certificate no. 41 / 04.2015).
- The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 % equal with 1.8 %.

Earthing blade in the most unfavourable position	
Arching distance measured (mm)	780
Correction factors:	
$k_1$	1.0018
$k_2$	0.9832
$k_3 = k_1 \cdot k_2$	0.9848
$U_{wet}(p, l, h)$ [kV <sub>eff</sub> ]	142
Frequency [Hz]	50
Time [s]	60

Symbols used:  $U_{wet}(p, l, h)$  - rated withstand voltage value.  
 O/C - open or respectively closed position of disconnector.  
 Dry power frequency withstand voltage test in the most unfavourable position of the earthing blade - earthing blade in the most unfavourable position

Condition	Voltage applied to	Earthed to	Free terminals	Voltage test [kV]	Time [s]
Disconnector open	A	a, B, b, C, c, F	-	142	60
	B	b, A, a, C, c, F	-	142	60
	C	c, A, a, B, b, F	-	142	60

Symbols used: A - male contact (contact with earthing blade); a - female contact (contact without earthing blade); F - frame.

8. Test set-up:




Fig. 5

7. Test result: The product passed the test.

000051



### VI - WET POWER FREQUENCY WITHSTAND VOLTAGE TEST IN THE MOST UNFAVOURABLE POSITION OF THE EARTHING BLADE

1. Test date: 04.03.2018
2. Test standard: IEC 62271-102: 2013, subclause 4.2; 6.2.6 and Table 5.
3. Atmospheric conditions: p = 987 mbar, t = 11 °C, h = 84.5 %
4. Equipment used:
  - for power frequency voltage:
    - Test transformer: 350 kVA / 350 kV, no. 3 - 1963.
  - for rain:
    - Artificial rain installation, serial no. 3 - 29.

#### Measuring systems used:

- for power frequency voltage:
  - AC measuring system 350 kV consists of: high voltage compressed gas capacitor type MCF 75/350P, no. 833699 and low voltage arm type H90, no. 695939 + digital peak voltmeter type MU-17, no. 910398. (Calibration Certificate no. 41 / 04.2015).

The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 % equal with 1.6 %.

- for measuring the parameters of the water have been used:
  - Liquid glass thermometer series 43; (Calibrate Certificate no. DJ 013.141 - 552 / 2012 - BRML Crlevo)

The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 % equal with 0.4 % / °C.

- conductivity meter type 3210 serial no. 15440915 encompassing conductivity cell type TetraCon 325, series 15440175; (Calibrate Certificate no. 132.05 - 03.2016)

The uncertainty stated is expanded uncertainty obtained by multiplying the standard uncertainty by the coverage factor k = 2. The value of measurand lies within the assigned range of values with probability of 95 % equal with 3.5 µS/cm.

#### 6. Test procedure:

Earthing blade in the most unfavourable position	
Arcing distance measured [mm]	780
<b>Correction factors:</b>	
$k_1$	1.0016
$k_2$	1
$k_3 = k_1 \cdot k_2$	1.0016
$U_{test} (p.u./h)$	142
Frequency [Hz]	50
Time [s]	60

Symbols used: -  $U_{test}$  (p.u./h) - rated withstand voltage value.  
- O/C - open or respectively closed position of disconnector.



Wet power frequency withstand voltage test in the most unfavourable position of the earthing blade - earthing blade in the most unfavourable position

Condition	Voltage applied to	Earthed to	Free terminals	Voltage test [kV]	Time [s]
Disconnector open	A	a, B, b, C, c, F	-	142	60
	B	b, A, a, C, c, F	-	142	60
	C	c, A, a, B, b, F	-	142	60

Symbols used: A - male contact (contact with earthing blade), a - female contact (contact without earthing blade), F - Frame.

#### 6. Test set-up:






Fig. 5

7. Test result: The product passed the test.



- end of test report -

ВЯНО С  
ОРИ НАЛА







NATIONAL INSTITUTE FOR RESEARCH, DEVELOPMENT  
AND TESTING IN ELECTRICAL ENGINEERING  
**ICMET CRAIOVA**  
HIGH VOLTAGE DIVISION  
Low and High Voltage Testing Laboratory  
290748 CRAIOVA, Blvd. DECEBAL, No.118A, ROMANIA  
Matriculation certificate: J18/312/1999, VAT number RO3871599  
Phone: + 40 0351 402425, 404688; Fax: + 40 0351 404890  
www.icmet.ro ; E-mail: [maris@icmet.ro](mailto:maris@icmet.ro)



Copy no.2 / 4

**TEST REPORT**  
No. 45326 / 22.04.2016

- CUSTOMER:** ABB Bulgaria EOOD – Branch Sevlëvo  
Address: 32, Nikola Petkov Str., 5400 Sevlëvo - BULGARIA
- MANUFACTURER:** ABB Bulgaria EOOD – Branch Sevlëvo  
Address: 32, Nikola Petkov Str., 5400 Sevlëvo - BULGARIA
- TESTED PRODUCT:** Operating mechanism box type MD 50  
Serial no. 500022670 – 160 - 016
- REFERENCE STANDARDS:** IEC 60529 : 2013; IEC 62271-202:2014
- PERFORMED TESTS:**  
I – Verification of the protection degree IP – 55  
II – Mechanical impact test (IK CODE)
- TESTS DATE:** (08 + 09).04.2016
- TESTS RESULTS:** The product passed the tests.

The test report contains 7 pages and is edited in 4 copies, copy no.1 remain in laboratory and copies 2+ 4 are sent to the customer.

HEAD OF HVD – TECHNICAL MANAGER,  
Dipl. Eng. BURCIU Ion

HEAD OF TESTING TEAM,  
Dipl. Eng. DINU Ion

**Warnings:**

- The results refer only to the tested product.
- Publication and reproduction of the contents of this report in any other form unless its complete photocopying is not allowed without writing approval of Division to which laboratory belongs.
- All signatures of the present report are original ones.

Cod F-01.22.01(e)  
© ICMET Craiova – 2016



TEST REPORT No. 45326

page 2 of 7

**Content**

- > Identification of the test product..... Page 3
- > The main technical characteristics established by manufacturer..... Page 3
- > Tests program..... Page 3
- > Responsible for tests..... Page 3
- > Present at the tests..... Page 3
- > Verification of the protection degree IP-55..... Page 4
- > Photos..... Page 5
- > Mechanical impact test (IK CODE)..... Page 8
- > Photo..... Page 7

Cod F-01.22.01(e)  
© ICMET Craiova – 2016



TEST REPORT No. 45326

page 3 of 7

- IDENTIFICATION OF THE TEST PRODUCT:** Operating mechanism box  
Type: MD 50  
Serial / year: 500022670 – 150 - 016 / 2016  
Technical Specification / Drawing: - / -  
Client test order: 705.2 / 682 / 22.01.2016 + Additional Act No.3 / 22.01.2016  
Internal test order: 22936 / 18.02.2016  
Product receiving date: 09.04.2016  
Product condition at receiving: New


- THE MAIN TECHNICAL CHARACTERISTICS ESTABLISHED BY MANUFACTURER:**  
- IP of Protection Degree : IP 55.

**3. TESTS PROGRAM:**

- I – Verification of the protection degree IP – 55
- II – Mechanical impact test (IK CODE)

- RESPONSIBLE FOR TEST:** Dipl. Eng. V. Telea (I)   
Dipl. Eng. R. Georgescu (II)

- PRESENT AT THE TEST:** Dipl.Eng. Delyan Stoev – ABB Bulgaria  
Dipl.Eng. Plamen Sharkov – ABB Bulgaria  
Dipl.Eng.Yavor Yankov – ABB Bulgaria



ICMET CRAIOVA  
ROMANIA

Cod F-01.22.01(e)  
© ICMET Craiova – 2016



TEST REPORT No. 45326

page 4 of 7

**I. VERIFICATION PROTECTION DEGREE IP – 55**

- Test date: (08 + 09).04.2016
- Test standard: IEC 60529 : 2013, clauses 12; 13 and 14
- Atmospheric conditions: 08.04.2016 p = 1007 mbar; t = 12.5 °C; h = 59 %  
09.04.2016 p = 1005 mbar; t = 11.7 °C; h = 62 %
- Test procedure / Test set-up:
  - Verification of the first characteristic numeral '5'
  - Protection against access to hazardous parts
  - Protection against the penetration of solid foreign objects

For a.1. It was used the access probe with a diameter of 1 mm and a length of 100 mm.  
(Calibration Certificate 01.01 1425 / 2015 IIM Buchares)

Measuring uncertainty is ± 0.010.  
The reported uncertainty is an expanded uncertainty, based on a standard uncertainty multiplied by a coverage factor k = 2, providing a level of confidence of approximately 95 %.

Result: The access caliber not penetrated the object tested.

For a.2. It was used dust chamber according to fig.2 of IEC 60529 : 2013.

Test object is of the category 2. (Enclosures where no pressure difference relative to the surrounding air is present – see subclause 13.4 of IEC 60529 : 2013).

The enclosure under test is supported in its normal operating position in side the test chamber, but was not connected to a vacuum pump. The test duration is 8 hours.

Result: No any dust ingresses inside of tested enclosure.

b. Verification of the second characteristic numeral '6', against splashing water

It was used the spray nozzle compliant with fig.6 of IEC 60529 : 2013

Internal diameter of the nozzle: 6.3 mm

Total area  $A_T = 1.32 \text{ m}^2$

Delivery rate: 12.5 [l / min ± 5 %]

Distance from nozzle to enclosure surface 2.5 – 3 m

Minimum test duration: 3 min.

Measuring uncertainty is ± 3 %.  
The reported uncertainty is an expanded uncertainty, based on a standard uncertainty multiplied by a coverage factor k = 2, providing a level of confidence of approximately 95 %.

Result: There was no ingress of water into the test object.

Pictures of the test product are presented on the page 5.

- Test result: The product passed the test.

Cod F-01.22.01(e)  
© ICMET Craiova – 2016

000053




Photo 1




Photo 2




Photo 3



## II. MECHANICAL IMPACT TEST (IK CODE)

1. Test date: 09.04.2016
2. Test standard: IEC 62271-202:2014, clause 6.101.3
3. Environmental conditions: temperature: 11.7°C  
relative humidity: 62 %

4. Equipment used:  
- Pendulum hammer 5-50J, ICMET Craiova,  
Calibration Certificate no. AG -- 10 - 1339 / 07.12.2011, SJML Pitesti

### 5. Testing procedure:

The enclosure was mounted on a rigid support, according to the manufacturer's instructions for use (photo 4).

The test was performed on the weak points of the exposed parts of the enclosure of the substation.

The impact energy was 20 J.

Five impacts were applied on each exposed side, using the pendulum hammer.

The impacts were distributed on the faces of the enclosure under test; there were no more than three impacts applied in the surroundings of the same point of the enclosure.

Only one impact was applied at the same point.

After the application of the impacts, the enclosure was inspected.

The paint was not removed; just 1 small depression were observed.

### 6. Test Results:

Clearance and creepage distances remained the same.

The protection degree of the enclosure was maintained.

Operation of control means, handles, was not impaired.

The product passed the test according to IEC 62271-202:2014, clause 6.101.3.





Photo 4. Test set-up for Mechanical Impact Test

— end of test report —

TEST REPORT  
CRAIOVA



000054

Laboratory for Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment - SHIT  
 Address: Str. Prof. Anton Jessen nr. 37, Testing Station B - ob. 101, Str. Gh. Asachi nr.13, Iasi - Testing Station A  
 Authorization Laboratory of 1<sup>st</sup> degree no. 21012, 08. 2010 issued by I.S.C.

APPROVED BY GENERAL MANAGER  
 INCERC "URBAN - INCERC"  
 Associate Professor Dr. Ing. Vasile Meliş  
 Director General  
 V.M.

SR EN ISO/IEC 17025  
 CERTIFICATE OF ACCREDITATION  
 1132

**TEST REPORT NR. 659T - 1/30.07.2014**  
**FOR CLIMATIC TEST ACCORDING TO EN 62271-102,**  
**CLAUSE 6.103 - CLIMATIC TEST UNDER SEVERE ICE CONDITIONS - CLASS 20 mm**  
**CLAUSE 6.104 - CLIMATIC TEST TO EXTREME NEGATIVE TEMPERATURE (-50°C)**

- Order/contract: 101/19.02.2014/ contract no.659T/2014
- Designation of tested object:  
 Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 operated by Motor Drive MD 50
- Customer name : RESEARCH DEVELOPMENT AND TESTING NATIONAL INSTITUTE FOR ELECTRICAL ENGINEERING - ICMET Craiova  
 Customer address: B-dul Decebal no. 116A, Craiova, Cateea Bucuresti no. 144 Tel. 0351 404888, 0351 404 889, Fax: 0351 404 890, 0251 415 482
- Manufacturer: ABB BULGARIA BRANCH SEVLIEVO BULGARIA  
 Manufacturer address: 32 N. PETROV STR. 6400 SEVLIEVO, Bulgaria
- Identification of the test specification or procedure:
  - Climatic test under severe ice conditions class 20 mm, according to: EN 62271-102, clause 6.103 (SR EN 62271-102:2003, clause 6.103) - PTE IH- 19 / 12.01 - URBAN INCERC Iasi
  - Climatic test to extreme negative - 50°C temperature, according to EN 62271-102, clause 6.104.1, EN 68-2:1990+A1:1993+A2:1994 (SR EN 62271-102:2003, clause 6.104.1, SR EN 60068 - 2 - 1:2007 and SR EN 60068 - 1:1995) - PTE IH - 19 / 12.08 - URBAN INCERC Iasi
- Description and identification of tested object:  
 Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021882, 2GPA45010021881
- Date when tested object was received: according to proceedings (F- PG-5.8-01) - PVPP no. 122HS from 14.07.2014 and expedition note ABB Bulgaria Branch Sevlievo/11.07.2014 Laboratory code IHS 324/E1-07.14
- Test date: 15.07.2014 - 25.07.2014

Test Report no.659T-1/30.07.2014, Copy no. 1/5 Page no. 1/3  
 The contents of the present report have been elaborated according to the requirements of SR EN ISO/IEC 17025:2005

9. Description of sampling procedure: Sampling of the test object was performed by the customer at their own risk.

10. Obtained results:  
 Equipment and materials used: climatic room with thermal adjustment, 600m<sup>3</sup>, artificial rain equipment.

10.1. The resistance of the circuit:

Resistance of the circuit (µΩ) - measurement at 100A			
Resistance of the main circuit (µΩ)			
Moment of measurements	Pole A	Pole B	Pole C
Initial	71.2	73.5	70.9
Final	76.6	78.4	78.8
Percentage Increase	6.18 %	8.03 %	8.32 %
Resistance of the earthing switch circuit (µΩ)			
Initial	62.4	58.9	61.4
Final	69.8	65.7	71.2
Percentage Increase	11.66%	11.54%	15.95%

10.2. The drive time cycles of closing and opening of the contact of main circuit:

Cycles	Initial drive time of cycles Nominal Voltage - Normal temperature (s)	Drive time of cycles Maximum Voltage (s)	Drive time of cycles Minimum Voltage (s)	Final drive time of cycles Nominal Voltage - Normal temperature (s)
Open - Close	4.329	4.468	4.639	4.581
	4.208	4.498	4.698	4.522
	4.224	4.563	4.485	4.335
	4.212	Medium value - 4.610	Medium value - 4.574	4.228
	4.377	Medium value - 4.610	Medium value - 4.574	4.412
Medium value	4.27	Medium value - 4.610	Medium value - 4.574	4.331
Percentage Increase:				
extreme negative - 50°C temperature				
Cycles Close - open	4.261	4.475	4.571	4.259
	4.222	4.365	4.502	4.451
	4.219	4.435	4.603	4.378
	4.287	Medium value: 4.432	Medium value: 4.559	4.317
	4.217	Medium value: 4.432	Medium value: 4.559	4.263
Medium value	4.237	Medium value: 4.432	Medium value: 4.559	4.331
Percentage Increase				
2.21%				

ВЪРНО С  
ОПИСАНИЕ

Test Report no.659T-1/30.07.2014, Copy no. 1/5 Page no. 2/3  
 The contents of the present report have been elaborated according to the requirements of SR EN ISO/IEC 17025:2005

10.3. The drive time cycles of closing and opening of the contact of earthing switch circuit:

Cycles	Initial drive time of cycles Nominal Voltage - Normal temperature (s)	Drive time of cycles Maximum Voltage (s)	Drive time of cycles Minimum Voltage (s)	Final drive time of cycles Nominal Voltage - Normal temperature (s)
Open - Close	4.819	4.926	5.034	4.813
	4.828	4.964	5.104	4.908
	4.784	5.012	4.987	4.815
	4.832	Medium value - 4.987	Medium value - 5.042	4.867
	4.867	Medium value - 4.987	Medium value - 5.042	4.905
Medium value	4.828	Medium value - 4.987	Medium value - 5.042	4.882
Percentage Increase:				
1.11%				
Cycles Close - open	4.651	4.976	5.112	4.654
	4.872	4.954	5.099	4.699
	4.899	4.988	5.018	4.923
	4.874	Medium value: 4.978	Medium value: 5.076	4.813
	4.827	Medium value: 4.978	Medium value: 5.076	4.699
Medium value	4.871	Medium value: 4.978	Medium value: 5.076	4.935
Percentage Increase				
1.33%				

- Uncertainty of measurement: Was not requested by the customer.
- Opinions and Interpretations: \* Item 12 is not covered by the RENAR accreditation

Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021881, 2GPA45010021882

**HAS FULFILLED THE TECHNICAL CONDITIONS REQUIRED FOR:**

- functioning in the presence of a layer of transparent ice of 20mm, according to EN 62271-102, clause 6.103 (SR EN 62271-102:2003, clause 6.103). The equipment (the main circuits and earthing switch) may be maneuvered on first operation by means of the motor drive mechanism. No malfunctions of the contact, drive elements and support insulators were detected, as well as no deformations or permanent blocking that might hinder the mechanical or electrical performance of the disconnector with earthing switch.
- functioning to extreme negative - 50°C temperature, according to EN 62271-102, clause 6.104.1, EN 68-2:1990+A1:1993+A2:1994 (SR EN 62271-102:2003, clause 6.104.1, SR EN 60068 - 2 - 1:2007 and SR EN 60068 - 1:1995). The equipment (the main circuits and earthing switch) may be maneuvered, performing the closed-open drive cycles imposed by the standard (three cycles close-open), by means of the motor drive mechanism. No malfunctions of the contact and drive elements, and support insulators, were detected, as well as no deformations or permanent blocking that might hinder the mechanical or electrical performance of the disconnector with earthing switch.

**NOTES:**

- The result of the test refers only to the tested object.
- The test report cannot be partially reproduced without the approval of the laboratory which performed the test.
- The test report is accompanied by the test report no. 659T-1/30.07.2014, 16 pages.

Certified by Branch Manager  
 eng. Constantin Miron, PhD

Verified by Head of HT Laboratory  
 eng. Lydia Miron, PhD

Prepared by Contract handler  
 eng. Constantin Miron, PhD

Test Report no.659T-1/30.07.2014, Copy no. 1/5 Page no. 3/3  
 The contents of the present report have been elaborated according to the requirements of SR EN ISO/IEC 17025:2005

**ANNEX TO TEST REPORT No. 659T -1/ 30.07.2014**

**1. PRODUCT PRESENTATION**

Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021881, 2GPA45010021882 has been assembled in the climatic chamber of the Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of the National Institute for Research and Development in Constructions, Urban Planning and Sustainable Territorial Development "URBAN - INCERC", Iasi Branch and has been verified by experimental means, through tests on its functional behavior when subjected to severe climatic conditions:

- such as the forming of an ice layer of 20 mm, according to EN 62271-102, clause 6.103 (SR EN 62271-102:2003, clause 6.103).
- to extreme negative - 50°C temperature, according to EN 62271-102, clause 6.104.1, EN 68-2:1990+A1:1993+A2:1994 (SR EN 62271-102:2003, clause 6.104.1, SR EN 60068 - 2 - 1:2007 and SR EN 60068 - 1:1995).

**1.1 Product identification (components)**

1) Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145, operated by Motor Drive MD 60  
 3) supporting metallic frame.

Producer: ABB BULGARIA BRANCH SEVLIEVO BULGARIA, 32 N. PETROV STR. 6400 SEVLIEVO, Bulgaria

**1.2 Installation in the climatic chamber of the Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of URBAN - INCERC Iasi Branch**

Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021881, 2GPA45010021882 has been assembled for tests in the climatic chamber of the Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of the "URBAN - INCERC", Iasi Branch, according to the reference technical documentation.

During installation, the following has been verified:

- Overall dimensions;
- dimensions and types of the component subsystems;
- elevations at which the subsystems may be mounted;
- product subassemblies;
- product integrity and recording of possible fissures, deformations or other damages caused by transportation, manipulation, and installation, in order to differentiate between original defects and the ones that have appeared following tests.

The installation and mounting of the Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021881, 2GPA45010021882 in the climatic chamber has been performed according to the normal installation procedures specified by the producers (according to 1HYD980321-011-izp, specification 1HYD300777-B, 1HYD300777-D, drawings 1HYD300777-001, and electrical connection diagram for Motor drive MD 60, fig. 1.1., 1.5 and picture no.1.2).  
 The pictures no. 5 through 9 show Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021881, 2GPA45010021882 assembled in the climatic chamber and during various stages of the test performed to determine its behavior when subjected to the pressure of an ice layer of 20 mm.


030055

REVISIONS		REVISIONS	
No.	Date	Description	By
1	25.06.2014	100% TEST	...
2	25.06.2014	...	...
3	25.06.2014	...	...
4	25.06.2014	...	...
5	25.06.2014	...	...
6	25.06.2014	...	...
7	25.06.2014	...	...
8	25.06.2014	...	...
9	25.06.2014	...	...
10	25.06.2014	...	...

Fig. 1.3 - Specification for Drive Lever Assembly (lower chart)

1HYD300777-D

REVISION C  
C. P. ...



000056




Fig. 1.1 - Three phase Horizontal Centre Break Disconnecter with one Earthing Switch SDF 14k, operated by Motor Drive MD 60




Fig. 1.4 - Detail of Drive Lever Assembly

1HYD300777-B

REVISIONS		REVISIONS	
No.	Date	Description	By
1	25.06.2014	100% TEST	...
2	25.06.2014	...	...
3	25.06.2014	...	...
4	25.06.2014	...	...
5	25.06.2014	...	...
6	25.06.2014	...	...
7	25.06.2014	...	...
8	25.06.2014	...	...
9	25.06.2014	...	...
10	25.06.2014	...	...

Fig. 1.2 - Specification for Drive Lever Assembly

1HYD300777-B




Fig. 1.5 - Electrical connection diagram - Motor drive MD 50




Picture no. 1, 2 - Installation details




Picture no. 3a

Picture no. 3b




Picture no. 4


Pictures no. 3a, 3b, 4 - Witness tube



Picture no. 5 - The disconnecter in open position




Picture no. 6 - The disconnecter in close position



Picture no. 7




Picture no. 8




Picture no. 9

Picture no. 7, 8, 9 - Details of the disconnecter

BSMO C  
CERTIFICATION




000057




Picture no. 10

Picture no. 10 – The disconnecter to extreme negative – 50°C temperature



Picture no. 11 - Dixel system for the monitoring and automatic recording of parameters XWEB 600



Picture 12 -- The controls of close position of circuit of the disconnecter.

2. Installation conditions:

The device has been assembled according to the details in figure no. 1HYD890321-011, specification 1HYD300777-B, 1HYD300777-D, drawing 1HYD300777-001, climatic chamber of the Research and Hydrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment Laboratory of "URBAN - INCERC", Iasi Branch, which has the following characteristics:

- chamber volume 600 m<sup>3</sup>;
- cooling capacity 11500 W;
- attainable temperatures: - 50°C...+70°C;
- ice layer of 0 ... 20 mm measured on a witness tube.

The device has been connected to its own drive mechanism.

3. Measuring equipment and technical means:

The climatic parameters have been measured in the following way:

- Digital thermohygrograph KIMO Instruments, CE nr. 4.8 -12-09-005/2009;
- Digital thermometer Thermo Loger R DigLSensa - 50... +100°C, Calibration Report BC - 308 - 1165/8, 10.2013;
- Micro - ohmmeter RMO 500; 20,4Ω /1mΩ /10mΩ /100mΩ/200mΩ, Calibration Report INM 03.01-476/2009
- Programmable counter PTE-30-CH, 0 + 99 999 s, Calibration Report FACV M 0123.11.2009
- Regulation of the temperature in the climatic chamber – automatically by means of Dual temperature and humidity regulators, Bizer compressor group and Dixel system for the monitoring and automatic recording of parameters XWEB 600, Calibration Report INM BC - 308-1045/2011;

4. Functional requirements during and after the climatic test. Acceptance criteria

Throughout the climatic test, the disconnecter with earthing switch has been fulfilling the conditions in fig.1.1 as well as the specifications at point 2, with no voltage applied to its terminals.

The disconnecter with earthing switch fulfill the acceptance criteria of the climatic sequence imposed if:

- 4A- For severe climatic conditions such as the forming of an ice layer of 20 mm, according to EN 62271-102, clause 6.103 (SR EN 62271-102:2003, clause 6.103):
- 1) prior to the operation under severe ice conditions, the disconnecter with earthing switch fulfill the routine mechanical operating test according to EN 62271-102, clause 6.103.3 – g;
  - 2) on first operation, the disconnecter with earthing switch performed the complete opening and closing of contacts
  - 3) no sudden maneuvers are performed on the disconnecter with earthing switch's contacts and the continuity of the circuit is maintained during the test, in the closed and open positions of the disconnecter switch;
  - 4) no damages are inflicted which can hinder the mechanical or electrical performance of the disconnecter with earthing switch;
  - 5) the position of the contacts is maintained – closed/open;
  - 6) the functioning of the kinematic system is maintained;
  - 7) the dielectric properties of the components of the drive mechanism's electric diagram are maintained

4B- For severe climatic conditions to extreme negative – 50°C temperature, according to EN 62271-102, clause 6.104.1, EN 68-2:1990+A1:1993+A2:1994 (SR EN 62271-102:2003, clause 6.104.1, SR EN 60068 - 2 - 1:2007 and SR EN 60068 - 1: 1995):

- 1) prior to the operation under extreme negative – 50°C temperature conditions, the disconnecter with earthing switch fulfill the routine mechanical operating test according to EN 62271-102, clause 6.103.3 – g;
- 2) it is possible to perform the complete drive cycles of closing and opening of the disconnecter with earthing switch, imposed by the standard (complete three operating cycles, at a minimum and maximum supply energy), using the equipment's own drive mechanism powered by maximum and minimum voltage, respectively;
- 3) no sudden maneuvers are performed on the disconnecter with earthing switch's contacts and the continuity of the circuit is maintained during the test, in the closed and open positions of the disconnecter with earthing switch;
- 4) no damages are inflicted which can hinder the mechanical or electrical performance of the disconnecter with earthing switch;
- 5) the position of the contacts is maintained – closed/open;
- 6) the functioning of the kinematic system is maintained;

7) the dielectric properties of the components of the drive mechanism's electric diagram are maintained

6. Conditioning of the equipment

The device has been kept at the parameters of the environment in the climatic chamber (cca 20°C) for a minimum of 24 hours. During this period, the routine mechanical operating test has been performed.

6. Test phases

6.A Test phases for severe climatic conditions such as the forming of an ice layer of 20 mm, according to EN 62271-102, clause 6.103 – according to the diagram no.1

Phase no. 1 – Three phase Horizontal Centre Break Disconnecter with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021881, 2GPA45010021882 in open position

- Cooling of the climatic chamber down to +2°C ± 1°C and keeping of the device inside for at least 6 hours.
- Ice formation according to EN 62271-102, clause 6.103 (SR EN 62271-102:2003, clause 6.103), at a temperature of +2°C ... -7°C for cca 8 hours.
- Maintaining at a temperature of -7°C ± 1°C for cca 5 hours.
- Performing of the closing maneuver using the device's own drive mechanism of circuits and the opening maneuver using the device's own drive mechanism for the disconnecter with earthing switch.

Phase no. 2 – Three phase Horizontal Centre Break Disconnecter with one Earthing Switch SDF 145 serial number 2GPA45040000087, operated by Motor Drive MD 60 serial number 2GPA45010021881, 2GPA45010021882 in closed position.

- Cooling of the climatic chamber down to +2°C ± 1°C and keeping of the device inside for at least 6 hours.
- Ice formation according to EN 62271-102, clause 6.103 (SR EN 62271-102:2003, clause 6.103), at a temperature of +2°C ... -7°C for cca 8 hours.
- Maintaining at a temperature of -7°C ± 1°C for cca 5 hours.
- Performing of the opening maneuver using the device's own drive mechanism of circuits and the closing maneuver using the device's own drive mechanism for the disconnecter with earthing switch.

Phase no.3 – Restoring of the normal environment conditions and verification the values of the drive time and of the contact resistance of the circuit.

OBSERVATIONS – the thickness of the ice layers formed was an average of 20 ... 25 mm, as measured on a witness tube.

ВЕРНО С  
ОПРЕДЕЛЕНА




Diagram no.1 – Diagram of the climatic test under the circumstances of a forming ice layer of 20 mm – corresponding to pictures 3 ... 9.

000058

**Experimental results**


In order to verify the integrity of the equipments before the beginning of the climatic test, we have performed a general inspection to confirm that the equipment had been assembled according to the requirements of the company standard (positions, dimensions, connections, gauging) and that no damage had been caused during assembling (insulator breaking, remaining deformations), and to ensure a complete maneuvering Closed - Open cycle.

Throughout the experimental program, we have observed the general state, structural integrity and functional behavior of the products in order to be able to identify possible defects or malfunctions. Consequently, at the end of each experimental phase, we have inspected the equipment's state and we have performed the necessary maneuvers according to the verification procedures.

Our observations of the general state, structural integrity and functional behavior of the products during the program of experimental testing under severe ice conditions (forming ice layer of 20 mm) prove that the device fulfils the acceptance criteria according to EN 62271-102, clause 6.103 (SR EN 62271-102:2003, clause 6.103), as follows:

- 1) on first operation, the disconnector with earthing switch performed the complete opening and closing of contacts;
- 2) the drive time is within the limits 4.2 - 5.2 s;
- 3) no sudden maneuvers were performed on the earthing switch's contacts and the continuity of the circuit was maintained during the test, in the closed and open positions of the disconnector with earthing switch;
- 4) no damages were inflicted which could have hindered the mechanical or electrical performance of the disconnector with earthing switch;
- 5) the position of the contacts was maintained - closed/open;
- 6) the functioning of the kinematic system was maintained;
- 7) the dielectric properties of the components of the drive mechanism's electric diagram were maintained.
- 8) The value of contact resistance - The increased resistance after the environmental test is in keeping with the max limit of 20% imposed by SR EN 62271-102, clause 6.102.3.2.

6B - Test phases for severe climatic conditions to extreme negative - 50°C temperature, according to EN 62271-102, clause 6.104.1 - according to the table and the diagram no. 2. Diagram of the climatic test under the circumstances of the extreme negative - 50°C temperature, according to EN 62271-102, clause 6.104.1.



Phases	Initial	Cooling	Maintenance	Steady-state regime	C-O Maneuvers	Reversion	Final
Nr.	1	2	3	4	5	6	7
$T_{med}$	+18,5		-50,1	-50,1	-50,1		+17
$\Delta T_{es}$	$\pm 1,5$		$\pm 1,8$	$\pm 1,8$	$\pm 1,8$		$\pm 1,2$
$\delta T / \Delta t$		-3				11,4	
$\varphi_r$	65		42	42	42		61
$\Delta t$		19,5	2	12	1	5	

**Legend:**

- $T_{med}$  - average temperature in the climatic chamber
- $\Delta T_{es}$  - maximum deviation of temperature on the chamber's height
- $\delta T / \Delta t$  - speed of temperature variation (°C/h)
- $\varphi_r$  - relative humidity of the air (%)
- $\Delta t$  - phase duration (h)

Phase 1 - Initial phase of maintaining the equipment at a temperature of 18 °C  $\pm$  1,5°C, for cca 5 hours. During this period, the routine mechanical operating test has been performed.

Phase 2,3 - cooling of the climatic chamber down to - 50°C  $\pm$  1,8°C cca 20 hours and keeping of the equipment inside for at least of 2 hours.

Phase 4 - steady-state regime at an extreme negative temperature of - 50°C, according to EN 62271-102, clause 6.104.1 EN 68-2:1990+A1:1993+A2:1994 (SR EN 62271-102:2003, clause 6.104.1, SR EN 60068-2-1:2007, SR EN 60068-1:1995), for cca 12 hours

**Phase 5**

- a. Performing the complete drive cycles of closing and opening of the disconnector with earthing switch, imposed by the standard, using the equipment's own drive mechanism powered by maximum and minimum voltage, respectively, at the same extreme negative temperature of - 50°C  $\pm$  1,8°C, cca 1 hour
- b. Verifying the values of the drive time.

Phase 6 - Reversion of the chamber temperature to 17°C for cca 5 hours and verification of the contact resistance of main circuit and the values of the drive time.

Three phase Horizontal Centre Break Disconnector with one Earthing Switch SDF 145 aerial number ZGPA4504000087, operated by Motor Drive MD 60 serial number ZGPA45010021681, ZGPA45010021882 has been assembled in the climatic chamber according to the details in fig. 1.1, in a closed position.

**Experimental results**

In order to verify the integrity of the equipments before the beginning of the climatic test, we have performed a general inspection to confirm that the equipment had been assembled according to the requirements of the company standard (positions, dimensions, connections, gauging) and that no damage had been caused during assembling (insulator breaking, remaining deformations), and to ensure a complete maneuvering Closed - Open cycle.

Throughout the experimental program, we have observed the general state, structural integrity and functional behavior of the products in order to be able to identify possible defects or malfunctions. Consequently, at the end of each experimental phase, we have inspected the equipment's state and we have performed the necessary maneuvers according to the verification procedures. Our observations of the general state, structural integrity and functional behavior of the products

during the program of experimental testing under the extreme negative - 50°C temperature, prove that the device fulfils the acceptance criteria according EN 62271-102, clause 6.104.1 (SR EN 62271-102:2003, clause 6.104.1, SR EN 60068-2-1:2007, SR EN 60068-1:1995), as follows:

- 1) we have been able to perform the complete three drive cycles of closing and opening of the disconnector with earthing switch imposed by the standard, using the equipment's own drive mechanism powered by maximum and minimum voltage, respectively;  
 $U_{nominal} = 110VDC$ ,  
 $U_{max} = U_{nom} + 15\% = 127VDC$ ,  
 $U_{min} = U_{nom} - 20\% = 88VDC$
- 2) the drive time is within the limits value 4.2 - 4.8 s;
- 3) no sudden maneuvers were performed on the earthing switch's contacts and the continuity of the circuit was maintained during the test, in the closed and open positions of the disconnector with earthing switch;
- 4) no damages were inflicted which could have hindered the mechanical or electrical performance of the disconnector with earthing switch;
- 5) the position of the contacts was maintained - closed/open;
- 6) the functioning of the kinematic system was maintained;
- 7) the dielectric properties of the components of the drive mechanism's electric diagram were maintained.
- 8) The value of contact resistance - The increased resistance after the environmental test is in keeping with the max limit of 20% imposed by SR EN 62271-102, clause 6.102.3.2.

All test phases have been carried out in the presence and with the technical assistance of the producer ABB BULGARIA Branch Servizo and ICMET Craiova.

Laboratory for Research and Hygrothermal, Climatic, Mechanical and Seismic Testing for Constructions, Installations and Equipment, Iasi Branch, Romania


Head of laboratory: eng. Livia Miron, PhD

Test responsible person: eng. Constantin Miron, PhD

Chief of test division: eng Livia Miron, PhD

Laboratory A-Q responsible person: eng Alina Cobzaru

ROBNO C  
CRAIOVA



**ASOCIAȚIA DE ACREDITARE DIN ROMÂNIA - RENAR**

București, Calea Vitan nr. 242, sector 3, cod 031301  
CFR RO 4311680



RENAR este semnatul al EA-MLA pentru încercări.

**CERTIFICAT DE ACREDITARE**  
Nr. LI 320

Asociația de Acreditare din România - RENAR, fiind recunoscută ca Organism Național de Acreditare prin OG 23/2009, prin prezentul certificat atestă că organizația:

**Institutul Național de Cercetare Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă "URBAN-INCERC"**

București, Șos. Pantelimon nr. 286, sector 2  
prin

**LABORATOARE "URBAN-INCERC"**

1. Laborator de Cercetare și Încercări Materiale și Elemente de Construcții - IME
2. Laborator de Cercetare și Încercări Instalații, Materiale și Echipamente - LI
3. Laborator de Cercetare și Încercări pentru Materiale, Elemente și Structuri de Construcții - ESQ
4. Laborator de Cercetare și Încercări pentru Protecția în Căminare și la Gardare Bioelectrică a Construcțiilor - POC
5. Laborator de Cercetare și Încercări Produs Polimeric și Plăci - LPP
6. Laborator de Cercetare și Încercări Hidraulică-Civilitate, Mecanică și Băncărie pentru Construcții, Instalații și Echipamente - BS
7. Laborator de Cercetare și Încercări Anvelope Construcții - AC
8. Laborator de Cercetare și Încercări "Săcurizată la Foc a Construcțiilor" - FOC

Îndeplinește cerințele SR EN ISO/CEI 17025:2005 și este competentă să efectueze activități de ÎNCERCĂRI, așa cum se detaliază în Anexele la prezentul certificat de acreditare.

Această acreditare este menținută cu condiția îndeplinirii în mod continuu a criteriilor de acreditare stabilite de Asociația de Acreditare din România - RENAR.

Prezentul certificat este însoțit de Anexele nr. 1 și nr. 6 (cele 3 pagini fiecare), nr. 2, nr. 3, nr. 4, nr. 5, nr. 7 și nr. 8 (cele 1 pagină fiecare), parte integrantă a acestuia.

Pentru verificarea validității certificatului de acreditare, inclusiv a Anexelor, se consultă website-ul RENAR, www.renar.ro.

Data acreditării inițiale: 20.12.2004

Data reînnoirii acreditării: 18.12.2014

Data expirării acreditării: 17.12.2018

**DIRECTOR GENERAL** PREȘEDINTE AL CONSILIULUI DE ACREDITARE

Cătălina Viorica NEAGU

dr. ing. Dumitru DINU

Reproducerea parțială a prezentului certificat este interzisă.

Anexa nr. 1 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 1: 18.12.2014

Laborator de Cercetare și Încercări Materiale și Elemente de Construcții - IME  
Cluj-Napoca, Calea Florești nr. 117, Județul Cluj

apartinand de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă "URBAN-INCERC" - Sucursala Cluj-Napoca

Nr. crt.	Tipul / Denumirea încercării	Materiale / produs	Documentul de referință
1	Încercări dimensionale		
1	Determinarea granulozității. Analiza granulometrică prin câștig	Agregate	SR EN 933-1:2012 PTE-IME-3302.01
2	Determinarea formei granulelor. Coeficient de abraziune	Agregate	SR EN 933-3:2012 PTE-IME-3302.02
3	Determinarea formei particulelor. Coeficient de formă	Agregate	SR EN 933-4:2008 PTE-IME-3302.15
4	Evaluarea părților fine. Determinarea echivalenței de nisip	Agregate	SR EN 933-8:2012 PTE-IME-3302.04
5	Evaluarea părților fine. Încercare cu abstru de nisip	Agregate	SR EN 933-9:AT:2013 PTE-IME-3302.16
6	Determinarea lungimii și lățimii	Produce termozolante	SR EN 822:2013 PTE-IME-1305.01
7	Determinarea grosimii	Produce termozolante caștile utilizate la cărți Piese termozolante pentru părțile ferante	SR EN 828:2013 PTE-IME-1305.13 SR EN 12431:2013 PTE-IME-1305.12
8	Determinarea perpendicularității	Produce termozolante	SR EN 824:2013 PTE-IME-1305.14
9	Determinarea planității	Produce termozolante	SR EN 828:2013 PTE-IME-1305.15
10	Determinarea stabilității dimensionale în condiții normale și constante de laborator (23 grade C și 50% umiditate relativă)	Produce termozolante	SR EN 1603:2013 PTE-IME-1305.04
11	Determinarea stabilității dimensionale în condiții specifice de temperatură și umiditate	Produce termozolante	SR EN 1604:2013 PTE-IME-1305.05
12	Încercări fizice		
12	Determinarea coeficientului de elasticitate coherente. Proiect de coșturi în agregate	Agregate	SR EN 933-7:2001 PTE-IME-3302.03
13	Determinarea masei volumice în vac și la porozități în agregate	Agregate	SR EN 1097-3:2002 PTE-IME-3302.06
14	Determinarea masei reale și a coeficientului de absorbție a apei	Agregate	SR EN 1097-6:2013 PTE-IME-3302.07
15	Determinarea procentului de suprafață concasă și sfărâmată din agregate groșiere	Agregate	SR EN 933-5:2001 SR EN 933-5:2001/A1:2006 PTE-IME-0201.01
16	Determinarea alunecării	Adeziți pentru plăci ceramice	SR EN 1308:2008 PTE-IME-1017.02
17	Determinarea absorbției apei: - de scurtă durată prin imersiune parțială - de lungă durată prin imersiune	Produce termozolante	SR EN 1605:2013 PTE-IME-1305.09 SR EN 12087:2013 PTE-IME-1305.16
18	Determinarea deformării în condiții specifice de încălzire la compresie și de temperatură	Produce termozolante	SR EN 1605:2013 PTE-IME-1305.06
19	Determinarea permeabilității la aer	Ferestre și uși	SR EN 1026:2001 PTE-IME-1001.06

Anexa nr. 1 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 1: 18.12.2014

Nr. crt.	Tipul / Denumirea încercării	Materiale / produs	Documentul de referință
20	Determinarea elasticității la apă	Ferestre și uși	SR EN 1327:2001 PTE-IME-1001.07
21	Încercarea de tasare	Beton proaspăt	SR EN 12350-2:2009 PTE-IME-0401.02
22	Determinarea densității	Beton proaspăt Beton întărit	SR EN 12350-6:2009 PTE-IME-0401.03 SR EN 12350-7:2009 PTE-IME-0402.07
23	Determinarea contracției axiale a betonului întărit	Beton	SR 2833:2009 PTE-IME-0402.06
24	Determinarea permeabilității la vapori de apă a sistemelor compozite de izolare termică la exterior (ETICS)	Produce termozolante	SR EN ISO 7783:2012 PTE-IME-4701.10
25	Determinarea rezistenței termice prin metoda termofluometrică la produse cu rezistență termică mare și medie	Produce termozolante	SR EN 12667:2002, pol.7.3.5.2 PTE-IME-6701.04
26	Determinarea permeabilității la apă lichidă a suprafeței sistemului - ETICS	Produce termozolante	SR EN 1062-3:2005 PTE-IME-2005.06
27	Încercări mecanice		
27	Determinarea rezistenței la sfărâmare. Metoda Los Angeles	Agregate	SR EN 1097-2:2010 PTE-IME-3302.06
28	Determinarea rezistenței la uzură (micro-Deval)	Agregate	SR EN 1097-1:2011 PTE-IME-3302.11
29	Determinarea timpului deschis (opacitate)	Adeziți pentru plăci ceramice	SR EN 1346:2003 PTE-IME-1017.01
30	Determinarea aderenței prin metode pentru adeziți pe bază de țesături organice	Adeziți pentru plăci ceramice	SR EN 1346:2003 PTE-IME-1017.04
31	Determinarea deformării la încălzire prin încercare pentru adeziți pe bază de țesături minerale și cărămidă	Adeziți pentru plăci ceramice	SR EN 12002:2009 PTE-IME-1017.05
32	Determinarea compozității la compresie	Produce termozolante	SR EN 828:2013 PTE-IME-1305.02
33	Determinarea rezistenței la tracțiune perpendiculară la fețe	Produce termozolante	SR EN 1607:2013 PTE-IME-1305.07
34	Determinarea caracteristicii la încovărire	Produce termozolante	SR EN 12668:2013 PTE-IME-1305.10
35	Determinarea rezistenței la eșecul de înghet-dezgheț	Produce termozolante	SR EN 12661:2013 PTE-IME-1305.11
36	Rezistența la încălzire din vânt	Ferestre și uși	SR EN 12211:2001 PTE-IME-1001.08
37	Determinarea rezistenței la încovărire stațică	Lăși balante sau pivotante	SR EN 948:2002 PTE-IME-1001.12
38	Determinarea rezistenței la răsucire stațică	Ferestre	SR EN 14609:2004 PTE-IME-1001.13
39	Determinarea rezistenței la compresie	Beton întărit Ciment	SR EN 12390-3:2009 SR EN 12390-3:2009/AC:2011 PTE-IME-0402.02 SR EN 196-1:2006 PTE-IME-3301.01
40	Determinarea rezistenței la încovărire	Beton întărit Ciment	SR EN 12390-5:2009 PTE-IME-0402.15 SR EN 196-1:2006 PTE-IME-3301.01

Anexa nr. 1 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 1: 18.12.2014

Nr. crt.	Tipul / Denumirea încercării	Materiale / produs	Documentul de referință
41	Rezistența la îndoire prin despicare a epruvelelor	Beton întărit	SR EN 12390-5:2010 PTE-IME-0402.16
42	Determinarea aderenței de pătrundere a apei sub presiune	Beton întărit	SR EN 12390-8:2009 PTE-IME-0402.03
43	Determinarea rezistenței la înghet-dezgheț prin măsurarea rezistenței la compresie	Beton	SR 3516:2009 PTE-IME-0402.04
44	Determinarea timpului de priză	Ciment	SR EN 196-3:AT:2009 PTE-IME-3301.02
45	Determinarea stabilității	Ciment	SR EN 106-3:AT:2009 PTE-IME-3301.03
46	Determinarea rezistenței la impact a sistemelor compozite de izolare termică la exterior (ETICS)	Produce termozolante	SR EN 13467:2004 PTE-IME-2005.03
47	Determinarea rezistenței la smulgere a sistemelor compozite de izolare termică la exterior (ETICS)	Produce termozolante	SR EN 13496:2003 PTE-IME-2005.04
48	Determinarea caracteristicilor mecanice ale plăcilor de fibră de sticlă	Produce termozolante	SR EN 13496:2003 PTE-IME-2005.05
49	Determinarea rezistenței la penetrare a sistemelor compozite de izolare termică la exterior (ETICS)	Produce termozolante	SR EN 13468:2004 PTE-IME-2005.07
50	Determinarea aderenței prin tracțiune a adeziivilor și a stratului de bază al materialului termozolant	Produce termozolante	SR EN 13494:2003 PTE-IME-4701.03
51	Încercarea la tracțiune. Metoda de încercare la temperatura ambiantă	Materiale metalice (otel-beton, benză, plăci, table, țesături, țesături metalice)	SR EN ISO 6892-1:2010 PTE-IME-0401.04
52	Încercări chimice		
52	Determinarea ecosolubilității	Lemn	SR 652:2009 PTE-IME-3301.01
53	Determinarea caracteristicilor termice și de stabilitate a agregatelor încercate cu bușet de incalzire	Agregate	SR EN 1357-2:2010 PTE-IME-3302.08
64	Determinarea unor soluții la apă. Metoda Volhard	Agregate	SR EN 1744-1:AT:2013 PTE-IME-3302.09

**DIRECTOR GENERAL**  
Cătălina Viorica NEAGU





Anexa nr. 2 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 2: 18.12.2014

Laborator de Cercetare și Încercări Instalații, Materiale și Echipamente - LII  
București, Șos. Pantelimon nr. 266, sector 2

aparținând de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă „URBAN – INCERC” - Sucursala INCERC București

Nr. crt.	Tipul / Denumirea încercării	Material / produs	Documentul de referință
<b>Încercări termice</b>			
1	Determinarea puterii termice și temperaturii medii la suprafețe	Radiatoare și convectoare Panouri radiante de plăci	SR EN 442-2:2002 SR EN 442-2:2002/A1:2002 SR EN 442-2:2002/A2:2004 SR EN 442-2:2002/C91:2007 PTE-IB-21.7.a SR EN 14037-2:2004 PTE-IB-21.8.a SR EN 14037-3:2004 PTE-IB-21.8.b
<b>Încercări mecanice</b>			
2	Verificarea rezistenței (elasticității) la presiune	Radiatoare și convectoare Panouri radiante de plăci	SR EN 442-1:2000 SR EN 442-1:2000/A1:2004 PTE-IB-21.3.a SR EN 14037-1:2004 PTE-IB-21.6.e
<b>Încercări fizice</b>			
3	Determinarea proprietăților de transmisie a vaporilor de apă	Produce termoizolante, folii	SR EN 12069:2013 PTE-IL-23.1.a
4	Determinarea densității aparente	Produce termoizolante	SR EN 1602:2013 PTE-IL-23.1.b
5	Determinarea dimensiunii inițiale a eșantionilor de încercare	Produce termoizolante	SR EN 12665:2013 PTE-IL-23.1.b
6	Determinarea rezistenței termice cu metoda plăcii calde gardate	Produce termoizolante plane cu rezistență termică mare și medie Produce termoizolante plane ușoare cu rezistență termică mare și medie Produce plane uscate cu rezistență termică medie și mică	SR EN 12667:2002 PTE-IL-23.1.b SR EN 12639:2002 PTE-IL-23.1.b SR EN 12664:2002 PTE-IL-23.1.b

DIRECTOR GENERAL  
Cătălina Viorica NEAGU  
Șos. Pantelimon nr. 266, sector 2  
București

Anexa nr. 3 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 3: 18.12.2014

Laborator de Cercetare și Încercări pentru Materiale, Elemente și Structuri de Construcții – ESC

București, Șos. Pantelimon nr. 266, sector 2

aparținând de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă „URBAN – INCERC” – Sucursala INCERC București

Nr. crt.	Tipul / Denumirea încercării	Material / produs	Documentul de referință
<b>Încercări dimensionale</b>			
1	Determinarea dimensiunilor	Elemente pentru zidărie	SR EN 772-16:2011 PTE-ESC-01
<b>Încercări fizice</b>			
2	Determinarea densității aparente	Cărămidă, blocuri ceramice	SR EN 772-13:2001 PTE-ESC-02
3	Determinarea permeabilității la aer	Ferestre și uși	SR EN 1078:2001 PTE-ESC-23
4	Determinarea etanșității la apă	Ferestre și uși	SR EN 1077:2001 PTE-ESC-24
<b>Încercări mecanice</b>			
5	Determinarea rezistenței la compresune	Elemente pentru zidărie Zidărie	SR EN 772-1:2011 PTE-ESC-04 SR EN 1052-1:2001 PTE-ESC-05
6	Determinarea rezistenței la încovășire din vânt	Ferestre și uși	SR EN 12211:2001 PTE-ESC-25
7	Încercarea la tracțiune	Bară, țesătură țesută și șarnă pentru armarea betonului	PTE-ESC-20 SR EN ISO 15630-1:2011
8	Încercarea la îndoire	Bară, țesătură țesută și șarnă pentru armarea betonului	SR EN ISO 15630-1:2011 PTE-ESC-21

DIRECTOR GENERAL  
Cătălina Viorica NEAGU  
Șos. Pantelimon nr. 266, sector 2  
București

Anexa nr. 4 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 4: 18.12.2014

Laborator de Cercetare și Încercări pentru Protecția la Coroziune și Degradare Biologică a Construcțiilor - PCC

București, Șos. Pantelimon nr. 266, sector 2

aparținând de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă „URBAN – INCERC” – Sucursala INCERC București

Nr. crt.	Tipul / Denumirea încercării	Material / produs	Documentul de referință
<b>Încercări fizice</b>			
1	Determinarea densității	Vopsele, lacuri și produse similare	SR EN ISO 2511-1:2011 PTE-PCC-01
2	Determinarea conținutului de substanță volatilă	Vopsele, lacuri și produse similare	SR EN ISO 3251:2008 PTE-PCC-02
3	Determinarea rezistenței la umiditate. Condenșarea condensului	Vopsele, lacuri și produse similare	SR EN ISO 6270-1:2002 PTE-PCC-03
<b>Încercări chimice</b>			
4	Determinarea rezistenței la încălzire a) Metoda prin imersie b) Metoda pelet	Vopsele, lacuri și produse similare	SR EN ISO 2812-1:2007 SR EN ISO 2812-4:2007 PTE-PCC-10
5	Încercări la corozivitate în atmosferă artificială. Determinarea rezistenței la ceață sărăcă neagră	Metale și aliaje, acoperiri metalice (anodice și catodice), acoperiri organice prin oxidare anodică, acoperiri organice pe materiale metalice	SR EN ISO 9227:2012 PTE-PCC-07
<b>Încercări dimensionale</b>			
6	Determinarea grosimii peliculii. Metoda magnetică	Vopsele, lacuri și produse similare	SR EN ISO 2808:2007 PTE-PCC-03
<b>Încercări mecanice</b>			
7	Determinarea durității peliculii. Încercarea de aderență a peliculii la suport	Vopsele, lacuri și produse similare	SR EN ISO 1522:2007 PTE-PCC-04
8	Încercarea la carptaj	Vopsele, lacuri și produse similare	SR EN ISO 2409:2013 PTE-PCC-05

DIRECTOR GENERAL  
Cătălina Viorica NEAGU  
Șos. Pantelimon nr. 266, sector 2  
București

Anexa nr. 5 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 5: 18.12.2014

Laborator de Cercetare și Încercări Produse Polimerice și Finisaje – LPPF

București, Șos. Pantelimon nr. 266, sector 2

aparținând de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă „URBAN – INCERC” – Sucursala INCERC București

Nr. crt.	Tipul / Denumirea încercării	Material / produs	Documentul de referință
<b>Încercări mecanice</b>			
1	Determinarea proprietăților de tracțiune	Materiale plastice	SR EN ISO 627-1:2012 SR EN ISO 627-2:2012 SR EN ISO 627-3:2000 SR EN ISO 627-3:2000/AC:2006 SR EN ISO 627-4:2000 PTE-LPPF-09
2	Determinarea proprietăților de încovășire	Materiale plastice Produce termoizolante (polistiren expandat, spumă poliuretanică) Mortare pentru zidărie	SR EN ISO 178:2011, Metoda A SR EN ISO 478:2011/A1:2013 PTE-LPPF-10 SR EN 12069:2013 PTE-LPPF-10 SR EN 1015-11:2002 SR EN 1015-11:2002/A1:2007 PTE-LPPF-10
3	Determinarea comportării la compresune	Produce termoizolante (polistiren expandat, spumă poliuretanică) Mortare pentru zidărie Lemn laminat învelit	SR EN 826:2013 PTE-LPPF-11 SR EN 1628:2007 PTE-LPPF-11 SR EN 1015-11:2002 SR EN 1015-11:2002/A1:2007 PTE-LPPF-11
4	Determinarea aderenței	Chituri de etanșare Adesivi pentru plăci ceramice	SR EN 1278-4:2003 PTE-LPPF-16 SR EN 1348:2008 PTE-LPPF-16
5	Încercarea la carptaj	Lacuri și vopsele	SR EN 1278-4:2003 PTE-LPPF-19
6	Determinarea rezistenței la forțarea sub sarcină concentrată	Plăci naturale	SR EN 1237:2007 PTE-LPPF-20
7	Încercarea de perforare statică (CBR)	Geotextile și produse înrudite	SR EN ISO 12335:2007 PTE-LPPF-23
<b>Încercări fizice</b>			
8	Determinarea absorbției de apă : - de scurtă durată prin imersie parțială - de lungă durată prin imersie	Produce termoizolante	SR EN 1609:2013 SR EN 12087:2013 PTE-LPPF-25
9	Determinarea etanșității la apă	Fol flexibilă hidroizolantă	SR EN 1528:2008 PTE-LPPF-26

DIRECTOR GENERAL  
Cătălina Viorica NEAGU  
Șos. Pantelimon nr. 266, sector 2  
București

Anexa nr. 6 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 6: 18.12.2014

Laborator de Cercetare și Încercări Hidrotermice-Climatice, Mecanice și Seismice pentru Construcții, Instalații și Echipamente - IHS

Iași, Str. Prof. Anton Sesan nr. 37, Județul Iași

aparținând de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă „URBAN – INCERC” - Sucursala Iași

Nr. crt.	Tip/Denumirea încercării	Material / produs	Documentul de referință
	Încercări dimensionale		
1	Determinarea lungimii, așmii și înălțimii	Fol flexibilă hidroizolantă. Fol hidroizolantă bituminosă pentru acoperiș	SR EN 1844-1:2003 PTE IHS-0/1.12
2	Determinarea dimensiunilor	Elemente pentru zidărie Elemente metalice ale cadrului pentru sisteme de penouri de gips carton	SR EN 772-16:2011 PTE IHS-0/1.01 SR EN 14185:2005, pct. 5.2 SR EN 14185:2005/A1:2008 PTE IHS-10/04.02
	Încercări fizice		
3	Determinarea densității	Elemente pentru zidărie din ceramică până la beton înalt	SR EN 772-13:2011 PTE IHS-0/1.02 SR EN 12390-3:2009 PTE IHS-0/0/7
4	Determinarea rezistenței termice cu ajutorul metodei plăcii calde gardate și al metodei termocometrice	Probusă cu rezistență termică mare și medie / Produse termoizolante destinate utilizării în clădiri	SR EN 8687:2002 PTE IHS-0/04.01
5	Determinarea conductivității termice	Materiale de construcție din gips carton	SIAS 5912-59 PTE IHS-6/03.09
6	Determinarea indicelui de pătrundere a umidității și măsurarea temperaturii punctului de rouă	Elemente de țevă izolantă	SR EN 1278-2:2004, pct. 5 și Anexa A PTE IHS-0/14.05 PTE IHS-0/14.01
7	Cercetările fizice ale rezistenței la tracțiune	Elemente de țevă izolantă	SR EN 1278-4:2003, pct. 5 PTE IHS-0/14.08
8	Determinarea propriilor peșteri / Metoda prin cântărire	Vopsala și lacuri	SR EN ISO 2828:2007 PTE IHS-0/02.01-02
9	Determinarea etanșității de apă - de lungă durată prin imersiune - de scurtă durată prin imersiune parțială	Produse termoizolante destinate utilizării în clădiri	SR EN 12667:2013 PTE IHS-0/08.05 SR EN 1269:2013 PTE IHS-0/09.05.01
10	Funcționarea în condiții severe de formare a gheții a) Condiționare b) Testare (înaltă, în timpul condiționării și după condiționare)	Aparatul de înaltă tensiune / Separatoare și separatoare de legare la pământ de înaltă tensiune și de curent alternativ	SR EN 62271-102:2003, pct. 6.103 SR EN 62271-102:2003/A1:2012 SR EN 62271-102:2003/A2:2013 SR EN 62271-102:2003/A3:2014 SR EN 62271-102:2003/AC2005:2014
11	Funcționarea la limita de temperatură a) Condiționare b) Testare (înaltă, în timpul condiționării și după condiționare)	Aparatul de înaltă tensiune / Separatoare și separatoare de legare la pământ de înaltă tensiune și de curent alternativ	SR EN 62271-102:2003, pct. 6.104 SR EN 62271-102:2003/A1:2012 SR EN 62271-102:2003/A2:2013 SR EN 62271-102:2003/A3:2014 SR EN 62271-102:2003/AC2005:2014

Anexa nr. 6 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 6: 18.12.2014

Nr. crt.	Tip/Denumirea încercării	Material / produs	Documentul de referință
			SR EN 62271-1:2003, pct. 6.4.17.3 SR EN 62271-1:2003/A1:2012 PTE IHS-18/12.03
12	Încercări de mediu. Încercarea A la frig a) Condiționare b) Testare (înaltă, în timpul condiționării și după condiționare)	Arșamburi de aparat de joasă tensiune - dulapuri și cofrete (Structuri mecanice pentru echipamente electronice-carcase pentru utilizare în exterior)	SR EN 60068-2-1:2007 SR EN 61439-1:2012, pct. 11.9 PTE IHS-18/12.02
13	Încercări de mediu. Încercarea B: Căldură uscată a) Condiționare b) Testare (înaltă, în timpul condiționării și după condiționare)	Arșamburi de aparat de joasă tensiune - dulapuri și cofrete (Structuri mecanice pentru echipamente electronice-carcase pentru utilizare în exterior)	SR EN 60068-2-2:2008 SR EN 61439-1:2012, pct. 11.9 PTE IHS-18/12.03
14	Încercări de mediu. Încercarea N - variații de temperatură a) Condiționare b) Testare (înaltă, în timpul condiționării și după condiționare)	Arșamburi de aparat de joasă tensiune - dulapuri și cofrete (Structuri mecanice pentru echipamente electronice-carcase pentru utilizare în exterior)	SR EN 60068-2-14:2010 SR EN 61439-1:2012, pct. 11.9 PTE IHS-18/12.06
15	Încercări de mediu. Încercarea D: Căldură directă umedă a) Condiționare b) Testare (înaltă, în timpul condiționării și după condiționare)	Arșamburi de aparat de joasă tensiune - dulapuri și cofrete (Structuri mecanice pentru echipamente electronice-carcase pentru utilizare în exterior)	SR EN 60068-2-30:2008 SR EN 60068-3-4:2003 SR EN 61439-1:2012, pct. 11.9 PTE IHS-18/12.04
16	Încercări de mediu. Încercarea C: Rezistența acțiunii agresive la rău și soarelui a) Condiționare b) Testare (înaltă, în timpul condiționării și după condiționare)	Arșamburi de aparat de joasă tensiune - dulapuri și cofrete (Structuri mecanice pentru echipamente electronice-carcase pentru utilizare în exterior)	SR EN 60068-2-5:2011 SR EN 61439-1:2012, pct. 11.9 PTE IHS-18/12.07
17	Permeabilitatea la aer	Ferestre și Uși	SR EN 1028:2001 PTE IHS-0/1.05
		Façade corinți	SR EN 12153:2002 PTE IHS-0/1.08.01
18	Etanșitatea la apă	Ferestre și Uși	SR EN 1027:2001 PTE IHS-0/1.07
		Façade corinți	SR EN 12155:2002 PTE IHS-0/1.07.01
19	Rezistența la încălzirea din vânt	Ferestre și Uși	SR EN 12211:2001 PTE IHS-0/1.17
		Façade corinți	SR EN 12178:2002 PTE IHS-0/1.17
	Încercări mecanice		
20	Determinarea rezistenței la înghițire / Cezămet	Elemente pentru zidărie	SR EN 772-18:2011 PTE IHS-0/1.07.01
21	Determinarea rezistenței la suport. Încercarea la carcasă	Vopsala și lacuri	SR EN ISO 2409:2013 PTE IHS-0/02.05
22	Determinarea comportării la compresune	Produse termoizolante destinate utilizării în clădiri	SR EN 826:2013 PTE IHS-0/09.14-01
23	Rezistența la compresune	Cuburi beton înalt	SR EN 12390-3:2009 SR EN 12390-3:2009/AC2011

Anexa nr. 6 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 6: 18.12.2014

Nr. crt.	Tip/Denumirea încercării	Material / produs	Documentul de referință
			PTE IHS-02/04
		Elemente pentru zidărie	SR EN 772-1:2011 PTE IHS-05/02
24	Rezistența la încovărire și la încălcări de rupere	Beton înalt	SR EN 12390-5:2009 PTE IHS-02/06
25	Rezistența la brânzire prin despicare	Beton înalt	SR EN 12390-6:2010 PTE IHS-02/05
26	Rezistența la tracțiune (înălțime de curgere, alungire)	Bară, sârme laminată și sârme pentru armarea betonului Plăci sudate	SR EN ISO 15630-1:2011 SR EN ISO 6892-1:2010 PTE IHS-06/02 SR EN ISO 15630-2:2011 SR EN ISO 6892-1:2010 PTE IHS-06/09
27	Încercarea la îndoire	Bară	SR EN ISO 15630-1:2011 SR EN ISO 14328:2005 PTE IHS-06/01
28	Determinarea capacității de rezistență a dispozitivelor de siguranță. Determinarea rezistenței la răsucire statică și încovărire statică.	Ferestre Uși	SR EN 14359:2004 PTE IHS-08/01.27 SR EN 548:2002 PTE IHS-08/01.27

Anexa nr. 7 la Certificatul de Acreditare nr. LI 320  
Data emiterii Anexei nr. 7: 18.12.2014

Laborator de Cercetare și Încercări Acustica Construcțiilor - AC  
București, Șos. Pantelimon nr. 266, Sector 2

aparținând de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă „URBAN – INCERC” Sucursala INCERC București

Nr. crt.	Tipul / Denumirea încercării	Material / produs	Documentul de referință
	Metode fizice		
1	Determinarea coeficientului de absorbție acustică în câmp difuz	Materiale fonoabsorbante Structuri fonoabsorbante Obiecte distincte fonoabsorbante	SR EN ISO 354:2004 SR EN ISO 11854:2002 PTE-AC/01.02
2	Determinarea în laborator a izolației acustice la zgomot exten	Periș, plânie, ușă și elemente similare, ferestre, jaluzele, elemente de fațadă, fațade, vitre, elemente tehnice mici, plăci acustice pentru pereți sau plânie, tavane suspendate și pardoseli	SR EN ISO 10140-1:2011 SR EN ISO 10140-1:2011/A1:2012 SR EN ISO 10140-1:2011/A2:2014 SR EN ISO 10140-2:2011 SR EN ISO 10140-4:2011 SR EN ISO 10140-5:2011 SR EN ISO 10140-5:2011/A1:2014 SR EN ISO 17174:2013 PTE-AC/02.01a
3	Determinarea în laborator a izolației acustice la zgomot de impact	Plăci brute, plânie cu perșee, plânie cu țevane, excoșoare la intradosul perșeei	SR EN ISO 10140-1:2011 SR EN ISO 10140-1:2011/A1:2012 SR EN ISO 10140-1:2011/A2:2014 SR EN ISO 10140-3:2011 SR EN ISO 10140-4:2011 SR EN ISO 10140-5:2011 SR EN ISO 10140-5:2011/A1:2014 SR EN ISO 717-2:2013 PTE-AC/02.02a

Laborator de Cercetare și Încercări "Securitatea la Foc a Construcțiilor" – FOC

București, Șos. Pantelimon nr. 266, Sector 2

aparținând de Institutul Național de Cercetare-Dezvoltare în Construcții, Urbanism și Dezvoltare Teritorială Durabilă „URBAN – INCERC” - Sucursala INCERC București

Nr. crt.	Tipul / Denumirea încercării	Material / produs	Documentul de referință
1	Determinarea rezistenței la foc	Uși, obloane și ferestre	SR EN 1634-1:2014 SR EN 1363-1:2012 SR EN 1363-2:2001 PTE-FOC-01.01
		Elemente de construcții neportante - Pereți	SR EN 1354-1:2002 SR EN 1354-1:2002/C91:2007 SR EN 1363-1:2012 SR EN 1363-2:2001 PTE-FOC-01.02
		Elemente de construcții neportante - Plafonduri	SR EN 1354-2:2002 SR EN 1363-1:2012 PTE-FOC-01.03
		Elemente de construcții neportante - Plafonduri cooperanți	SR EN 1355-2:2002 SR EN 1363-1:2012 PTE-FOC-01.05

Șiraghi document  
DIRECTOR GENERAL  
Cătălina Viorela NEAGHE  
REAR

ROMANIAN ACCREDITATION ASSOCIATION - RENAR

București, Călea Vîlani no. 242, sector 3, zip code 031301  
CF RO 4311880



RENAR is EA-MLA signatory for Testing.

ACCREDITATION CERTIFICATE  
No. LI 004

Romanian Accreditation Association – RENAR, being recognized as National Accreditation Body by OG 23/2009, herewith attests that the organization:

**NATIONAL INSTITUTE FOR RESEARCH-DEVELOPMENT-AND TESTING IN ELECTRICAL ENGINEERING – ICMET CRAIOVA**  
Docebal Avenue no. 118A, Craiova, county Dolj

through  
**HIGH POWER TESTING LABORATORY FOR ELECTRICAL EQUIPMENT (HPTL)**

fulfills the requirements of SR EN ISO/CEI 17025:2005 and is competent to carry on TESTING activities, as it is detailed in the Annex of the present accreditation certificate.

This accreditation is maintained provided that the accreditation criteria established by the Romanian Accreditation Association – RENAR are met continuously.

The present certificate includes Annex no. 1/21.03.2016 (11 pages), which is an integrated part of this certificate.

In order to check the validity of the accreditation certificate, including the Annex, the website of RENAR shall be consulted: [www.renar.ro](http://www.renar.ro).

Date of initial accreditation: 22.11.2010

Date of accreditation renewal: 21.11.2014

Updated on: 21.03.2016

The accreditation is valid until: 20.11.2018

GENERAL DIRECTOR

PRESIDENT OF THE ACCREDITATION COUNCIL

Cătălina Viorela NEAGHE

PhD. Eng. Dumitru DINU



The translation of this certificate was issued today, 03.05.2016.

The Accreditation Certificate does not relieve/exempt CAB the obligation to obtain all permits and authorizations required for its operation under the law.

Partial reproduction of this certificate is forbidden.

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

HIGH POWER TESTING LABORATORY FOR ELECTRICAL EQUIPMENT (HPTL)

Docebal Avenue no. 118A, Craiova, county Dolj

belonging to NATIONAL INSTITUTE FOR RESEARCH-DEVELOPMENT AND TESTING IN ELECTRICAL ENGINEERING – ICMET CRAIOVA

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
<b>A. SWITCHING CAPACITY VERIFICATION (MAKING AND BREAKING OPERATIONS)</b>			
1.	Basic short-circuit switching test. Basic sequences: T10, T30, T60, T100s, T100a	a) Alternating current circuit-breakers for voltages above 1 kV b) Single-pole alternating current circuit-breakers for voltages above 1 kV - railway applications	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.102+6.106 IEC 62271-100:2012, clause 6.102+6.106 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4 IEC 62655-1:2009 clause 7.8 + 7.12 SR EN 62271-2:2009, clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4
2.	Critical current switching test	a) Alternating current circuit-breakers for voltages above 1 kV b) Single-pole alternating current circuit-breakers for voltages above 1 kV - railway applications	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.107 IEC 62271-100:2012, clause 6.107 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4 IEC 62655-1:2009 clause 7.13 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4
3.	Single-phase and double-earth fault switching test	Alternating current circuit-breakers for voltages above 1 kV	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.103 IEC 62271-100:2012, clause 6.103 PT-03.01, Ed. 4
4.	Out of phase making and breaking switching test (OP1, OP2)	a) Alternating current circuit-breakers for voltages above 1 kV b) Single-pole alternating current circuit-breakers for voltages above 1 kV - railway applications	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.110 IEC 62271-100:2012, clause 6.110 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4 IEC 62655-1:2009 clause 7.14 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4
5.	Capacitive current switching test (LC1, LC2, CC1, CC2), (BC1, BC2)	a) Alternating current circuit-breakers for voltages above 1 kV	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.111 IEC 62271-100:2012, clause 6.111 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
		b) Single-pole alternating current circuit-breakers for voltages above 1 kV - railway applications	IEC 62655-1:2009 clause 7.15 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6 IEC 62271-1:2011, clause 6 PT-03.01, Ed. 4
6.	Electrical usage test (electrical endurance)	Alternating current circuit-breakers for voltages above 1 kV	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.102+6.106 and 6.112 IEC 62271-100:2012, clause 6.102+6.106 and 6.112 PT-03.01, Ed. 4
7.	Bus transfer current switching test	Alternating current disconnectors	SR EN 62271-102:2003, SR EN 62271-102:2009/A1:2013, clause 6.106 IEC 62271-102:2013, clause 6.106 SR EN 62271-102:2013, clause 6.106 PT-03.02, Ed. 4
8.	Induced current switching test	Alternating current disconnectors earthing switches	SR EN 62271-102:2003, SR EN 62271-102:2009/A1:2013, clause 6.107 IEC 62271-102:2013, clause 6.107 PT-03.02, Ed. 4
9.	Verification of rated making and breaking capacity	High-voltage alternating current contactors	SR EN 62271-106:2012, clause 6.102 IEC 62271-106:2011, IEC 62271-106:2011/Cor.1:2014, clause 6.102 PT-03.02, Ed. 4
10.	Overload ability test	High-voltage alternating current contactors	SR EN 62271-106:2012, clause 6.103 IEC 62271-106:2011, IEC 62271-106:2011/Cor.1:2014, clause 6.103 PT-03.02, Ed. 4
11.	Short-circuit current making and breaking test	High-voltage alternating current contactors	SR EN 62271-106:2012, clause 6.104 IEC 62271-106:2011, IEC 62271-106:2011/Cor.1:2014, clause 6.104 PT-03.02, Ed. 4
12.	Verification of making and breaking capacities	AC metal-enclosed switchgear and circuit-breaker for rated voltages above 1 kV up to and including 52 kV	SR EN 62271-200:2012, clause 6.101 IEC 62271-200:2011, clause 6.101 PT-03.01, Ed. 4
13.	Short-circuit making current test	High voltage alternating current disconnectors and earthing switches	SR EN 62271-102:2003, SR EN 62271-102:2009/A1:2013, clause 6.101 IEC 62271-102:2013, clause 6.101 PT-03.02, Ed. 4
14.	Mainly active load switching test	a) Switches for rated voltages above 1 kV up to and including 52 kV (Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV) b) Single-pole disconnectors, earthing switches and switches for rated voltages above 1 kV for railway application	SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2014, clause 6.101 PT-03.02, Ed. 4 IEC 62655-2:2009, clause 7.1 SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2014, clause 6.101 PT-03.02, Ed. 4
15.	Closed loop switching test	a) Alternating current switches for rated voltages above 1 kV up to and including 52 kV	SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
		(Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV) b) Single-pole disconnectors, earthing switches and switches for rated voltages above 1 kV - railway application	Corr. 12013, clause 6.101 PT-03.02, Ed.3 IEC 62505-2:2009, clause 7 SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Corr. 12013, clause 6.101 PT-03.02, Ed.4
16.	Capacitive current switching test (no-load cables and lines)	a) Alternating current switches for rated voltages above 1 kV up to and including 52 kV (Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV) b) Single-pole disconnectors, earthing switches and switches for rated voltages above 1 kV - railway application	SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, Corr. 12013 clause 6.101 PT-03.02, Ed.4 IEC 62505-2:2009, clause 7 SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Corr. 12013 clause 6.101 PT-03.02, Ed.4
17.	Short-circuit making current test	a) Alternating current switches for rated voltages above 1 kV up to and including 52 kV (Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV) b) Single-pole disconnectors, earthing switches and switches for rated voltages above 1 kV for railway application	SR EN 62271-102:2003, SR EN 62271-102:2003/A1:2012, SR EN 62271-102:2003/A2:2013, clause 6.101 IEC 62271-102:2003, clause 6.101 SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Corr. 12013 clause 6.101 PT-03.02, Ed.4 IEC 62505-2:2009, clause 7 SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Corr. 12013 clause 6.101 PT-03.02, Ed.4
18.	Switching test on earthing fault current	Alternating current switches for rated voltages above 1 kV up to and including 52 kV (Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV)	SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Corr. 12013 clause 6.101 PT-03.02, Ed.4
19.	No-load cables and lines switching current test under earth fault conditions	Alternating current switches for rated voltages above 1 kV up to and including 52 kV (Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV)	SR EN 62271-103:2012, clause 6.101 IEC 62271-103:2011, IEC 62271-103:2011/Corr. 12013 clause 6.101 PT-03.02, Ed.4
20.	Making and breaking test at the rated short-circuit current (I <sub>sc</sub> )	Alternating current mechanical switch-fuse combinations	SR EN 62271-105:2013, clause 6.101 IEC 62271-105:2012, clause 6.101 PT-03.02, Ed.4
21.	Making and breaking test at the maximum breaking (I <sub>max</sub> )	Alternating current mechanical switch-fuse combinations	SR EN 62271-105:2013, clause 6.101 IEC 62271-105:2012, clause 6.101 PT-03.02, Ed.4
22.	Breaking test at the rated transfer current (I <sub>tr</sub> )	Alternating current mechanical switch-fuse combinations	SR EN 62271-105:2013, clause 6.101 IEC 62271-105:2012, clause 6.101 PT-03.02, Ed.4

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
23.	Verification of the breaking capacity	a) High-voltage current limiting exceeding 1kV fuses b) High-voltage expulsion fuses c) Low-voltage fuses	SR EN 60282-1:2010, clause 6.6 IEC 60282-1:2009, clause 6.6 IEC 60282-2:2008, clause 8.6 PT-03.03, Ed.4 SR EN 60289-1:2006, SR EN 60289-1:2006/A1:2010, clause 8.5 IEC 60289-1:2009, clause 8.5 PT-03.03, Ed.4
24.	Test for verifying time-current characteristics	High-voltage current limiting exceeding 1kV fuses	SR EN 60282-1:2010, SR EN 60282-1:2010/A1:2015, clause 6.7 IEC 60282-1:2010, clause 6.7 PT-03.03, Ed.4
<b>B. TYPE TESTS FOR LOW VOLTAGE CIRCUIT-BREAKERS</b>			
25.	General performance characteristics (test sequence 1)	All circuit-breakers categories	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.3 IEC 60947-2:2013, clause 8.3.3
26.	Rated service short-circuit breaking capacity (test sequence 2)	All circuit-breakers categories	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.4 IEC 60947-2:2013, clause 8.3.4
27.	Rated ultimate short-circuit breaking capacity (test sequence 3)	Circuit-breakers category A Circuit-breakers category B integrally fused	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.5 IEC 60947-2:2013, clause 8.3.5
28.	Rated short-time withstand current (test sequence 4)	Circuit-breakers category B	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.6 IEC 60947-2:2013, clause 8.3.6
29.	Performance of integrally fused circuit-breakers (test sequence 5)	Integrally fused circuit-breakers	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.7 IEC 60947-2:2013, clause 8.3.7
30.	Combined test (test sequence 6)	Circuit-breakers category B	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.8 IEC 60947-2:2013, clause 8.3.8
<b>C. SHORT-TIME WITHSTAND CURRENT BEHAVIOR (SHORT-CIRCUIT)</b>			
31.	Short-time withstand current test and peak withstand current tests	a) Alternating current circuit-breakers exceeding 1 kV b) Single-pole alternating current circuit-breakers with nominal voltage above 1 kV - railway applications	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.6 IEC 62271-100:2012, clause 6.6 SR EN 62271-120:2009, SR EN 62271-120:2009/A1:2012 clause 6.6 IEC 62271-120:2011 clause 6.6 PT-03.04, Ed.4 SR EN 62271-120:2009, SR EN 62271-120:2009/A1:2012 clause 6.6 IEC 62271-120:2011 clause 6.6 PT-03.04, Ed.4

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
			IEC 62505-1:2009 clause 7.6 PT-03.04, Ed.4
		c) Alternating current switches for rated voltages above 1 kV up to and including 52 kV (Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV)	SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6.6 IEC 62271-1:2011, clause 6.6 SR EN 62271-103:2012, clause 6.6 IEC 62271-103:2011, IEC 62271-103:2011/Corr. 12013 clause 6.6 PT-03.04, Ed.4
		d) High voltage alternating current disconnectors and earthing switches	SR EN 62271-102:2003, clause 6.6 IEC 62271-102:2003, A1:2012, A2:2013, clause 6.6 IEC 62271-102:2012, clause 6.6 PT-03.04, Ed.4
		e) Single-pole switches, earthing switches and switches with nominal voltage above 1 kV - railway applications	IEC 62505-2:2009, clause 7 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012 clause 6.6 IEC 62271-1:2011, clause 6.6 PT-03.04, Ed.4
		f) AC metal enclosed switchgear and controlgear for rated voltages above 1 kV up to and including 52 kV	SR EN 62271-200:2012, clause 6.6 IEC 62271-200:2011, clause 6.6 PT-03.04, Ed.4
		g) Low voltage switchgear and controlgear switches, circuit-breakers, disconnectors	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.6 IEC 60947-2:2013, 8.3.6 SR EN 60947-3:2009, SR EN 60947-3:2009/A1:2012, clause 8.3.5.1 IEC 60947-3:2012, IEC 60947-3:2012/A1:2013, clause 8.3.5.1 PT-03.18, Ed.4 PT-03.19, Ed.4
		h) Current switches and fuse switch combination units	SR EN 62271-105:2013, clause 6.6 IEC 62271-105:2012, clause 6.6 PT-03.04, Ed.4
		i) Busbars and low-voltage switchgear and controlgear assemblies (distributing boxes, measuring and protection units)	SR EN 61439-1:2012, clause 10.10 IEC 61439-1:2011, clause 10.10 PT-03.04, Ed.4
		j) Busbarings	SR EN 60137:2008, SR EN 60137:2008/A1:2012, clause 8.6 IEC 60137:2008, clause 8.6 PT-03.04, Ed.4
		k) Prefabricated substations	SR EN 62271-202:2007, clause 6.4 IEC 62271-202:2014, clause 6.4 PT-03.04, Ed.4
		l) Current transformers	SR EN 61869-2:2013, clause 7.2.201 IEC 61869-2:2012, clause 7.2.201 PT-03.04, Ed.4
		m) Busbar trunking systems (busways)	SR EN 61439-6:2013, clause 10.11.1 IEC 61439-6:2012, clause 10.11.1 PT-03.04, Ed.4

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
32.	Intra-turn overvoltage test	Current transformers	SR EN 61869-2:2013, clause 7.3.204 IEC 61869-2:2012, clause 7.3.204 PT-03.17, Ed.4
33.	Short-circuit withstand capability test	a) Inductive voltage transformers b) Capacitive voltage transformers	SR EN 61869-3:2012, clause 7.2.301 IEC 61869-3:2011, clause 7.2.301 PT-03.11, Ed.3 SR EN 61869-5:2012, clause 7.2.502 IEC 61869-5:2011, clause 7.2.502 PT-03.04, Ed.4
34.	Short-circuit current test	Tap changers	SR EN 60214-1:2004, clause 7.2.3 IEC 60214-1:2004, clause 7.2.3 PT-03.21, Ed.1
35.	Short-circuit current test (temperature and dynamic stability)	Portable equipment for earthing or earthing and short-circuiting	SR EN 61230:2009, clause 6.6 IEC 61230:2008, clause 6.6 PT-03.12, Ed.4
36.	Ability to withstand short-circuit	a) Power transformers: • oil immersed • dry b) Current limiting reactors c) Line traps for alternating current power systems d) Filter, damping and discharge reactors associated with capacitors e) Earthing transformers (neutral couplers)	SR EN 60076-5:2006, clause 4.2 IEC 60076-5:2006, clause 4.2 SR EN 60076-11:2005, clause 25 IEC 60076-11:2004, clause 25 PT-03.05, Ed.4 SR EN 60076-6:2009, clause 8.9.13 IEC 60076-6:2007, clause 8.9.13 PT-03.14, Ed.4 IEC 60353-1:1989, IEC 60353-1:1989/A1:2002, clause 19.4 PT-03.14, Ed.4 SR EN 60076-6:2009, clause 9.5 IEC 60076-6:2007 clause 9.5 PT-03.05, Ed.4 SR EN 60076-6:2009, clause 10.5 IEC 60076-6:2007, clause 10.5 PT-03.05, Ed.4
37.	Short-circuit tests	Metal-oxide surge arresters without gaps for a.c. systems	SR EN 60099-1:2009, SR EN 60099-1:2009/A1:2003, clause 8.7 IEC 60099-1:1999, clause 8.7 SR EN 60099-4:2005, SR EN 60099-4:2005/A1:2007, SR EN 60099-4:2005/A2:2009, clause 8.7 IEC 60099-4:2009, clause 8.7 PT-03.09, Ed.4
<b>D. INTERNAL ARC TEST</b>			
38.	Internal arc fault test	a) AC metal enclosed switchgear and controlgear for rated voltages above 1 kV up to and including 52 kV b) Prefabricated substations c) Current transformers	SR EN 62271-200:2012, clause 6.105 IEC 62271-200:2011, clause 6.106 PT-03.08, Ed.4 SR EN 62271-202:2007, 6.8 IEC 62271-202:2014, 6.102 PT-03.08, Ed.4 SR EN 61869-1:2010 clause 7.4.6 IEC 61869-1:2007 clause 7.4.6 SR EN 61869-2:2013, clause 7.4.6

000064

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
		d) Voltage transformers	IEC 61859-2:2012, clause 7.4.6 PT-03.08, Ed. 4 SR EN 61859-1:2010, clause 7.4.6 IEC 61859-1:2007, clause 7.4.6 SR EN 61859-3:2012, clause 7.4.6 IEC 61859-3:2011, clause 7.4.6 PT-03.08, Ed. 4
39	AC power arc tests	e) Low-voltage switchgear and controlgear assemblies Insulators for overhead lines with a nominal voltage above 1000 V	IEC 61841:2014, clause 8 PT-03.08, Ed. 4 SR EN 61457:2009, clause 8 IEC 61457:2008, clause 8 PT-03.15, Ed. 4
40	Tests using a constrained and directed arc	Protective clothing against the thermal hazards of an electric arc	SR EN 61452-1:2010 IEC 61452-1:2009 SR EN 61452-1-2:2007 IEC 61452-1-2:2007 IEC 61452-2:2009 PT-03.22, Ed. 1
<b>E. TEMPERATURE-RISE TESTS</b>			
41	Temperature-rise test	a) Circuit-breakers for rated voltages above 1 kV b) Single-pole alternating current circuit-breakers with nominal voltage above 1 kV - railway applications c) Switches for rated voltages above 1 kV up to and including 52 kV (Mechanical disconnectors for rated voltage above 1 kV up to and including 52 kV) d) Switches and earthing switches, single-pole switches with nominal voltage above 1 kV - railway applications e) High-voltage current-limiting fuses	SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012, clause 6.5 IEC 62271-1:2011, clause 6.5 SR EN 62271-102:2009, SR EN 62271-102:2009/A1:2013, clause 6.5 IEC 62271-102:2012, clause 6.5 PT-03.06, Ed. 4 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012, clause 6.5 IEC 62271-1:2011, clause 6.5 IEC 62505-1:2009, clause 7.4 PT-03.06, Ed. 4 SR EN 62271-103:2012, clause 6.5 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.5 SR EN 62271-102:2003, SR EN 62271-102:2003/A1:2012, SR EN 62271-102:2003/A2:2013, clause 6.5 IEC 62271-102:2013, clause 6.5 SR EN 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.5 IEC 62505-2:2009, clause 7 PT-03.05, Ed. 4 SR EN 62271-102:2003, SR EN 62271-102:2003/A1:2012, SR EN 62271-102:2003/A2:2013, clause 6.5 IEC 62271-102:2013, clause 6.5 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.5 IEC 62505-2:2009, clause 7 PT-03.05, Ed. 4 SR EN 60282-1:2010, clause 6.5 IEC 60282-1:2009, clause 6.5 IEC 60282-2:2008, clause 6.5 PT-03.06, Ed. 4

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
		i) Low voltage fuses	SR EN 60269-1:2008, SR EN 60269-1:2008/A1:2010, clause 8.3 IEC 60269-1:2009, clause 8.3 SR HD 60269-2:2011, clause 8.3 IEC 60269-2:2013, clause 8.3 PT-03.06, Ed. 3
		g) Disconnectors for rated voltages above 1 kV	SR EN 62271-102:2003, SR EN 62271-102:2003/A1:2012, SR EN 62271-102:2003/A2:2013, clause 6.5 IEC 62271-102:2013, clause 6.5 PT-03.06, Ed. 4
		h) Bushings	SR EN 60137:2008, clause 25 IEC 60137:2008, clause 25 PT-03.05, Ed. 4
		j) High voltage alternating current contactors	SR EN 62271-105:2012, clause 6.5 IEC 62271-105:2011, IEC 62271-105:2011/Cor.1:2014, clause 6.5 PT-03.05, Ed. 4
		k) Current transformers	SR EN 61869-1:2010, clause 7.2.2 IEC 61869-1:2007, clause 7.2.2 SR EN 61869-2:2013, clause 7.2.2 IEC 61869-2:2012, clause 7.2.2 PT-03.16, Ed. 4
		l) Tap changers	SR EN 60214-1:2004, clause 7.2.2 IEC 60214-1:2014, clause 7.2.2 PT-03.05, Ed. 4
		m) Inductive voltage transformers	SR EN 61669-1:2010, clause 7.2.2 IEC 61669-1:2007, clause 7.2.2 SR EN 61669-3:2012, clause 7.2.2 IEC 61669-3:2011, clause 7.2.2 PT-03.16, Ed. 4
		n) Capacitive voltage transformers	SR EN 61869-5:2012, clause 7.2.2 IEC 61869-5:2011, clause 7.2.2 PT-03.16, Ed. 3
		o) Power transformers • oil immersed • dry	SR EN 60076-2:2011, clause 7 IEC 60076-2:2005, clause 8 SR EN 60076-11:2005, clause 23 IEC 60076-11:2004, clause 23 PT-03.10, Ed. 4
		c) Prefabricated substations	SR EN 62271-202:2007, clause 6.3 IEC 62271-202:2013, clause 6.3 PT-03.10, Ed. 4
		p) Alternating current switch-fuse combinations	SR EN 62271-105:2013, clause 6.5 IEC 62271-105:2012, clause 6.5 PT-03.05, Ed. 4
		r) AC metal enclosed switchgear and controlgear for rated voltages above 1 kV up to and including 52 kV s) Low voltage switchgear and controlgear, switches, disconnectors, switch-disconnectors and fuse-combination units	SR EN 62271-200:2012, clause 6.5 IEC 62271-200:2011, clause 6.5 PT-03.05, Ed. 4 SR EN 62047-1:2008, SR EN 62047-1:2008/A1:2011, clause 8.3.3.3 IEC 62047-1:2011, clause 8.3.3.3

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
			SR EN 60947-3:2009, SR EN 60947-3:2009/A1:2012, clause 8.3.3.6 IEC 60947-3:2012, IEC 60947-3:2012/A1:2013, clause 8.3.3.6 PT-03.19, Ed. 4
		s) Low voltage switchgear and controlgear, Circuit-breakers	SR EN 60947-2:2007, SR EN 60947-2:2007/A1:2010, SR EN 60947-2:2007/A2:2013, clause 8.3.3.6, clause 8.3.4.4, clause 8.3.6.3, clause 8.3.7.2 IEC 60947-2:2013, clause 8.3.3.6, clause 8.3.4.4, clause 8.3.6.3, clause 8.3.7.2 PT-03.18, Ed. 3
		t) Busbars and low-voltage switchgear and controlgear assemblies (distributing boxes, measuring and protection units)	SR EN 61439-1:2012, clause 9.2 IEC 61439-1:2011, clause 9.2 PT-03.05, Ed. 4
		u) Neutral Grounding Resistors	ANSI/IEEE 32-1972, Amendment 1974, clause 14.4 PT-03.23, Ed. 4
		v) Busbar trunking systems (busways)	SR EN 61439-6:2013, clause 10.10 IEC 61439-6:2012, clause 10.10 PT-03.06, Ed. 4
		x) Earthing transformers (neutral couplers)	SR EN 60076-6:2009, clause 10.6 IEC 60076-6:2007, clause 10.6 PT-03.06, Ed. 4
<b>F. MECHANICAL TESTS</b>			
42	Mechanical endurance tests	a) Circuit-breakers for ac voltages above 1 kV b) Alternating current disconnectors above 1 kV c) Alternating current switches for rated voltages above 1 kV d) Switches and earthing switches, single-pole switches with nominal voltage above 1 kV - railway applications	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.101 IEC 62271-100:2012, clause 6.101 PT-03.07, Ed. 4 SR EN 62271-103:2012, clause 6.102 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.102 SE EN 62271-102:2003, SE EN 62271-102:2003/A1:2012, SR EN 62271-102:2003/A2:2013, clause 6.102 IEC 62271-102:2013, clause 6.102 PT-03.07, Ed. 4 SR EN 62271-102:2003, SR EN 62271-102:2003/A1:2012, SR EN 62271-102:2003/A2:2013, clause 6.102 IEC 62271-102:2013, clause 6.102 SR EN 62271-103:2012, clause 6.102 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.102 PT-03.07, Ed. 4 SR EN 62271-102:2003, SR EN 62271-102:2003/A1:2012, A2:2013, clause 6.102 IEC 62271-102:2013, clause 6.102 SR EN 62271-103:2012, clause 6.102 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.102 IEC 62505-2:2009, clause 7.3 PT-03.07, Ed. 4

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area / Measurement technique / Name of the test	Material / product / test object	Reference document
		e) High-voltage alternating current contactors	SR EN 62271-105:2012, clause 6.101 IEC 62271-105:2011, IEC 62271-105:2011/Cor.1:2014, clause 6.101 PT-03.07, Ed. 4
43	Switching devices	AC metal enclosed switchgear and controlgear for rated voltages above 1 kV up to and including 52 kV	SR EN 62271-200:2012, clause 6.102.1 IEC 62271-200:2011, clause 6.102 PT-03.07, Ed. 4
44	Interlocks verification	AC metal enclosed switchgear and controlgear for rated voltages above 1 kV up to and including 52 kV	SR EN 62271-200:2012, clause 6.102.2 IEC 62271-200:2011, clause 6.102 PT-03.07, Ed. 4
<b>G. SOUND LEVEL DETERMINATION</b>			
45	Sound levels determination	a) Power transformers • oil immersed • dry b) Prefabricated substations	SR EN 60076-10:2003 IEC 60076-10:2001 IEC 60076-10-1:2005 PT-03.13, Ed. 3 SR EN 62271-202:2007, Annex B8 IEC 62271-202:2013, Annex B8 SR EN 60076-10:2005, IEC 60076-10:2001 IEC 60076-10-1:2005 PT-03.13, Ed. 3
<b>H. MAIN AND AUXILIARY CIRCUIT RESISTANCE MEASURING</b>			
46	Main and auxiliary circuit resistance measuring	a) Alternating current circuit-breaker for rated voltages above 1 kV b) AC metal enclosed switchgear and controlgear for rated voltages above 1 kV up to and including 52 kV c) Alternating current switches for rated voltages above 1 kV up to and including 52 kV, mechanical disconnectors (switches) for rated voltage above 1 kV up to and including 52 kV d) Switches and earthing switches, single-pole switches with nominal voltage above 1 kV for railway applications e) Single-pole alternating current (AC) circuit-breakers with nominal voltage above 1 kV for railway applications f) Alternating current switch-fuse combinations	SR EN 62271-100:2009, SR EN 62271-100:2009/A1:2013, clause 6.4 IEC 62271-100:2012, clause 6.4 SR EN 62271-1:2009, SR EN 62271-1:2009/A1:2012, clause 6.4 IEC 62271-1:2011, clause 6.4 PT-03.20, Ed. 3 SR EN 62271-200:2012, clause 6.4 IEC 62271-200:2011, clause 6.4 PT-03.20, Ed. 3 SR EN 62271-103:2012, clause 6.4 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.4 SR EN 62271-102:2003, SR EN 62271-102:2003/A1:2012, SR EN 62271-102:2003/A2:2013, clause 6.4 IEC 62271-102:2013, clause 6.4 PT-03.20, Ed. 3 SR EN 62271-103:2012, clause 6.4 IEC 62271-103:2011, IEC 62271-103:2011/Cor.1:2013, clause 6.4 IEC 62505-2:2009, clause 7.5 PT-03.20, Ed. 3 SR EN 62271-105:2013, clause 6.4 IEC 62271-105:2012, clause 6.4 PT-03.20, Ed. 4

000005

Annex no. 1 to Accreditation Certificate no. LI 004  
Annex no. 1 Issue Date: 21.03.2016

No.	Activity area/ Measurement technique / Name of the test	Material / product/ test object	Reference document
<b>INDIVIDUAL TESTS</b>			
47	Measurement of winding resistance	Power transformers	SR EN 60076-1:2012, clause 11.2 IEC 60076-1:2012, clause 11.2 PT-03.10, Ed. 4
48	Measurement of voltage ratio and check of phase displacement	Power transformers	SR EN 60076-1:2012, clause 11.3 IEC 60076-1:2012, clause 11.3 PT-03.10, Ed. 4
49	Measurement of short-circuit impedance and load loss	Power transformers	SR EN 60076-1:2012, clause 11.4 IEC 60076-1:2012, clause 11.4 PT-03.10, Ed. 4
50	Measurement of no-load loss and current	Power transformers	SR EN 60076-1:2012, clause 11.5 IEC 60076-1:2012, clause 11.5 PT-03.10, Ed. 4

End of document

GENERAL DIRECTOR  
Cătălina Viorica NEAGU




RECEIVED


*[Handwritten signature]*

*[Handwritten signature]*

RECEIVED  
CĂTĂLINA NEAGU



*[Handwritten signature]*



High Voltage Products

# Current transformers PA 123a and PA 145a

ABB  
CANADA



*Handwritten mark*

Power and productivity  
for a better world™

**ABB**

000087

# Product description



The PVA 123a and PVA 145a current transformers are used for feeding measurement and protection systems in electric power grids with the highest system voltage of 123 kV or 145 kV, respectively, and frequency of 50 Hz. They are designed to operate in grids with effectively earthed or insulated neutral points as well as in compensated earthed systems. The transformers are suitable to operate in outdoor conditions with ambient temperature from 233 K (-40°C) to 313 K (+40°C) and at relative humidity of up to 100% at 303 K (+30°C), at an altitude not exceeding 1000 m above sea level. Two designs are available: with composite or porcelain insulator.

Current transformers type PA 123a and PA 145a feature a top core design; active parts are placed in a tight enclosure filled with PCB-free transformer oil.

The covered transformer's stainless steel compensation bellows in casing is fixed to the head. The compensation bellows compensates for thermal changes in oil volume.

## Top core construction

The use of the top core design in the current transformer makes it possible to achieve high values of thermal and dynamic short-circuit currents as well as a broad range of rated primary currents and burdens of secondary windings.

## Primary and secondary windings and accuracy classes

The primary and secondary windings are made of electrical copper and aluminum. For clients requiring high transformation accuracy with low values of selected rated primary currents, we are able to deliver a solution comprising the use of special classes 0.2S and 0.5S. We guarantee very high transformation accuracy in the special classes, from 1% to 120%, 150% and even to 200% of the value of selected primary current for both secondary currents of 1 A and 5 A.

Secondary windings for protection purposes are offered in all accuracy classes, namely: 5P, 10P, 5PR, 10PR, TPX, TPY, TPZ, PX, PXR.

Our laboratory for measurements of accuracy classes of instrument transformers is one of the most advanced and well-equipped research facilities in the country. We are accredited by the Polish Central Office of Measures.

## Current range switching

The transformer can be switched on the primary side as well as on the secondary side. A metal jumper is used for current range switching on the primary side. It shall be placed in appropriate location in accordance with the terminal board. This solution does not require performance of additional operations related to change of location of line connections.

## Main insulation

The main insulation is made of insulation paper impregnated with transformer oil. We utilize high quality oil conforming to IEC 60296 Standard requirements. This oil does not contain PCBs or any other highly toxic substances and has low environmental impact.

## Hollow insulator

The standard insulator is made of brown porcelain with creepage distance required for the 3rd pollution zone. A grey composite insulator with creepage distance required for the 4th pollution zone is available upon request. All materials used in the production of our insulators conform to relevant IEC Standards.

## Enclosure

All external parts are robust and made of corrosion resistant materials. All enclosure joints are leak proof due to O-ring sealing system. Each completely assembled unit is subject to stringent leakage checks during routine testing. The expansion bellows is equipped with a large oil level indicator that enables observations of changes in oil volume even from a large distance.


## Primary terminals

The standard primary terminals are flat, made of aluminum, and their width is 100 mm or 200 mm. Upon request we can offer pin type primary terminals, made of copper or aluminum, with a diameter of 30 mm or 40 mm.

## Terminal box

The terminal box is made of aluminum and fixed to the transformer's bottom tank. Tightness – according to IP55. Secondary terminals are available for connection of conductors with cross-section of up to 10 mm<sup>2</sup>. Sealing of current measurement terminals is also possible upon request. The standard terminal box is equipped with two M40 cable glands (for cables from Ø 19 mm to Ø 28 mm). We offer terminal boxes with different number of cable glands upon request. IT's with two secondary boxes are available upon request (possibility of splitting into measuring and protective part).

БЯВНО С  
ОПРИТЪННАТА





# Technical specifications



## General information

Parameter	Value	
Type	PA 123a	PA 145a
Compliance with standards	IEC 61869-2; PN-EN 61869-2	
Highest system voltage	123 kV	145 kV
Power-frequency withstand test voltage	50 Hz 230 kV	50 Hz 275 kV
Rated lighting-impulse withstand voltage	1,2/50 $\mu$ s 550 kV	1,2/50 $\mu$ s 650 kV
Minimum creepage distance	16; 20; 25; 31 mm/kV	
Rated frequency	50 Hz	
Total weight [max.]	420; 360* kg	

\*Composite insulator.


## Current module

Rated current [A]	Short-circuit thermal current 1 s [kA]	Dynamic short-circuit current [kA]
50-3000	up to 63	up to 157

Switched design 1:2 or 1:2:4 on request.

Parameter	Value
Rated secondary current	1 A; 5 A
Extended current range	120%; 150%; 200%
Number of cores	1-6
Measuring cores parameters:	
- total rated output	1-200 VA
- accuracy class	0,1; 0,2; 0,2S; 0,5; 0,5S; 1; 3; 5
Protection cores parameters:	
- total rated output	1-200 VA
- accuracy class	5P, 10P, 5PR, 10PR, TPX, TPY, TPZ, PX, PXR

## Dimensional drawing



\*) The dimension depends on the insulator and the type of a primary terminal

ВЕРНО С  
ОБЪЯВЛЕНА



000669

# More information



## ABB Contact Center

ph.: +48 22 22 37 777

e-mail: kontakt@pl.abb.com

## ABB Sp. z o.o.

### Branch Office in Przasnysz

ul. Leszno 59

06-300 Przasnysz

ph.: +48 22 22 38 931, +48 22 22 39 255

fax: +48 22 22 38 958

[www.abb.pl](http://www.abb.pl)

We reserve the right to make technical changes or modify the contents of this document without prior notice. With regard to purchase orders, the agreed particulars shall prevail. ABB does not accept any responsibility whatsoever for potential errors or possible lack of information in this document.


We reserve all rights to this document and its subject matter, as well as illustrations contained therein. Any reproduction, disclosure to third parties or utilization of its contents – in whole or in parts – is forbidden without prior written consent of ABB.

© Copyright 2014 ABB  
All rights reserved

2129PL1191-W1-en Edition 11.2014



БЕЛГНО С  
ОПШТИНАЛА



000670



Power and productivity  
for a better world™





РЕПУБЛИКА БЪЛГАРИЯ  
Български институт по метрология  
REPUBLIC OF BULGARIA  
Bulgarian Institute of Metrology



**УДОСТОВЕРЕНИЕ  
ЗА ОДОБРЕН ТИП СРЕДСТВО ЗА ИЗМЕРВАНЕ**  
*Measuring Instrument Type-approval Certificate*


**№ 16.05.5104**

**Издадено на производител:** ABB Sp. zo. o., Poland  
*Issued to manufacturer:* 06-300 Przasnysz, ul. Leszno 59

**На основание на:** чл. 32, ал. 1 от Закона за измерванията (ДВ, бр. 46 от  
*In Accordance with:* 2002 г., изм. бр. 88 от 05 г., изм. и доп. бр. 95 от 2005 г.)

**Относно:** измервателни токови трансформатори тип PA 123а, PA 145а  
*In Respect of:*

**Знак за одобрен тип:**  
*Type Approval Mark:*



**Технически и метрологични  
характеристики:**  
*Technical and metrological  
characteristics:*


приложение, неразделна част от настоящото  
удостоверение за одобрен тип средство за измерване

**Срок на валидност:** 12.05.2026 г.  
*Valid until:*

**Вписва се в регистъра на  
одобрените за използване  
типове средства за  
измерване под №:**  
*Reference №:*

5104

ВЪРНО С  
ОРИГИНАЛА



**Дата на издаване на  
удостоверението за  
одобрен тип:**  
*Date:*

12.05.2016 г.

И. Д. ПРЕДСЕДАТЕЛ  
Пау Илчев



страница 1 от 2

000071



**Приложение към удостоверение за одобрен тип № 16.05.5104**

**Издадено на производител:** ABB Sp. zo. o., Poland, 06-300 Przasnysz, ul. Leszno 59

**Относно:** измервателни токови трансформатори тип PA 123a, PA 145a

**1. Описание на типа:**

Измервателните токови трансформатори тип PA 123a и PA 145a се използват за измерване и защита на електрически мрежи с максимално допустимо работно напрежение до 123 kV и 145 kV и честота 50 Hz. Те са проектирани да работят в системи с ефективно заземен или изолиран звезден център, както и в компенсирани системи. Предназначени са за външен монтаж.

Активната част на токовете трансформатори се състои от първична намотка, вторични намотки и ядро, разположени в херметичен корпус запълнен с трансформаторно масло, не съдържащо полихлорирани бифинили PCB. Ядрата са разположени в горната част на токовия трансформатор.

Първичната и вторичната намотки са направени от висококачествена електротехническа мед, позволяваща висок клас на точност започващ от 0,1 при ниски стойности на номиналния първичен ток. При измервателните токови трансформатори тип PA 123a и PA 145a има възможност за превключване на първичната намотка.

Изолаторът може да бъде направен от порцелан с път на утечка 25 mm/kV или 31 mm/kV. Възможно е той да бъде изработен и от полимерен композитен материал с път на утечка 31 mm/kV.

Токовете трансформатори тип PA 123a и PA 145a са подходящи за работа в условия на открито с температура на околната среда от -40 °C до +40 °C при относителна влажност на въздуха до 100% при 30 °C и надморска височина до 1000 m. Трансформаторите са изработени за общо механично натоварване от скоростта на вятъра до 34 m/s, поледница с дебелина до 20 mm и до опъване на проводника не повече от 500 N.

Вторичните клеми са обозначени със стандартни маркировки на изводите. Всички външни метални части са изработени от корозоустойчиви материали.

**2. Технически и метрологични характеристики:**

Характеристика	Трансформатори тип PA 123a	Трансформатори тип PA 145a
Максимално работно напрежение, kV	123	145
Честота, Hz	50	
Номинален първичен ток, A	от 50 до 3000	
Клас на точност: - измервателна намотка: - защитна намотка:	0,1; 0,2S; 0,2; 0,5S; 0,5; 1; 3; 5 5P; 10P; 5PR; 10PR; PX; PXR; TPX; TPY; TPZ;	
Коефициент на сигурност, FS	FS5; FS10	
Номинален вторичен ток, A	1; 5	
Мощност, VA	до 200	

**3. Типово означение:** PA 123a, PA 145a.

**4. Описание на местата, предназначени за поставяне на знаци от метрологичен контрол:**

- Знакът за одобрен тип (марка за залепване) се поставя на табелката с технически данни;
- Знакът за първоначална проверка (марка за залепване) се поставя до знака за одобрен тип.

ИЗДАНО С  
ОРИГИНАЛА



**ABB**  
Data Schedule : Current Transformer

Date : 2017-07-05 Name : bozena.trajer@pl.abb.com  
 CCP Number: -  
 Our ref : KU 657/17 Revision : A  
 Project : CEZ

**General data**

Quantity 6  
 Type PA 123a  
 Standards IEC 61869-2  
 Design Outdoor  
 Insulation Oil / paper hermetic  
 Manufacturer, country ABB, Poland

**Service conditions**

Highest voltage of a system (phase-to-phase)  $U_{sys}$  kV r.m.s. 123  
 Rated frequency  $f_n$  Hz 50  
 Ambient air temperature (Temperature category) °C -40/ +40  
 Average ambient air temp. (period 24h) °C ≤ 35  
 Altitude m 1000  
 Seismic activity acc. to IEC 62271-300 AF3

**Rated insulation level**

Highest voltage for equipment (phase-to-phase)  $U_m$  kV r.m.s. 123  
 Rated lightning impulse withstand voltage 1,2/50  $\mu$ s kV peak 550  
 Rated power-frequency withstand voltage, dry kV r.m.s. 230  
 Rated power-frequency withstand voltage, wet kV r.m.s. 230

**Current ratings**

Rated primary current  $I_{pr}$  A r.m.s. 150 - 300 - 600  
 Rated continuous thermal current  $I_{cth}$  A r.m.s. 180-360-720  
 Rated short-time thermal current  $I_{th}$  / time kA r.m.s./s 31,5-31,5-31,5/1  
 Rated dynamic current  $I_{dyn}$  kA peak 80 - 80 - 80

**Reconnection**

Primary 1:2:4

**Accuracy ratings**

Core No.	Terminals	Ratio A / A	Accuracy	Rct75	No. of terminal box	Cover for sealing
1, 2	[x]S1-[x]S2	150-300-600/5	1-15VA 0,2S ext.120% FS5	-	1	-
3, 4	[x]S1-[x]S2	150-300-600/5	30VA 10P20	-	1	-


[x] – means given number of the core

**Product data**

Dimension drawing 2GKA614717A0657;rev.A  
 Rating plate language Bulgarian  
 Insulator type / colour Composite / grey  
 Minimum creepage distance mm 4411  
 Minimum arcing distance mm 1174  
 Primary terminal type Al flat pad 100x120 T=20 mm;  
 4xD=14/50x50mm  
 Earthing terminals type 2 x  $\phi$ 14 / 45-60mm  
 Secondary terminal type Phoenix rail terminal blocks;  
 spring connection, type ST 10  
 without cable glands;


Cable glands – terminal box No. 1

BOZENA C  
 TRAJER





000673

Withstand test load on primary terminal FR	(Static/Dyn)N	3600/5000
Painting (colour)		
- Housing above insulator		Not painted
- Housing below insulator		Not painted
Total weight	kg	330
Weight of oil	kg	130
Insulating oil type		Nynas Nytro 10XN – Inhibited mineral insulating oil acc. to IEC 60296
Packing		Vertical -3-pack wooden crate
Shipping weight	kg/3unit	1160
Shipping dimensions	cm x cm x cm/3unit	242x106x263
Shipping volume	m3/3unit	6,4



БЕРНО С  
СЕРВИС





**INSTITUTE OF POWER  
ENGINEERING**

DISTRIBUTION EQUIPMENT LABORATORY

01-330 Warsaw, ul Mory 8  
tel./fax. +48 22 836-73-35  
tel. +48 22 345-13-86  
http://www.ieu.com.pl/eur

Page 1/9

**TEST REPORT No. EUR/34/E/14-1 E**

**TEST OBJECT:** Current transformer type PA.145a with spiral composite insulator  
Serial No. 2GKP014A1287155

**MANUFACTURER:** ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

**TESTS ORDERED BY:** ABB Sp. z o.o., ul. Żogańska 1, 04-713 Warszawa  
order No. 4500574872 dated 22.07.2014

**TYPE OF TESTS:** Mechanical tests

**TESTS PROCEDURE:** According to IEC 61869-1:2007 p. 7.4.5

**DATE OF TESTS:** 21.08.2014

**TESTS RESULT:** Positive for  
Fr = 3600 N

Tests result refers only to the test object

**THE TESTS WERE  
WITNESSED BY:**

Test engineer

*Tomasz Kaczmarek*

Tomasz Kaczmarek

Lidia Gruza

HEAD OF LABORATORY

*Lidia Gruza*

Warsaw, 05.09.2014

Publishing or reproducing of this report in other version than exact and complete without permission in writing from the laboratory is forbidden.

000075



**INSTITUTE OF POWER ENGINEERING**

DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/34/E/14-1 E  
Page 2/9

**Contents**

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	3
4. Tests and theirs detailed results	4
5. Test results evaluation	4
Annexes: 1. Photographs taken during the tests	5
2. Documentations delivered by orderer	8

**Report contents:**

numbered pages	9
tables	1
photographs	6



## 1. TEST OBJECT

### 1.1 Description

Current transformer type PA 145a is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of current transformer mounted housing with spiral composite insulator immersed with transformer oil.

### 1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 145 kV  
Rated frequency 50 Hz  
Rated static load 3600 N

### 1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:  
- dimensional drawing current instrument transformer PA 145, No. 2GKA612004, 01.08.2014,

- rating plate,  
- instrument transformer electrical diagram  
prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate.

### 1.4 Preparation for tests

The test object was prepared for test by factory.

## 2. SCOPE OF TESTS

Test program, agreed with orderer, comprised the following tests according to requirements of IEC 61869-1:2007:  
- mechanical tests acc. to item 7.4.5 of above standard for  $F_R = 3600$  N of P1 and P2 3000 A terminals.

During the tests deflection of the transformer shall be recorded.

## 3. TEST AND MEASURING CIRCUITS

For the tests the transformer was fixed to the rigid construction of the test stand. Mechanical tests were performed applying the load consecutively to the transformer's P1 and P2 3000 A terminals as shown on photographs in Annex 1.

000076



## 4. TESTS AND THEIRS DETAILED RESULTS

Tests results presents table 1. The load was increased and released smoothly (30 - 90 s) and was maintained 60 s. During the tests deflection of the transformer was recorded by laser displacement sensor (accuracy of measurement  $\pm 0,1$  mm).

During the tests the following records were made:

- phot. 1 to 6 - current transformer during mechanical tests.  
(Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at  $F = 3620$  N


Test No.	Terminal	Load direction	Test time	Observations
-	-	-	s	-
1	P1	longitudinal	60	During the static load deflection was 16,9 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.
2	P1	transverse	60	During the static load deflection was 21,4 mm. Residual deflection was 1,3 mm. After tests no damage nor oil leak was stated.
3	P1	vertical	60	During the static load deflection was 4,9 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.
4	P2 3000 A	longitudinal	60	During the static load deflection was 16,3 mm. Residual deflection was 1,3 mm. After tests no damage nor oil leak was stated.
5	P2 3000 A	transverse	60	During the static load deflection was 20,9 mm. Residual deflection was 0,3 mm. After tests no damage nor oil leak was stated.
6	P2 3000 A	vertical	60	During the static load deflection was 3,9 mm. Residual deflection was 0,1 mm. After tests no damage nor oil leak was stated.

## 5. TESTS RESULTS EVALUATION


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of tests of tested current transformer is positive for:

$F_R = 3600$  N.





Phot. 3. Vertical load of terminal P1




Phot. 4. Longitudinal load of terminal P2 3000 A


*[Handwritten signature]*



ANNEX 1      Photographs taken during the tests




Phot. 1. Longitudinal load of terminal P1



Phot. 2. Transverse load of terminal P1

ВЕРНО  
СЕРТИФИКАТ





*[Handwritten signature]*

000077


*[Handwritten signature]*



**ANNEX 2** Documentations delivered by orderer



Phot. 5. Transverse load of terminal P2 3000 A



Phot. 6. Vertical load of terminal P2 3000 A

СЕРТИФИКАТ  
ОПРАВДАНИЕ



*Handwritten signature*

000673




**Current Transformer**

Insulation level **145/275/650 KV** Standard **PN-EN 61869-2** Type **PA 145a**  
 Oil type **Nyro Libra** Weight / Oil weight **360 / 120 kg** Temp. range **-40°C → +40°C**  
 S/N **2GKPF014A1287155**

$K_n$  **1500-3000/5-1-5-1-1** A/A  
 $I_n/1s$  **63-63** kA  $I_{dyn}$  **158-158** kA  
 $I_{eth}$  **1800-3600** A

A	VA	Class	FS/ALF	Ext %
1S1-1S2	5	200	0,2	10
2S1-2S2	1	100	0,1	5
3S1-3S2	5	20	5P	60
4S1-4S2	1	35	10P	40
5S1-5S2	1	40	10P	20
6S1-6S2				


Transportation  Vertical /  Horizontal



Instrument transformer electrical diagram

- ATTENTION!**
- HIGH VOLTAGE AT OPEN CURRENT SECONDARY TERMINALS 1S1 - 5S2
  - DURING INSTRUMENT TRANSFORMER OPERATION TERMINAL 1g6 MUST BE EARTHED

FORM C  
OPERATIONAL



Handwritten signature

000679



# INSTITUTE OF POWER ENGINEERING

DISTRIBUTION EQUIPMENT LABORATORY

01-530 Warsaw, ul. Mory 8  
tel./fax. +48 22 836-73-35  
tel. +48 22 345-13-86  
<http://www.ien.com.pl/enr>

Page 1/9

## TEST REPORT No. EUR/34/E/14-2 E

**TEST OBJECT:**

Current transformer type PA 145a with composite insulator  
Serial No. 2GKP014A1287180

**MANUFACTURER:**

ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

**TESTS ORDERED BY:**

ABB Sp. z o.o., ul. Żegalska 1, 04-713 Warszawa  
order No. 4500574872 dated 22.07.2014

**TYPE OF TESTS:**

Mechanical tests

**TESTS PROCEDURE:**

According to IEC 61869-1:2007 p. 7.4.5

**DATE OF TESTS:**

22.08.2014

**TESTS RESULT:**

Positive for  
F<sub>R</sub> = 3600 N

**THE TESTS WERE WITNESSED BY:**

Tests result refers only to the test object

Test engineer

*Tomasz Kaczmarezyk*

HEAD OF LABORATORY

*Lidia Gruza*  
Lidia Gruza

Warsaw, 23.09.2014

000080

Publishing or reproducing of this report in other version than exact and complete without permission in writing from the laboratory is forbidden.



# INSTITUTE OF POWER ENGINEERING

DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/34/E/14-2 E  
Page 2/9

### Contents

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	3
4. Tests and theirs detailed results	4
5. Test results evaluation	4

Annexes: 1. Photographs taken during the tests  
2. Documentations delivered by orderer

### Report contents:

numbered pages	9
tables	1
photographs	6



**1. TEST OBJECT**

**1.1 Description**

Current transformer type PA 145a is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of current transformer mounted housing with composite insulator immersed with transformer oil.

**1.2 Technical data**

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 145 kV  
Rated frequency 50 Hz  
Rated static load 3600 N

**1.3 Technical documentation**

For the purpose of tests the orderer delivered the following technical documentation:  
- dimensional drawing current instrument transformer PA 145a, No. 2GKK612002, 11.09.2014,  
- rating plate,  
- instrument transformer electrical diagram  
prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate.

**1.4 Preparation for tests**

The test object was prepared for test by factory.

**2. SCOPE OF TESTS**


Test program, agreed with orderer, comprised the following tests according to requirements of IEC 61869-1:2007:

- mechanical tests acc. to item 7.4.5 of above standard for  $F_k = 3600$  N of P1 and P2 2000 A terminals.

- During the tests deflection of the transformer shall be recorded.

**3. TEST AND MEASURING CIRCUITS**

For the tests the transformer was fixed to the rigid construction of the test stand. Mechanical tests were performed applying the load consecutively to the transformer's P1 and P2 2000 A terminals as shown on photographs in Annex 1.



000081



**4. TESTS AND THEIRS DETAILED RESULTS**

Tests results presents table 1. The load was increased and released smoothly (30 – 90 s) and was maintained 60 s.

During the tests the following records were made:

- phot. 1 to 6 - current transformer during mechanical tests.  
(Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at  $F = 3620$  N

Test No.	Terminal	Load direction	Test time s	Observations
1	P1	longitudinal	60	During the static load deflection was 32,5 mm. Residual deflection was 0,8 mm. After tests no damage nor oil leak was stated.
2	P1	transverse	60	During the static load deflection was 42,5 mm. Residual deflection was 0,5 mm. After tests no damage nor oil leak was stated.
3	P1	vertical	60	During the static load deflection was 4,5 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.
4	P2 2000 A	longitudinal	60	During the static load deflection was 36,3 mm. Residual deflection was 1,1 mm. After tests no damage nor oil leak was stated.
5	P2 2000 A	transverse	60	During the static load deflection was 39,8 mm. Residual deflection was 0,4 mm. After tests no damage nor oil leak was stated.
6	P2 2000 A	vertical	60	During the static load deflection was 7,0 mm. Residual deflection was 0,1 mm. After tests no damage nor oil leak was stated.

**5. TESTS RESULTS EVALUATION**


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of tests of tested current transformer is positive for:

$F_k = 3600$  N.




ANNEX I

Photographs taken during the tests





Phot. 1. Longitudinal load of terminal P1




Phot. 2. Transverse load of terminal P1

ИЗДАНО С  
ОРИГИНАЛОМ  
С 1980 г.



Phot. 3. Vertical load of terminal P1





Phot. 4. Longitudinal load of terminal P2 2000 A


000082



ANNEX 2 Documentations delivered by orderer




Phot. 5. Transverse load of terminal P2 2000 A



Phot. 6. Vertical load of terminal P2 2000 A

*[Handwritten signature]*

ИЗДАНО  
КОПИРОВАНО



000083



**ABB**

**Current Transformer**

Insulation level	1.45/275/650 kV	Standard	PN-EN 61869-2	Type	PA 145a
Oil type	Nytro Libra	Weight/Oil weight	360 / 120 kg	fn	50 Hz
S/N	2GKP014A1287180	Temp. range	-40°C → +40°C		


$K_n$  1000-2000/5-1-1.5-1-1 A/A

$I_{th}/I_s$  63-63 kA  $I_{dyn}$  159-158 kA

$I_{cth}$  1200-2400 A

	A	VA	Class	FS/ALF	Ext.%
1S1-1S2	5	100	0.2	10	120
2S1-2S2	1	70	0.1	5	120
3S1-3S2	1	35	5P	20	
4S1-4S2	5	15	5P	60	
5S1-5S2	1	30	5P	30	
6S1-6S2	1	10	5P	20	

Transportation | Vertical / Horizontal




Instrument transformer electrical diagram

- ATTENTION!**
- HIGH VOLTAGE AT OPEN CURRENT SECONDARY TERMINALS XS1 - XS2
  - DURING INSTRUMENT TRANSFORMER OPERATION TERMINAL tgd MUST BE EARTHED

000084

ВЕРНО  
СЕРТИФИКАТ



*[Handwritten signature]*

*[Handwritten signature]*





**INSTITUTE OF POWER  
ENGINEERING**

DISTRIBUTION EQUIPMENT LABORATORY

01-330 Warsaw, ul. Mory 8  
tel. fax. +48 22 836-73-35  
tel. +48 22 345-13-86  
http://www.ipen.com.pl/eur

Page 1/9

**TEST REPORT No. EUR/34/E/14-3 E**

**TEST OBJECT:**

Current transformer type PA 145a with porcelain insulator  
Serial No. 2GKFP014A.1287182

**MANUFACTURER:**

ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

**TESTS ORDERED BY:**

ABB Sp. z o.o., ul. Żegańska 1, 04-713 Warszawa  
order No. 4500574872 dated 22.07.2014

**TYPE OF TESTS:**

Mechanical tests

**TESTS PROCEDURE:**

According to IEC 61869-1:2007 p. 7.4.5

**DATE OF TESTS:**

22.08.2014

**TESTS RESULT:**

Positive for  
F<sub>R</sub> = 3600 N

Tests result refers only to the test object

**THE TESTS WERE  
WITNESSED BY:**

Test engineer

*Tomasz Kaczmarczyk*

Tomasz Kaczmarczyk

HEAD OF LABORATORY

*Lidia Gruza*

Lidia Gruza

Warsaw, 23.09.2014

Publishing or reproducing of this report in other version than exact and complete without permission in writing from the laboratory is forbidden.



**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/34/E/14-3 E  
Page 2/9

**Contents**

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	3
4. Tests and theirs detailed results	4
5. Test results evaluation	4
Annexes: 1. Photographs taken during the tests	5
2. Documentations delivered by orderer	8

**Report contents:**

numbered pages	9
tables	1
photographs	6

*[Handwritten signature]*



**1. TEST OBJECT**

**1.1 Description**

Current transformer type PA 145a is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency, 50 Hz. The transformer consists of current transformer mounted housing with porcelain insulator immersed with transformer oil.

**1.2 Technical data**

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 145 kV  
Rated frequency 50 Hz  
Rated static load 3600 N

**1.3 Technical documentation**

For the purpose of tests the order delivered the following technical documentation:  
dimensional drawing current instrument transformer PA 145a, No. 2GKK612001, 11.09.2014,  
- rating plate,  
- instrument transformer electrical diagram  
prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate.

**1.4 Preparation for tests**

The test object was prepared for test by factory.

**2. SCOPE OF TESTS**

Test program, agreed with orderer, comprised the following tests according to requirements of IEC-61869-1:2007:  
- mechanical tests acc. to item 7.4.5 of above standard for  $F_R = 3600$  N of P1 and P2 150 A terminals.

During the tests deflection of the transformer shall be recorded.

**3. TEST AND MEASURING CIRCUITS**

For the tests the transformer was fixed to the rigid construction of the test stand. Mechanical tests were performed applying the load consecutively to the transformer's P1 and P2 150 A terminals as shown on photographs in Annex 1.

000000



**4. TESTS AND THEIRS DETAILED RESULTS**

Tests results presents table 1. The load was increased and released smoothly (30 – 90 s) and was maintained 60 s.

During the tests the following records were made:

- phot. 1 to 6 - current transformer during mechanical tests.  
(Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at  $F = 3620$  N

Test No.	Terminal	Load direction	Test time s	Observations
1	P1	longitudinal	60	During the static load deflection was 9,0 mm. Residual deflection was 1,5 mm. After tests no damage nor oil leak was stated.
2	P1	transverse	60	During the static load deflection was 9,7 mm. Residual deflection was 1,6 mm. After tests no damage nor oil leak was stated.
3	P1	vertical	60	During the static load deflection was 3,2 mm. Residual deflection was 0,1 mm. After tests no damage nor oil leak was stated.
4	P2 150 A	longitudinal	60	During the static load deflection was 7,8 mm. Residual deflection was 1,1 mm. After tests no damage nor oil leak was stated.
5	P2 150 A	transverse	60	During the static load deflection was 9,0 mm. Residual deflection was 1,4 mm. After tests no damage nor oil leak was stated.
6	P2 150 A	vertical	60	During the static load deflection was 3,0 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.

**5. TESTS RESULTS EVALUATION**


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of tests of tested current transformer is positive for:

$F_R = 3600$  N.




**ANNEX 1**

Photographs taken during the tests




**Phot. 1. Longitudinal load of terminal P1**




**Phot. 2. Transverse load of terminal P1**

*[Handwritten signature]*


РЕЦЕНЗІЯ  
СЕРГІЙ СІМОНОВИЧ  
СІМОНОВИЧ



*[Handwritten signature]*



**Phot. 3. Vertical load of terminal P1**



**Phot. 4. Longitudinal load of terminal P2 1.50 A**


*[Handwritten signature]*

000027




**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY


Test report No.  
EUR/34/E/14-3 E  
Page 7/9



Phot. 5. Transverse load of terminal P2 150 A



Phot. 6. Vertical load of terminal P2 150 A



БІЛНО С  
СЕРТИФІКАЦІЯ

880088



**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/34/E/14-3 E  
Page 8/9

**ANNEX 2 Documentations delivered by orderer**

<p>A</p>	<p>B</p>	<p>C</p>	<p>D</p>	<p>E</p>	<p>F</p>	<p>G</p>
<p>ABB ABB Sp. z o.o. Power Products ZAKA612001</p> <p>Project No. 1492014 Current transformer PA 1450 Dimensional drawing Scale 1:5</p> <p>Standard IEC 61859-2</p> <p>Max. operating voltage (kV) 145 Insulating amount (kV) 120 Wind pressure surface (m<sup>2</sup>) 0.65 Creepage distance (mm) 3640 Mechanical load (kN) 3.6 F<sub>1</sub> - Static load (kN) 3.0 F<sub>2</sub> - Dynamic load (kN) 5.0</p> <p>Standard IEC 61859-2</p>						



**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/34/E/14-3 E  
Page 9/9

**ABB**


**Current Transformer**

Insulation level 145/275/650 kV Type PA 145a  
Standard PN-EN 61869-2 fn 50 Hz  
Oil type Nyro Libra Weight/Oil weight 420 / 120 kg Temp. range -40°C → +40°C  
SIN 2GKF014A1287182

$K_n$  150-300/5-1-5-1 A/A  
 $I_{th}/I_S$  20-20 kA  $I_{dyn}$  50-50 kA  
 $I_{th}$  180-360 A

A	VA	Class	FS/ALF	Ext.%
1S1-1S2	5	30	0,2	5 120
2S1-2S2	1	40	5P	20
3S1-3S2	5	60	5P	20
4S1-4S2	1	60	5P	20
5S1-5S2				
6S1-6S2				


Transportation Vertical / Horizontal



Instrument transformer electrical diagram

- ATTENTION!**
- HIGH VOLTAGE AT OPEN CURRENT SECONDARY TERMINALS X51 - X52
  - DURING INSTRUMENT TRANSFORMER OPERATION TERMINAL 1S6 MUST BE EARTHED

ВЕРНО С  
СОСТАВЛЕНА



000080

*(Handwritten scribble)*



**INSTITUTE OF POWER  
ENGINEERING**

DISTRIBUTION EQUIPMENT LABORATORY

01-530 Warsaw, ul.Mory 8  
tel.fax. +48 22 836-73-35  
tel. +48 22 345-13-86  
http://www.ipen.com.pl/eur

Page 1/9

**TEST REPORT No. EUR/34/E/14-4 E**

**TEST OBJECT:**

Current transformer type PA 145a with porcelain insulator  
Serial No. 2GKP014A1287181

**MANUFACTURER:**

ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

**TESTS ORDERED BY:**

ABB Sp. z o.o., ul. Żegajńska 1, 04-713 Warszawa  
order No. 4500574872 dated 22.07.2014

**TYPE OF TESTS:**

Mechanical tests

**TESTS PROCEDURE:**

According to IEC 61869-1:2007 p. 7.4.5

**DATE OF TESTS:**

27.08.2014

**TESTS RESULT:**

Positive for  
Fr = 3600 N

Tests result refers only to the test object

**THE TESTS WERE  
WITNESSED BY:**

Test engineer

*Tomasz Kaczmarczyk*

Tomasz Kaczmarczyk

HEAD OF LABORATORY

*Lidia Gruza*

Lidia Gruza

Warsaw, 23.09.2014

Publishing or reproducing of this report in other version than exact and complete without permission in writing from the laboratory is forbidden.



**INSTITUTE OF POWER ENGINEERING  
DISTRIBUTION EQUIPMENT LABORATORY**

Test report No.  
EUR/34/E/14-4 E  
Page 2/9

**Contents**

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	3
4. Tests and theirs detailed results	4
5. Test results evaluation	4
Annexes: 1. Photographs taken during the tests	5
2. Documentations delivered by orderer	8

**Report contents:**

numbered pages	9
tables	1
photographs	6

050000



## 1. TEST OBJECT

### 1.1 Description

Current transformer type PA 145a is used for supplying of measuring and protection circuits in the network of maximum operating voltage 145 kV and frequency 50 Hz. The transformer consists of current transformer mounted housing with porcelain insulator immersed with transformer oil.

### 1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Maximum operating voltage 145 kV  
Rated frequency 50 Hz  
Rated static load 3600 N

### 1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:  
- dimensional drawing current instrument transformer PA 145a, No. 2GKK612003, 11.09.2019,  
- rating plate,  
- instrument transformer electrical diagram  
prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the rating plate.

### 1.4 Preparation for tests

The test object was prepared for test by factory.

## 2. SCOPE OF TESTS

Test program, agreed with orderer, comprised the following tests according to requirements of IEC 61869-1:2007:  
- mechanical tests acc. to item 7.4.5 of above standard for  $F_R = 3600$  N of P1 and P2 600 A terminals.

During the tests deflection of the transformer shall be recorded.

## 3. TEST AND MEASURING CIRCUITS

For the tests the transformer was fixed to the rigid construction of the test stand. Mechanical tests were performed applying the load consecutively to the transformer's P1 and P2 600 A terminals as shown on photographs in Annex 1.

1600091



## 4. TESTS AND THEIRS DETAILED RESULTS

Tests results presents table 1. The load was increased and released smoothly (30 – 90 s) and was maintained 60 s.

During the tests the following records were made:

- phot. 1 to 6 - current transformer during mechanical tests.

(Annex 1 presents the photographs)

Table 1. Results of static load withstand tests at  $F = 3620$  N

Test No.	Terminal	Load direction	Test time	Observations
1	P1	longitudinal	60	During the static load deflection was 7,5 mm. Residual deflection was 0,3 mm. After tests no damage nor oil leak was stated.
2	P1	transverse	60	During the static load deflection was 4,3 mm. Residual deflection was 0,8 mm. After tests no damage nor oil leak was stated.
3	P1	vertical	60	During the static load deflection was 3,1 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.
4	P2 600 A	longitudinal	60	During the static load deflection was 8,4 mm. Residual deflection was 0,7 mm. After tests no damage nor oil leak was stated.
5	P2 600 A	transverse	60	During the static load deflection was 9,3 mm. Residual deflection was 0,5 mm. After tests no damage nor oil leak was stated.
6	P2 600 A	vertical	60	During the static load deflection was 2,7 mm. Residual deflection was 0,2 mm. After tests no damage nor oil leak was stated.

## 5. TESTS RESULTS EVALUATION


According to criteria given in IEC 61869-1:2007 p. 7.4.5 the results of tests of tested current transformer is positive for:

$F_R = 3600$  N.




**ANNEX 1**

Photographs taken during the tests




Phot. 1. Longitudinal load of terminal P1




Phot. 2. Transverse load of terminal P1


ИЗДАНО С  
ОТВЕТСТВЕННОСТЬЮ



000092



Phot. 3. Vertical load of terminal P1





Phot. 4. Longitudinal load of terminal P2 600 A






ANNEX 2 Documentations delivered by orderer



Phot. 5. Transverse load of terminal P2 600 A



Phot. 6. Vertical load of terminal P2 600 A

РЕПОЗ  
СЕРТИФИКАТ



000093



**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/34/E/14-4 E  
Page 9/9

**ABB**


**Current Transformer**

Insulation level	145/275/650 KV	Standard	IEC 61869-2	Type	PA 145a
Oil type	Nyro Libra	Weight / Oil weight	420 / 120 kg	$f_n$	50 Hz
S/N	2GKPF014A1287181	Temp. range	-40°C → +40°C		

$K_n$	300-600/5-1	A/A
$I_{th}/1S$	40-40 kA	100-100 kA
$I_{th}$	450-900 A	

A	VA	Class	FS/ALF	Ext. %
1S1-1S2	5	40	0.2	5
2S1-2S2	5	60	5P	20
3S1-3S2	1	120	10P	15
4S1-4S2				
5S1-5S2				
6S1-6S2				


Transportation  Vertical  Horizontal



Instrument transformer electrical diagram

- ATTENTION!**
- HIGH VOLTAGE AT OPEN CURRENT SECONDARY TERMINALS XS1 - XS2
  - DURING INSTRUMENT TRANSFORMER OPERATION TERMINAL 4S1 MUST BE EARTHED

000094



КОНТРОЛЬ  
СОБЛЮЖАЮТ

*[Handwritten signature]*

*[Handwritten signature]*



**INSTYTUT ENERGETYKI**  
INSTITUTE OF POWER ENGINEERING  
**LABORATORIUM WIELKOPRAĐOWE**  
HIGH CURRENT LABORATORY

01-330 Warszawa  
ul. Mory 8  
tel. 22 345-1-386  
tel./fax 22 836-80-16  
e-mail: ewp@ien.com.pl  
www.ien.com.pl/ewp



AB 323



**RAPORT Z BADAŃ**  
**NR EWP/47/E/2014-1**

**OBIEKT BADAŃ:** Przekładnik prądowy typu PA 145a  
**PRODUCENT:** ABB Sp. z o.o. Oddział w Przasnyszu  
ul. Leszno 59  
06-300 Przasnysz  
**BADANIA WYKONANO NA ZAMÓWIENIE:** ABB Sp. z o.o. Oddział w Przasnyszu  
ul. Leszno 59  
06-300 Przasnysz  
Zamówienie nr 4500574872 z dnia 22.07.2014 r.

**RODZAJ BADAŃ:** Próba nagrzewania  
**PROCEDURA BADAŃ:** IEC 61869-1:2007, IEC 61869-2:2012, IEC 62271-1:2011, PN-EN 61869-1:2009E, PN-EN 61869-2:2013-06E, PN-EN 62271-1:2009/A1:2011E

**DATA OTRZYMANIA OBIEKTU:** 23.07.2014  
**DATA WYKONANIA BADAŃ:** 30.07-31.07.2014  
**WYNIK BADAŃ:** Pozytywny dla prądu  $I_{rat}=1800A$  (zakres 1500 A)

**W BADAANIACH UCZESTNICZYŁ:**  
**KIEROWNIK BADAŃ:** mgr inż. Mariusz Sul  
**KIEROWNIK LABORATORIUM:** mgr inż. Lidia Gruza

Warszawa, 5.08.2014r.



**INSTYTUT ENERGETYKI**  
**LABORATORIUM WIELKOPRAĐOWE**

Report z badań nr  
EWP/47/E/2014-1

**Spis treści**

1.	Opis obiektu badań
2.	Dane techniczne deklarowane przez Producenta
3.	Dokumentacja techniczna obiektu badań
4.	Zakres badań
5.	Przebieg prób i ich wyniki
6.	Podsumowanie
7.	Opinie i interpretacje
8.	Dokumentacja fotograficzna

Report zawiera 12 stron kolejno numerowanych, w tym:

1	rysunek
1	fotografia
2	załączniki

Wyniki badań odnośnie się wyłącznie do badanego obiektu. Raport z badań zawiera próby z zakresu akredytacji oraz spoza zakresu akredytacji (szczegóły p. 4). Bez pisemnej zgody laboratorium nie zezwala się na publikowanie lub reproduktowanie raportu w innej postaci niż dokładna i kompletna jego kopia.



<b>1. Opis obiektu badań</b>	
Obiekt badań	Przekładnik prądowy
Typ	PA 145a
Numer fabryczny	2GKP014A1287155
Producent	ABB Sp. z o.o. ul. Leszno 59 06-300 Przasnysz
Rok produkcji	2014
Izolator	Kompozytowy
Liczba uzwojeń	5
Typ oleju	Nyro Libra
Droga upływu	3075 mm
Waga oleju	120 kg
Waga całkowita	360 kg
Wymiary	Wg rys. nr 2GKA614301

Laboratorium dokonano identyfikacji obiektu badań na podstawie dostarczonych dokumentów podanych w p. 3, załącznik nr 1. Badany obiekt pokazano na Fot. 1. Obiekt został przygotowany do prób przez Zleceniodawcę.

**2. Parametry deklarowane przez producenta**

Najwyższe napięcie robocze	145 kV
Częstotliwość znamionowa	50 Hz
Prąd znamionowy ciepły długotrwały, $I_{th}$	1800 A
Prąd znamionowy krótkotrwały ciepły, $I_{th}/1s$	63 kA
Prąd znamionowy dynamiczny, $I_{dyn}$	158 kA



Uzwojenie	Prąd znamionowy uzwojeń	Moc znamionowa uzwojenia	Klasa dokładności	FS/ALF	Ext.%
1S1-1S2	5 A	200 VA	0,2	10	120
2S1-2S2	1 A	100 VA	0,1	5	120
3S1-3S2	5 A	20 VA	5P	60	
4S1-4S2	1 A	35 VA	10P	40	
5S1-5S2	1 A	40 VA	10P	20	

**3. Dokumentacja techniczna obiektu badań**

- Rysunek nr 2GKA614301 – Rysunek wymiarowy, „Przekładnik prądowy PA 145”, ABB Sp. z o.o. Power Products, zatwierdzony 01.08.2014
- Rysunek nr 2GKK314141 – „Tor prądowy, pręt 40 Cu, rura 60x4 Al. 3600A”, ABB Sp. z o.o. Power Products, zatwierdzony 24.06.2014
- Protokół sprawdzania przekładnika prądowego, typ PA 145, Nr fabr.: 2GKP014A1287155, ABB Sp. z o.o., Przasnysz, 16.07.2014

**4. Zakres badań**

Uzgodniony ze Zleceniodawcą program badań obejmował:

Lp.	Rodzaj badań	Badania wg wymagań normy	Miejsce wykonania badań
1.	Sprawdzenie nagrzewania	IEC 61869-1:2007 p. 6.4.17.2.2, IEC 61869-2:2012 p.6.4.1.17.2.2.204 IEC 62271-1:2011, tablica 3	EWP

EWP Badanie wykonane w Instytucie Energetyki przez Laboratorium Wielkoprądowe.

A Metoda badań akredytowana przez Polskie Centrum Akredytacji. Certyfikat akredytacji nr AB 323.

000000

**5. Przebieg prób i ich wyniki**

Próba wg IEC 61869-1 p. 6.4 i p. 7.2.2; IEC 61869-2 p.6.4.1 i 7.2.2.204. Przekładnik prądowy został zainstalowany na stanowisku probierczym tak jak w eksploatacji. Zasilanie doprowadzono do zacisków pierwotnych P1- P2/A.

Uzwojenia wtórne obciążono mocami: 1S1-1S2 ⇒ 200 VA, cos φ = 1; 2S1-2S2 ⇒ 100 VA, cos φ = 1; 3S1-3S2 ⇒ 20 VA, cos φ = 1; 4S1-4S2 ⇒ 35 VA, cos φ = 1; 5S1-5S2 ⇒ 40 VA, cos φ = 1.

Uzwojenie pierwotne prądowe P1 i P2/A zwarto na zakresie 1500 A. Na zyczenie Zleceniodawcy prąd w uzwojeniu pierwotnym członu prądowego podczas prób był równy  $I_{zab} = 1800$  A. Próbę wykonywano do ustalenia się temperatur.

Przyrost temperatury uzwojeń mierzono metodą przyrostu rezystancji i obliczano z zależności:

$$\Delta T = \frac{R - R_0}{R_0 \alpha} \cdot R_0 \cdot 0,004$$

Podczas próby, co 1 h wykonywano pomiary rezystancji obciążanych uzwojeń, odczytywano wychylenie wskaźnika poziomu oleju i wskazania termoelementów. Rozmieszczenie termoelementów pokazano na Rys. 1.

Wyciąg z protokołu nagrzewania podano w Tabelicy 1. Zestawienie wyników badań podano w Tabelicy 2.


**Aparatura pomiarowa**

Pomiary temperatury wykonywano termoelementami typu K (NiCr-NiAl) – niepewność pomiaru ± 0,3°C<sup>1</sup>.

Temperaturę otoczenia mierzono termometrami rtęciowymi umieszczonymi w oleju, rozmieszonymi w odległości 1 m wokół obiektu badań, na wysokości 1 m nad podłogą - niepewność pomiaru ± 0,3°C<sup>1</sup>.

Pomiary rezystancji wykonano przy użyciu miernika typu 2291 produkcji Tettex – niepewność pomiaru 0,001 mΩ<sup>1</sup>.

<sup>1</sup> Podane wartości niepewności stanowią niepewności rozszerzone przy poziomie ufności ok. 95 % i współczynniku rozszerzenia k = 2.



Rys. 1. Rozmieszczenie termoelementów podczas próby nagrzewania:

1 – olej (nad cewką prądową), 2 – głowica (przewężenie nad flangą łączącą głowicę z izolatorem), 3 – zacisk P1 (u podstawy pierwotny zacisk), 4 – zacisk P1 (u podstawy zacisku stałego), 5 – zacisk P2/A (u podstawy pierwotny zacisk), 6 – zacisk P2/A (u podstawy zacisku stałego), 7 – termopara wewnątrz przekładnika w torze prądowym 3000 A.

000037



Tablica 1. Wyniki próby nagrzewania przekładnika kombinowanego PA 145a, nr fabr. 2GKP014A1287155

Nr termoelementu	Czas nagrzewania [h]																					
	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
ΔT 1, K	-	2,2	7,8	13,7	18,0	20,8	22,6	24,8	26,6	28,0	29,2	30,3	31,2	31,8	32,5	33,2	33,6	34,1	34,6	35,0	35,3	35,8
ΔT 2, K	-	4,3	8,4	11,9	14,6	16,6	18,0	19,7	21,0	21,7	22,8	23,6	24,3	24,8	25,4	26,0	26,4	26,8	27,2	27,4	27,6	27,9
ΔT 3, K	-	23,2	28,6	31,5	33,0	34,5	35,3	36,7	37,2	37,8	38,5	39,0	39,5	39,8	40,2	40,6	40,7	41,0	41,2	41,5	41,6	41,6
ΔT 4, K	-	28,1	33,6	36,7	38,5	40,2	41,5	43,2	43,7	44,6	45,4	46,2	46,5	47,2	47,4	48,0	48,3	48,7	49,1	49,3	49,6	49,6
ΔT 5, K	-	18,9	24,9	28,4	30,2	31,7	32,5	33,9	34,5	34,9	35,7	36,1	36,5	36,7	37,0	37,5	37,6	38,0	38,3	38,4	38,7	38,8
ΔT 6, K	-	20,5	26,6	30,2	32,4	34,2	35,2	36,8	37,3	38,1	38,7	39,4	39,8	40,2	40,6	40,9	41,1	41,6	41,7	42,0	42,3	42,3
ΔT 7, K	-	15,5	21,9	26,7	29,9	32,7	34,6	36,9	38,2	39,5	40,7	41,7	42,5	43,4	44,0	44,7	45,2	45,8	46,3	46,7	47,1	47,4
T <sub>oil</sub> , °C	23,5	23,8	24,4	25,0	25,2	25,4	25,9	25,7	25,8	25,9	26,0	26,0	26,1	26,1	26,2	26,2	26,3	26,3	26,3	26,4	26,4	26,5
R <sub>IS1-152</sub> mΩ	456,16	464,59	470,27	477,78	485,33	493,04	499,86	506,57	513,30	518,85	524,43	529,73	533,95	538,40	542,29	545,68	548,90	551,77	554,33	556,79	559,01	561,03
R <sub>251-252</sub> Ω	5,5170	5,5999	5,6680	5,7649	5,8571	5,9507	6,0409	6,1256	6,2065	6,2819	6,3514	6,4180	6,4736	6,5272	6,5784	6,6199	6,6608	6,6984	6,7309	6,7621	6,7909	6,8160
R <sub>351-352</sub> mΩ	394,58	605,83	613,91	623,22	633,06	642,73	652,00	660,94	669,79	677,38	684,75	691,84	697,03	702,99	708,27	712,54	716,84	720,86	724,22	727,58	730,37	733,36
R <sub>451-452</sub> Ω	5,7350	5,7923	5,8617	5,9541	6,0492	6,1462	6,2402	6,3307	6,4152	6,4934	6,5667	6,6349	6,6943	6,7507	6,8024	6,8469	6,8887	6,9274	6,9611	6,9945	7,0227	7,0507
R <sub>551-552</sub> Ω	6,0568	6,1347	6,2117	6,3102	6,4123	6,5140	6,6128	6,7085	6,7957	6,8779	6,9536	7,0248	7,0863	7,1449	7,2000	7,2454	7,2885	7,3288	7,3644	7,3990	7,4288	7,4580
R <sub>F1-P2/A</sub> mΩ (zakres 150 A)	0,0657	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
ΔT <sub>IS1-152</sub> K	-	4,6	7,7	11,8	16,0	20,2	24,0	27,6	31,3	34,4	37,4	40,3	42,6	45,1	47,2	49,1	50,8	52,4	53,8	55,2	56,4	57,5
ΔT <sub>251-252</sub> K	-	3,8	6,8	11,2	15,4	19,7	23,7	27,6	31,2	34,7	37,8	40,8	43,3	45,8	48,1	50,0	51,8	53,5	55,0	56,4	57,7	58,9
ΔT <sub>351-352</sub> K	-	4,7	8,1	12,0	16,2	20,2	24,1	27,9	31,6	34,8	37,9	40,9	43,1	45,6	47,8	49,6	51,4	53,1	54,5	55,9	57,1	58,4
ΔT <sub>451-452</sub> K	-	2,5	5,5	9,6	13,7	17,9	22,0	26,0	29,7	33,1	36,3	39,2	41,8	44,3	46,5	48,5	50,3	52,0	53,4	54,9	56,1	57,4
ΔT <sub>551-552</sub> K	-	3,2	6,4	10,5	14,7	18,9	22,9	26,9	30,5	33,9	37,0	40,0	42,5	44,9	47,2	49,1	50,8	52,5	54,0	55,4	56,6	57,8
Wychylenie wskaźnika oleju, mm	0	2	4	5	8	10	13	15	18	21	23	25	26	27	29	30	31	32	32	33	33	33
I <sub>IS1-151</sub> , A	0	6,05	6,06	6,04	6,03	6,05	6,05	6,00	6,04	6,06	6,04	6,04	6,03	6,04	6,04	6,05	6,05	6,03	6,03	6,03	6,03	6,03
I <sub>F1-P2/A</sub> , kA	0	1,815	1,818	1,810	1,806	1,812	1,816	1,801	1,809	1,819	1,815	1,809	1,804	1,806	1,806	1,809	1,809	1,807	1,803	1,803	1,805	1,805



Tablica 1. cd.

Tablica 1. Wyniki próby nagrzewania przekładnika kombinowanego PA 145a, nr fabr. GKP014A1287155

Nr termoelementu	Czas nagrzewania [h]				
	22	23	24	25	26
ΔT 1, K	36,1	36,1	36,5	36,6	37,1
ΔT 2, K	28,2	27,8	28,1	28,2	28,5
ΔT 3, K	42,0	42,1	42,2	42,1	42,4
ΔT 4, K	50,0	50,3	50,3	50,5	50,8
ΔT 5, K	38,9	39,1	39,2	39,2	39,5
ΔT 6, K	42,4	42,6	43,1	43,2	43,6
ΔT 7, K	47,7	47,8	48,2	48,3	48,8
T <sub>oil</sub> , °C	26,5	26,6	26,8	27,0	27,1
R <sub>IS1-152</sub> mΩ	563,10	565,09	566,66	567,97	569,32
R <sub>251-252</sub> Ω	6,8419	6,8629	6,8853	6,9064	6,9209
R <sub>351-352</sub> Ω	735,81	738,66	741,07	743,13	745,24
R <sub>451-452</sub> mΩ	7,0754	7,0989	7,1208	7,1417	7,1608
R <sub>551-552</sub> Ω	7,4834	7,5095	7,5322	7,5530	7,5748
R <sub>F1-P2/A</sub> mΩ (zakres 150 A)	-	-	-	-	0,0881
ΔT <sub>IS1-152</sub> K	58,6	59,7	60,6	61,3	62,0
ΔT <sub>251-252</sub> K	60,0	61,0	62,0	63,0	63,6
ΔT <sub>351-352</sub> K	59,4	60,6	61,6	62,5	63,3
ΔT <sub>451-452</sub> K	58,4	59,5	60,4	61,3	62,2
ΔT <sub>551-552</sub> K	58,9	60,0	60,9	61,8	62,7
Wychylenie wskaźnika oleju, mm	34	34	34	35	35
I <sub>IS1-151</sub> , A	6,05	6,01	6,04	6,05	6,04
I <sub>F1-P2/A</sub> , kA	1,809	1,803	1,807	1,807	1,807



Tablica 2. Przyrosty temperatur uzyskane podczas próby nagrzewania przekładnika PA 145a nr fabr. 2GKPO14A1287155

Uzwojenie	$\Delta T$ [K]	$\Delta T_{dep}$ [K]	
1S1-1S2	62,0	65 <sup>1), 2)</sup>	
2S1-2S2	63,6		
3S1-3S2	63,3		
4S1-4S2	62,2		
5S1-5S2	62,7		
Nr termo-elementu	Miejsce pomiaru termoelementem	$\Delta T$ [K]	$\Delta T_{dep}$ [K]
1	olej	37,1	55 <sup>1), 2)</sup>
2	Głowica (przełożenie nad flangą łączącą głowicę z izolatorem)	28,5	40 <sup>3)</sup>
3	Zacisk P1 (u podstawy pierścienia zacisków)	42,4	
4	Zacisk P1 (u podstawy zacisku stałego)	50,8	
5	Zacisk P2/A 3000A (u podstawy pierścienia zacisków)	39,5	65 <sup>3)</sup>
6	Zacisk P2/A 3000A (u podstawy zaciska stałego)	43,6	
7	Tor prądowy 3000 A	48,8	65 <sup>1), 2)</sup>

<sup>1)</sup> wg IEC 61869-1, <sup>2)</sup> wg IEC 61869-2, <sup>3)</sup> wg IEC 62271-1,  $\Delta T$  - przyrost temperatury;  $\Delta T_{dep}$  - wartość dopuszczalna w stanie ustalonym


6. Podsumowanie

W badanym przekładniku prądowym typu PA 145a z izolatorem kompozytowym, w wyniku próby nagrzewania prądem  $I_{gn} = 1800$  A na zakresie 1500 A, nie stwierdzono przekroczenia dopuszczalnych przyrostów temperatur. Badany przekładnik spełnił wymagania norm: IEC 61869-1:2007, IEC 61869-2:2012 i IEC 62271-1:2011.

7. Opinie i interpretacje

Brak

8. Dokumentacja fotograficzna




Fot. 1. Przekładnik prądowy na stanowisku probierczym podczas próby nagrzewania


000009



Załącznik nr 2.



Załącznik nr 1.



0010CC





**HIGH VOLTAGE LABORATORY**  
**INSTYTUTU ENERGETYKI**  
 01-330 WARSZAWA, ul. Mory 8, tel. (22)3451242  
 tel. fax. 836-80-48, e-mail: ewn@ien.com.pl

EWN/11/E/12-2  
**APPENDIX**  
**1**


*[Handwritten mark]*

*[Handwritten text]*

**APPENDIX 1 for test report EWN/11/E/12-2**



Documents provided by ABB Sp. z o.o. used as base of identification of test object:


- Manufacturer Conformity Declaration
- Dimension drawing No. 2GKA614117 (19.01.2012)
- Electric diagram of Current instrument transformer
- Drawing of rated nameplate



*[Handwritten signature]*


000101

 ABB Sp. z o.o.	Declaration of conformity	ABB Sp. z o.o. Dept. in Przasnysz POLAND
<p align="center"><b>DECLARATION OF CONFORMITY No. 001/PA_IEN/2012</b>          (acc. to ISO/IEC 17050-1)</p>		
Manufacturer:	ABB Sp. z o.o. Dept. in Przasnysz	
Address:	Str. Leszno 59 06-300 Przasnysz / POLAND	
Product:	Current transformer type PA 123/145	
Above mentioned product conforms with the following standard :		
Standard IEC 60044 - 1	Title Current transformers	Edition/Date 1.2 / Feb. 2003
Additional information: Serial numbers: <b>2GKP011A1084700; 2GKP011A1084701; 2GKP011A1084704; 2GKP011A1084705.</b>		
Place and date of issue of declaration Przasnysz 02.04.2012.		
..... (Name)		 ..... (Signature)
Dyrektor, Centralnej Jachociki Biznesu Wzrostu i Nispiq ABB Sp. z o.o. Paweł Radecki		



Instrument transformer electrical diagram

- ATTENTION!
1. HIGH VOLTAGE AT OPEN SECONDARY TERMINALS
  2. TERMINAL MARKED "19" DURING NORMAL OPERATION MUST BE EARTHED



<p>ABB ABB Sp. z o.o. Power Products Document No. ZCKA614117</p>		<p>Scale: 1:15 A3</p>	
<p>Current transformer PA 145 / PA 123 Dimensional drawing</p>		<p>Approved by: 19.01.2012 Checked by: 19.01.2012 Issued by: 19.01.2012</p>	
<p>Standard IEC 60044-1</p>		<p>Maximum operating voltage (kV) 145</p>	
<p>Mechanical load Fg - Dynamic load (kN) 3.6 Fg - Static load (kN) 3.6</p>		<p>Total weight (kg) 360 Insulating oil amount (kg) 90 Wind pressure surface (m<sup>2</sup>) 0.65 Creepage distance (mm) 3800</p>	
<p>Earthing terminal Flat terminals - Aluminum alloy DIN 46206-3 F1</p>		<p>Mechanical load</p>	
<p>Oil level indicator</p>		<p>Lifting eye D=43mm</p>	
<p>Composite insulator / Isolator / Izolator / Izolator kompozitny</p>		<p>Rating plate</p>	
<p>For fixing Cable glands 2x R40</p>		<p>Oil draining valve</p>	
<p>Secondary terminal box</p>		<p>Dimensions in mm</p>	



**HIGH VOLTAGE LABORATORY**  
**INSTYTUTU ENERGETYKI**

01-330 WARSZAWA, ul. Mory 8, tel. (22)3451242  
 tel. fax. 836-80-48, e-mail: ewn@icn.com.pl

EWN/11/E/12-2

**APPENDIX**

**2**



### Current Transformer

Insulation level	145/275/650 kV	Standard	IEC 60044-1	Type	PA 145
Oil type	Nytró Libra	Weight / oil	360 / 90 kg	fn	50 Hz
SN	84700 / 11	Temp. range	-40°C → +40°C		

$K_n$	50-100-200/5-1-5-1	A/A
$I_{th}/1s$	40-50-50 kA	100-125-125 kA
$I_{cth}$	100-200-400 A	

1S1-1S2 2S1-2S2 3S1-3S2 4S1-4S2 5S1-5S2 6S1-6S2

A	5	1	5	1
VA	5	5	10	10
CL	0,5	0,5	5P	5P
FS/ALF	5	5	10	10
Ext.%	200	200		


Transportation  Vertical /  Horizontal

### APPENDIX 2 for test report EWN/11/E/12-2

Reports of routine test and determination of errors of current transformer type PA 123 performed in Factory Laboratory of ABB sp. z o.o.

- Tests before type test and special test (Measurements before type test and special tests) - 2GKP011A1084700 - 19.01.2012.
- Tests after type test and special tests completed (Measurements after type test and special test completed) - 2GKP011A1084700 - 26.03.2012.

ВАРНО С  
ОРИГИНАЛА



000103

<b>ABB Sp. z o.o.</b> 06-300 Przasnysz ul. Leszno 59		<b>TYPE:</b> PA 123 / PA 145	
<b>Serial no:</b> 2GKP011A1084700		<b>Rated ratio [A/A]</b>	
<b>lth 1s [kA]:</b>	<b>lch [A]:</b>	<b>Insulation level:</b>	<b>50 Hz</b>
40-50-50	100-125-125	145/275/650 kV	IEC 60044-1
<b>Winding</b>	<b>Isn [A]</b>	<b>Sn [VA]</b>	<b>class</b>
1S1-1S2	5	5	0,5FS 5
2S1-2S2	1	5	0,5FS 5
3S1-3S2	5	10	5P 10
4S1-4S2	1	10	5P 10


**List of performed tests:**

1. Oil dielectric parameters check before transformer filling (oil after treatment):  
lg δ : IEC 60247, breakdown voltage : IEC 60158
2. Verification of terminal markings
3. Oil tightness test oil overpressure: 0,8 bar / 24h - no traces of oil leakage
4. Power-frequency withstand test on primary windings
5. Partial discharge measurement
6. Power-frequency withstand test on secondary windings
7. Inter-turn overvoltage test for current transformers
8. Determination of errors
9. Verification of secondary limiting c.m.f. (check of instrument security factor (FS) and accuracy limit factor (ALF))  
- R<sub>1</sub> = 100 MΩ  
- R<sub>2</sub> = 3000 MΩ
10. Measurement of primary windings insulation resistance (1kV DC)
11. Measurement of secondary windings insulation resistance (2,5kV DC)
12. Measurement of capacitance and dielectric dissipation factor - lg δ
13. Determination of core magnetization characteristics
14. Measurement of windings' resistance

**Oil dielectric parameters check before transformer filling (oil after treatment)**

- Measurement of oil lg δ according to IEC 60247  
lg δ = 0.08 %; electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90°C ±1°C
- Measurement of oil breakdown voltage according to IEC 60156  
Mean breakdown voltage = 81,43 kV, Relative standard deviation = 5,07 %;  
f = 50Hz, oil temp. = 25 °C, measurement with the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	83.9
2	85.2
3	77.8
4	86.2
5	78.7
6	78.8



*[Handwritten signature]*

00010A

**Partial discharge measurement...**

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary windings)
- Stress voltage: 275 kV / 60 s
- Frequency: 50 Hz

Test voltage	1,2 Um / √3 = 180,5 kV
Level of partial discharge	2,5 pC
	2,7 pC

Remarks: background noise level: 1,6 pC (measured after voltage switch off), measuring circuit was calibrated with 5pC (calibrating charge)

**Inter-turn overvoltage test for current transformers**

Winding	Peak voltage on secondary winding [kV/peak]	Current in primary winding [A]
1S1-1S2	0.128	400
2S1-2S2	0.608	400
3S1-3S2	0.256	400
4S1-4S2	1.12	400

**Determination of errors (ΔI%), (δI mV), cos φ = 0,8 lagging (cos φ = 1 for S < 5VA)**

1S1-1S2: 5 VA		1S1-1S2: 1,25 VA	
ΔI	0,05 In	0,05 In	0,05 In
δI	0,845	0,218	0,247
ΔI	30,0	14,4	17,4
δI	14,4	-1,2	8,6
ΔI	0,05 In	0,05 In	0,05 In
δI	0,845	0,218	0,247
ΔI	30,0	14,4	17,4
δI	14,4	-1,2	8,6
ΔI	0,05 In	0,05 In	0,05 In
δI	0,845	0,218	0,247
ΔI	30,0	14,4	17,4
δI	14,4	-1,2	8,6

**1pN (A): 100**

1S1-1S2: 5 VA		1S1-1S2: 1,25 VA	
ΔI	0,05 In	0,05 In	0,05 In
δI	0,845	0,218	0,247
ΔI	30,0	14,4	17,4
δI	14,4	-1,2	8,6
ΔI	0,05 In	0,05 In	0,05 In
δI	0,845	0,218	0,247
ΔI	30,0	14,4	17,4
δI	14,4	-1,2	8,6

**1pN (A): 200**

1S1-1S2: 5 VA		1S1-1S2: 1,25 VA	
ΔI	0,05 In	0,05 In	0,05 In
δI	0,845	0,218	0,247
ΔI	30,0	14,4	17,4
δI	14,4	-1,2	8,6
ΔI	0,05 In	0,05 In	0,05 In
δI	0,845	0,218	0,247
ΔI	30,0	14,4	17,4
δI	14,4	-1,2	8,6

3S1-3S2: 10 VA	4S1-4S2: 10 VA
ΔI: 0.536	1.0 In
ΔI: 0.223	ΔI
ΔI: 12.6	ΔI: 12.9

Measurements uncertainty:  $\Delta I = \pm 0.045\%$ ,  $\delta I = \pm 2.3$  min

Verification of secondary limiting a.m.f.  
(check of instrument security factor (FS) and accuracy limit factor (ALF))

Winding	e.m.f. [V]	I <sub>exc</sub> measured [A]	I <sub>exc</sub> required [A]	Condition
1S1-1S2	5.91	> 5	> 2.5	✓
2S1-2S2	27.02	> 1	> 0.5	✓
3S1-3S2	21.48	0.55	< 2.5	✓
4S1-4S2	105.17	0.12	< 0.5	✓

Measurement of capacitance and dielectric dissipation factor - tg δ  
Temperature: 22.2 °C, Frequency: 50 Hz

Primary voltage	Tg δ [%]	Capacitance [pF]	Leakage current [mA]
10 kV	0.22	973	3.133
33 kV	0.22	973	19.16
71 kV	0.22	973	21.74

Measurement of windings' resistance

	R (22 °C)	Ref (75 °C)
P1-P2 range 50A	252.0 μΩ	304.5 μΩ
P1-P2 range 100A	80.0 μΩ	96.7 μΩ
P1-P2 range 200A	32.0 μΩ	38.7 μΩ
1S1-1S2	0.036 Ω	0.043 Ω
2S1-2S2	0.410 Ω	0.495 Ω
3S1-3S2	0.030 Ω	0.036 Ω
4S1-4S2	0.528 Ω	0.638 Ω

ВЕРНО С  
ОРИГИНАЛА




*Handwritten signature*

*Handwritten signature*


000105

Determination of core magnetization characteristics:


1. Winding 1S1-1S2; f = 50Hz




2. Winding 2S1-2S2; f = 50Hz



3. Winding 3S1-3S2; f = 50Hz



4. Winding 4S1-4S2; f = 50Hz



000100

Rating plate:



### Current Transformer


Insulation level	145/275/650 KV	Standard	IEC 60044-1	Type	PA 145
Oil type	Nyro Libra	Weight / oil	360 / 90 kg	fn	50 Hz
SN	84700 / 11	Temp. range	-40°C → +40°C		

$K_n$	50-100-200/5-1-5-1	A/A
$I_{th}/I_s$	40-50-50 kA	100-125-125 kA
$I_{cth}$	100-200-400 A	


1S1-1S2 2S1-2S2 3S1-3S2 4S1-4S2 5S1-5S2 6S1-6S2

A	5	1	5	1
VA	5	5	10	10
CL	0,5	0,5	5P	
FS/ALF	5	5	10	10
Ext.%	200	200		

Transportation: Vertical / Horizontal



Electrical diagram plate:



Przasnysz, 2012-01-19

Checked by: *[Signature]* OG-4  
K-21

The tests were witnessed by:

Representative of  
**HIGH VOLTAGE LABORATORY**  
**INSTYTUT ENERGETYKI**  
01-330 WARSZAWA, Mory 8

*[Signature]*  
Kierownik Wydziału Przemysłowego  
Instytut Energetyki  
Przasnysz, ul. Leszno 59  
*[Signature]*  
Paweł Dąbek

*[Signature]*

000107

<b>ABB Sp. z o.o.</b>		<b>Routine test report</b>		<b>TYPE: PA 123 / PA 145</b>	
06-300 Przasnysz		of current transformer		Serial no: 2GKP011A1084700	
ul. Leszno 59		after dielectric type tests		Insulation level: IEC 60044-1	
lth 1s [kA]:	ldyn [kA]:	lcth [A]:	Insulation level:	50 Hz	
40-50-50	100-125-125	100-200-400	145/275/650 kV		
<b>Winding</b>	<b>Isn [A]</b>	<b>Sn [VA]</b>	<b>class</b>	<b>Rated ratio [A/A]</b>	
1S1-1S2	5	5	0,5FS 5	50-100-200/5	
2S1-2S2	1	5	0,5FS 5	50-100-200/1	
3S1-3S2	5	10	5P 10	50-100-200/5	
4S1-4S2	1	10	5P 10	50-100-200/1	

List of performed tests:

1. Power-frequency withstand test on primary windings
2. Partial discharge measurement
3. Power-frequency withstand test on secondary windings
4. Inter-turn overvoltage test for current transformers
5. Determination of errors
6. Verification of secondary limiting e.m.f. (check of instrument security factor (FS) and accuracy limit factor (ALF))
7. Measurement of secondary windings insulation resistance (1kV DC)
8. Measurement of primary windings insulation resistance (2.5kV DC)
9. Measurement of capacitance and dielectric dissipation factor - tg δ
10. Measurement of windings' resistance

- Up = 220 kV/60s, f = 50Hz  
 - Up = 3 kV/60s, f = 50Hz  
 - lower value (U peak=4,5kV or U peak at lcth) / 60s  
 - R >= 100 MΩ  
 - R >= 3000 MΩ

Partial discharge measurement

- Measurement according to procedure A
- (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary windings)

Stress voltage: 220 kV / 60 s  
 Frequency: 50 Hz

Test voltage	1,2 Um / √3 = 174 kV	1,2 Um / √3 = 100,5 kV
Level of partial discharge	8 pC	2,5 pC

Remarks: background noise level: 1,3 pC (measured after voltage switch off), measuring circuit was calibrated with 5pC (calibrating charge)

Inter-turn overvoltage test for current transformers

Winding	Peak voltage on secondary winding [kV/peak]	Current in primary winding [A]
1S1-1S2	0,128	400
2S1-2S2	0,608	400
3S1-3S2	0,286	400
4S1-4S2	1,15	400

Determination of errors (Δ%), (δ) min, cos φ = 0,8 lagging (cos φ = 1 for S < 5VA)

IpN (A): 50

1S1-1S2: 5 VA		0,05 In		1,0 In		2,0 In		1S1-1S2: 1,25 VA	
ΔI	-0,847	-0,578	-0,087	0,074	0,250	0,230	0,257	0,289	0,05 In
δI	29,9	14,2	-1,2	-3,9	22,3	16,5	8,3	5,5	0,2 In
2S1-2S2: 5 VA		0,05 In		1,0 In		2,0 In		2S1-2S2: 1,25 VA	
ΔI	-0,651	-0,382	0,003	0,153	0,05 In	0,382	0,347	0,345	0,05 In
δI	27,3	12,4	0,7	-1,1	16,5	12,4	7,2	5,5	1,0 In

3S1-3S2: 10 VA		4S1-4S2: 10 VA	
ΔI	1.0 In	ΔI	1.0 In
ΔI	0.518	ΔI	0.219
ΔI	13.4	ΔI	13.1

IpN (A): 100

1S1-1S2: 5 VA		1S1-1S2: 1.25 VA	
ΔI	0.05 In	ΔI	0.05 In
ΔI	-0.843	ΔI	0.234
ΔI	29.8	ΔI	16.5
ΔI	14.3	ΔI	8.3
ΔI	-1.1	ΔI	5.7
ΔI	-3.9	ΔI	5.7

IpN (A): 100

2S1-2S2: 5 VA		2S1-2S2: 1.25 VA	
ΔI	0.05 In	ΔI	0.05 In
ΔI	-0.845	ΔI	0.234
ΔI	28.2	ΔI	16.5
ΔI	12.4	ΔI	8.3
ΔI	-1.0	ΔI	5.7
ΔI	-1.0	ΔI	5.7

IpN (A): 200

1S1-1S2: 5 VA		1S1-1S2: 1.25 VA	
ΔI	0.05 In	ΔI	0.05 In
ΔI	-0.884	ΔI	0.234
ΔI	33.3	ΔI	16.5
ΔI	15.4	ΔI	8.3
ΔI	-2.0	ΔI	5.7
ΔI	-2.0	ΔI	5.7

IpN (A): 200

2S1-2S2: 5 VA		2S1-2S2: 1.25 VA	
ΔI	0.05 In	ΔI	0.05 In
ΔI	-0.823	ΔI	0.234
ΔI	28.4	ΔI	16.5
ΔI	12.4	ΔI	8.3
ΔI	-1.0	ΔI	5.7
ΔI	-1.0	ΔI	5.7

Measurements uncertainty: ΔI = ±0.045%, δI = ±2.3 min

Verification of secondary limiting e.m.f.  
(check of instrument security factor (FS) and accuracy limit factor (ALF))

Winding	e.m.f. [V]	I <sub>exc</sub> measured [A]	I <sub>exc</sub> required [A]	Condition
1S1-1S2	5.90	> 5	> 2.5	<input checked="" type="checkbox"/>
2S1-2S2	27.02	> 1	> 0.5	<input checked="" type="checkbox"/>
3S1-3S2	21.47	0.53	< 2.5	<input checked="" type="checkbox"/>
4S1-4S2	105.16	0.12	< 0.5	<input checked="" type="checkbox"/>

Measurement of capacitance and dielectric dissipation factor - tg δ

Temperature: 22.3 °C, Frequency: 50 Hz

Primary voltage	Tg δ [%]	Capacitance [pF]	Leakage current [mA]
10 kV	0.22	973	3.188
63 kV	0.22	973	18.24
71 kV	0.22	973	21.73

807000

Measurement of windings' resistance

	R (22.8 °C)	Ret (75 °C)
P1-P2 range 50A	256.0 μΩ	308.5 μΩ
P1-P2 range 100A	83.0 μΩ	100.0 μΩ
P1-P2 range 200A	34.0 μΩ	41.0 μΩ
1S1-1S2	0.036 Ω	0.043 Ω
2S1-2S2	0.410 Ω	0.494 Ω
3S1-3S2	0.030 Ω	0.036 Ω
4S1-4S2	0.528 Ω	0.636 Ω

Rating plate:



Current Transformer

Insulation level	145/275/650 kV	Standard	IEC 60044-1	fn	50 Hz
Oil type	Nytro Libra	Weight / oil	360 / 90 kg	Temp. range	-40°C → +40°C
SN	84700 / 11				
Type					PA 145

K <sub>n</sub>	50-100-200/5-1-5-1	A/A
I <sub>th</sub> /I <sub>S</sub>	40-50-50	kA / dyn
I <sub>cth</sub>	100-200-400	A

1S1-1S2	2S1-2S2	3S1-3S2	4S1-4S2	5S1-5S2	6S1-6S2
A	5	1	5	1	
VA	5	5	10	10	
CI	0.5	0.5	5P	5P	
FS/ALF	5	5	10	10	
Ext.%	200	200			

Transportation: Vertical / Horizontal






**HIGH VOLTAGE LABORATORY**  
**INSTYTUTU ENERGETYKI**  
 01-330 WARSZAWA, ul. Mory 8, tel. (22)3451242  
 tel. fax. 836-80-48, e-mail: ewn@ien.com.pl

EWN/11/E/12-2  
**APPENDIX**  
**3**


**APPENDIX 3 for test report EWN/11/E/12-2**

Report of performed tests in Distribution Equipment Laboratory  
 of Institute of Power Engineering in Warsaw.  
 Test Report No. EUR/12/E/12-1E  
 (Mechanical tests.)

BRUNO  
 C...



Electrical diagram plate:



**Instrument transformer electrical diagram**

- ATTENTION!**
1. HIGH VOLTAGE AT OPEN SECONDARY TERMINALS
  2. TERMINAL MARKED "16" DURING NORMAL OPERATION MUST BE EARTHED

Przasnysz, 2012-03-26

Kierownik Wydziału Produkcji  
 Ograniczników i Przekładniczków WN  
 ABB Sp. z o.o.  
 Oddział w Przasnyszu  
*D. Paweł*

The tests were witnessed by:

Representative of  
**HIGH VOLTAGE LABORATORY**  
**INSTYTUT ENERGETYKI**  
 01-330 WARSZAWA, Mory 8



Checked by: *GOSI*





**INSTITUTE OF POWER  
ENGINEERING**

DISTRIBUTION EQUIPMENT LABORATORY

01-350 Warsaw, ul Mory 8  
tel./fax. +48 22 836-73-35  
tel. +48 22 345-13-86

Page 1/9

**TEST REPORT No. EUR/12/E/12-1E**

**TEST OBJECT:** Current transformer type PA 145 / PA 123 with composite insulator  
Serial No. 84700/11

**MANUFACTURER:** ABB Sp. z o.o. Division in Przasnysz, ul. Leszno 59, 06-300 Przasnysz

**TESTS ORDERED BY:** Internal order No. EWN/11/E/12 dated 10.05.2012

**TYPE OF TESTS:** Mechanical tests

**TESTS PROCEDURE:** According to IEC 60044-1:1996+A1:2000+A2:2002

**DATE OF TESTS:** 28.03.2012

**TESTS RESULT:** Positive for  
 $F_R = 3600$  N and resulting dynamic load

Tests result refers only to the test object

**THE TESTS WERE  
WITNESSED BY:**

Test engineer

*Tomasz Kaczmarek*  
Tomasz Kaczmarek

**HEAD OF LABORATORY**

*Lidia Gruza*  
Lidia Gruza

Warsaw, 14.05.2012

Publishing or reproducing of this report in other version than exact and complete without permission in writing from the laboratory is forbidden.

0100110




**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/12/E/12-1E  
Page 2/9

**Contents**

1. Test object	3
1.1. Description	3
1.2. Technical data	3
1.3. Technical documentation	3
1.4. Preparation for tests	3
2. Scope of tests	3
3. Test and measuring circuits	4
4. Tests and theirs detailed results	4
5. Test results evaluation	4
Annexes: 1. Photographs taken during the tests	5
2. Documentations delivered by orderer	8

БІСНО С  
СЕРТИФІКАЦІЯ



*[Handwritten signature]*

**Report contents:**

numbered pages	9
tables	1
photographs	6

*[Handwritten signature]*



## 1. TEST OBJECT

### 1.1 Description

Current transformer type PA 145 / PA 123 is used for supplying of measuring and protection circuits in the network of highest voltage for equipment 145/123 kV and frequency 50 Hz. The transformer consists of current transformer mounted in composite enclosure immersed with transformer oil.

### 1.2 Technical data

The Manufacturer attributed the following construction data to the test object.

Highest Voltage for Equipment	145/123 kV
Rated frequency	50 Hz
Rated continuous thermal current	50 A, 100 A, 200 A
Rated short-time current	40 kA, 50 kA, 50 kA
Rated dynamic current	100 kA, 125 kA, 125 kA
Rated static load	3600 N

### 1.3 Technical documentation

For the purpose of tests the orderer delivered the following technical documentation:  
- dimensional drawing current transformer PA 145 / PA 123, No. 2GKA614117, 19.01.2012,  
- rating plate  
prepared by ABB Sp. z o.o. (Annex 2).

The laboratory proceeded the identification of test object on the base of above documentation and the nameplate.

### 1.4 Preparation for tests

The test object was prepared for test by factory.

## 2. SCOPE OF TESTS

Test program, agreed with orderer, comprised the following tests according to requirements of IEC 60044-1:1996+A1:2000+A2:2002:  
- mechanical tests acc. to item 9.3 of above standards for  $F_k = 3600$  N and resulting dynamic load of terminals P1 and P2 200 A.

000111



## 3. TEST AND MEASURING CIRCUITS

For the tests the transformer was fixed to the rigid construction of the test stand. Mechanical tests were performed applying the load consecutively to the transformer's terminals as shown on photographs 1 to 6 in Annex 1.

## 4. TESTS AND THEIRS DETAILED RESULTS

Mechanical tests were performed 28.03.2012. Tests results present table 1.  
During the tests the photos were made (Annex 1 presents the photographs)  
- phot. 1 to 6 - current transformer during mechanical tests

Table 1. Results of static load withstand tests at  $F = 3620$  N and dynamic<sup>\*)</sup>

Test No.	Terminal	Load direction	Test time	Observations
-	-	-	s	-
1	P1	longitudinal	60	After tests no damage nor oil leak was stated.
2	P1	longitudinal	dyn. <sup>*)</sup>	After tests no damage nor oil leak was stated.
3	P1	transverse	60	After tests no damage nor oil leak was stated.
4	P1	transverse	dyn. <sup>*)</sup>	After tests no damage nor oil leak was stated.
5	P1	vertical	60	After tests no damage nor oil leak was stated.
6	P1	vertical	dyn. <sup>*)</sup>	After tests no damage nor oil leak was stated.
7	P2	longitudinal	60	After tests no damage nor oil leak was stated.
8	P2	longitudinal	dyn. <sup>*)</sup>	After tests no damage nor oil leak was stated.
9	P2	transverse	60	After tests no damage nor oil leak was stated.
10	P2	transverse	dyn. <sup>*)</sup>	After tests no damage nor oil leak was stated.
11	P2	vertical	60	After tests no damage nor oil leak was stated.
12	P2	vertical	dyn. <sup>*)</sup>	After tests no damage nor oil leak was stated.


Remarks:

<sup>\*)</sup> Dynamic tests were performed by sudden loading the terminal by the weight 3620 N.

## 5. TESTS RESULTS EVALUATION

According to criteria given in IEC 60044-1:1996+A1:2000+A2:2002 the results of tests of tested current transformer is positive for:

-  $F_k = 3600$  N and resulting dynamic load.



Handwritten signature




**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY


Test report No.  
EUR/12/E/12-1E  
Page 5/9

ANNEX I

Photographs taken during the tests



Phot. 1. Longitudinal load of terminal P1




Phot. 2. Longitudinal load of terminal P2 200 A




**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY


Test report No.  
EUR/12/E/12-1E  
Page 6/9



Phot. 3. Transverse load of terminal P1




Phot. 4. Transverse load of terminal P2 200 A





C30112


ANNEX 2 Documentations delivered by orderer



ВСТУПНО С  
 СЕРТИФИКАТ



Phot. 5. Vertical load of terminal P1



Phot. 6. Vertical load of terminal P2 200 A



**INSTITUTE OF POWER ENGINEERING**  
DISTRIBUTION EQUIPMENT LABORATORY

Test report No.  
EUR/12/E/12-1E  
Page 9/9

**ABB**  
**Przekładnik prądowy**

Typ obciąż. NF  
Typ obciąż. 145276500 KV  
Typ obciąż. 24700 / 11  
Typ obciąż. 360 / 90 kg  
Typ obciąż. 50 Hz  
Typ obciąż. 40°C

Norma PN EN 60044-1  
Waga  
Temperatura pracy

Typ PA 145PA 123  
In 50 Hz  
-40°C

Typ 50-100-200S-1S-1 A/A  
40-20-20 BA 100-125-125 VA  
100-200-400 A

10-100-200-400 A

A	VA	KL	Prąd	Prąd
6	6	0.5	6	10
1	5	0.5	6	10
5	10	0.5	6	10
10	10	0.5	6	10
200	200	0.5	6	10

Transport  Factory

*Handwritten signature*

000114



**HIGH VOLTAGE LABORATORY**  
INSTYTUTU ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22)3451242  
tel. fax. 836-80-48, e-mail: ewn@ien.com.pl


EWN/11/E/12-2

**APPENDIX**

4

**APPENDIX 4 for test report EWN/11/E/12-2**

Lightning impulse test. Impulse 1,2/50  $\mu$ s, full and chopped:  
 Oscillograms of test currents and detection currents.



WSPRÓC  
CERTYFIKACJA

*Handwritten signature*

*Handwritten signature*



**Lightning impulse test of the current transformer**

project: ewm11e12-u2 test date: 30-03-2012 page 1

**Test - object - data**

WNR EWN/11/E/12-2 TR-No. 84700/11 O.-No.

test object PA145 vector group 650 Hz  
output kVA BIL  
voltage 145 kV frequency 50 Hz

customer ABB Sp. z o. o., ul. Zeganska 1, 04-713 Warszawa

no.	Up [kV]	T1 [µs]	T2 [µs]	Tc [µs]	remark
1	-324.7	1.09	51.4		LI: P1 - RW(50.0%)
2	-649	1.1	51.7		LI: P1 - FW(100.0%)
3	-375.5	1.1		3.32	LI: P1 - CRW(57.5%)
4	-745	1.13		3.32	LI: P1 - OFW(115.0%)
5	-744.6	1.13		3.37	LI: P1 - OFW(115.0%)
6	-649.7	1.1	51.7		LI: P1 - FW(100.0%)
7	-649.6	1.09	51.8		LI: P1 - FW(100.0%)
8	-649.9	1.1	51.8		LI: P1 - FW(100.0%)
9	-650.2	1.09	51.7		LI: P1 - FW(100.0%)
10	-649.8	1.09	51.8		LI: P1 - FW(100.0%)
11	-648.9	1.09	51.8		LI: P1 - FW(100.0%)
12	-649.4	1.1	51.8		LI: P1 - FW(100.0%)
13	-649.7	1.1	51.7		LI: P1 - FW(100.0%)
14	-649.5	1.1	51.8		LI: P1 - FW(100.0%)
15	-649.7	1.09	51.8		LI: P1 - FW(100.0%)
16	-648.7	1.09	51.9		LI: P1 - FW(100.0%)
17	-649.1	1.1	51.9		LI: P1 - FW(100.0%)
18	-649.6	1.1	51.8		LI: P1 - FW(100.0%)
19	-649.8	1.1	51.8		LI: P1 - FW(100.0%)
20	325.9	1.09	51.6		LI: P1 - RW(50.0%)
21	651.2	1.1	52.1		LI: P1 - FW(100.0%)
22	650.7	1.09	52.1		LI: P1 - FW(100.0%)
23	650.7	1.1	52.1		LI: P1 - FW(100.0%)
24	650.8	1.09	52.2		LI: P1 - FW(100.0%)
25	650.1	1.1	52.2		LI: P1 - FW(100.0%)
26	650.3	1.09	52.1		LI: P1 - FW(100.0%)
27	650.2	1.09	52.1		LI: P1 - FW(100.0%)
28	649.5	1.1	52.2		LI: P1 - FW(100.0%)
29	650.2	1.1	52.1		LI: P1 - FW(100.0%)

030115



**Lightning impulse test of the current transformer**

project: ewm11e12-u2 page 2

no.	Up [kV]	T1 [µs]	T2 [µs]	Tc [µs]	remark
30	650	1.1	52.1		LI: P1 - FW(100.0%)
31	649.1	1.09	52.3		LI: P1 - FW(100.0%)
32	650.5	1.1	52.1		LI: P1 - FW(100.0%)
33	649	1.1	52.3		LI: P1 - FW(100.0%)
34	649.2	1.09	52.3		LI: P1 - FW(100.0%)
35	650	1.1	52.2		LI: P1 - FW(100.0%)

BIURO C  
OPRACOWANIA



*[Handwritten signature]*




# HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mocy 8  
fax: (+4822) 836-80-48, mail: ewm@ien.com.pl

Lightning impulse test of the current transformer

project: ewm11e12-u2

page 3



911003




# HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mocy 8  
fax: (+4822) 836-80-48, mail: ewm@ien.com.pl

Lightning impulse test of the current transformer

project: ewm11e12-u2

page 4



Stamp: *Handwritten signature*  
 2001-12-02  
 1200 210700










# HIGH VOLTAGE LABORATORY

POLAND 01-330 WARSZAWA, ul. Mory 8  
fax: (+4822) 835-80-48, mail: ewn@ten.com.pl

Lightning impulse test of the current transformer

project: ewn11e12-u2

page 7



# HIGH VOLTAGE LABORATORY INSTYTUTU ENERGETYKI

01-330 WARSZAWA, ul. Mory 8, tel. (22)3451242  
tel. fax. 835-80-48, e-mail: ewn@ten.com.pl

EWN/11/E/12-2

## APPENDIX

5

### APPENDIX 5 for test report EWN/11/E/12-2

Transmitted overvoltage measurement:

- Oscillograms of measured transmitted to secondary windings overvoltages.

СЕРТИФИКАТ  
СТАРЫЙ МАШИНА







*PS*


*[Handwritten signature]*

000118

Transmitted overvoltage measurement of PA 145 factory number 84700/11



84700/11



Handwritten signature

000119

# LABORATORIUM WYSOKICH NAPIĘĆ



## INSTYTUTU ENERGETYKI



LABORATORY ACCREDITED  
BY THE POLISH CENTRE FOR ACCREDITATION  
Accreditation Certificate of Testing Laboratory  
No AB 272

### TEST REPORT

No. EWN/11/E/12-2

Tests of current instrument transformer type PA 123 (PA 145) for insulation level  
LI 650kV/AC 275kV, manufactured by ABB sp. z o.o.

Warsaw, March 2012

021000



## HIGH VOLTAGE LABORATORY INSTYTUT ENERGETYKI

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@ien.com.pl

EWN/11/E/12-2

Page 2/18

### TESTS REPORTS No EWN/11/E/12-2

#### TEST OBJECT:

Current instrument transformer type PA 123 (PA145)  
Serial No: 2GKP011A1084700 (84700/11)

#### TEST ORDERED BY:

ABB Sp. z o.o.  
04-713 Warszawa, ul. Żegalska 1

#### ORDER NO:

4500380553/2 - 20.01.2012

#### SCOPE OF TEST:

Selected type tests and special tests

#### PROCEDURA OF TESTS:

in accordance with standards:

PN-EN 60044-1:2000 (EN 60044-1:1999)

January 2012

#### RECEIVING OBJECT DATE:

#### DATE OF TESTS:

January 2012 - March 2012

#### TESTS RESULTS:

are presented in following parts of report  
Test results are concern to tested object only.

Tests was performed in witness of representatives of ABB sp. z o.o.:

Marcin TARNOWSKI M.Sc.E.E.

Paweł DEBSKI M.Sc.E.E.

Jarosław DUZDOWSKI M.Sc.E.E.

Zbigniew WESOŁOWSKI M.Sc.E.E.

#### TEST PERFORMER:

Jan SZOKALSKI  
M.Sc.E.E.

#### TEST OVERSEERER:

Jerzy MIKOŁAJCZYK  
M.Sc.E.E.

#### HEAD OF HIGH VOLTAGE DEPARTMENT:


January L. MIKULSKI,  
Ass. Prof., Dr. hab. E. E.

Warsaw, March 2012

Reproduction or publishing of Reports in form other than complete without writing permission of Laboratory  
is strictly forbidden

	SIGNATURE
	SIGNATURE
	SIGNATURE

021000





**HIGH VOLTAGE LABORATORY**  
**INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@icm.com.pl

EWN/11/E/12-2

Page 3/18

**CONTENTS**

1. COMPETENCE OF LABORATORY	4
2. DESCRIPTION OF TEST OBJECT	5
3. AGREED SCOPE OF TESTS	6
4. PERFORMED TESTS	8
4.0 Routine test and determination of errors before tests in IEn and after tests finishing	8
4.1 Lightning impulse test	9
4.2 Wet test for outdoor transformers	10
4.3 Determination of errors	11
4.4 Radio interference voltage measurement	13
4.5 Chopped impulse test on the primary winding	15
4.6 Measurement of capacitance and dielectric dissipation factor	15
4.7 Mechanical tests	16
4.8 Transmitted overvoltage measurement	16
5. SUMMARY	17
6. LIST OF APPENDIXES	18

The Report contain:

- 18 numbered pages
- In Report are presented:
  - 5 drawing
  - 1 numbered table
  - 6 appendixes
  - and non numbered diagrams and tables

000121



**HIGH VOLTAGE LABORATORY**  
**INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@icm.com.pl

EWN/11/E/12-2

Page 4/18

**1. COMPETENCE OF THE LABORATORY**


The High Voltage Laboratory of Institute of Power Engineering (IEn) in Warsaw is in possession of accreditation issued by the Polish Centre for Accreditation (Accreditation Certificate of Testing Laboratory No AB 272) concerning following tests:

Insulators and insulator strings	-	lightning and switching impulse tests
	-	power-frequency voltage 50 Hz tests
	-	radio interference measurements
Distribution substations	-	lightning and switching impulse tests
	-	power-frequency voltage 50 Hz tests
	-	radio interference measurements
Circuit breakers, disconnectors	-	lightning and switching impulse tests
	-	power-frequency voltage 50 Hz tests
	-	radio interference measurements
Insulators	-	lightning and switching impulse tests
	-	power-frequency voltage 50 Hz tests
	-	radio interference measurements
Current and voltage transformers	-	lightning and switching impulse tests
	-	power-frequency voltage 50 Hz tests
	-	lightning and switching impulse tests
Power transformers	-	power-frequency voltage 50 Hz tests
	-	lightning and switching impulse tests
Lightning arresters and limiters	-	power-frequency voltage 50 Hz tests
	-	lightning and switching impulse tests
Cables and cable fittings	-	lightning and switching impulse tests

Note! Tests described in sub-clauses 4.8, hereby Report are not comply the scope of Laboratory accreditation.

Hereby Report concerning test results obtained in other competent laboratories - (see Appendixes 2,3) :

- Distribution Equipment Laboratory of Institute of Power Engineering in Warsaw having Accreditation Certificate PCA Nr AB 324
- High Current Laboratory of Institute of Power Engineering in Warsaw having Accreditation Certificate PCA Nr AB 323
- Factory Laboratory of ABB sp. z o.o. in Przasnysz - Regional Verification Office in Warsaw - determination of errors and test in range of type tests at supervision of representative of High Voltage Laboratory of Institute of Power Engineering in Warsaw.





**HIGH VOLTAGE LABORATORY  
INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@ten.com.pl

EWN/11/E/12-2

Page 5/18

**2. DESCRIPTION OF TEST OBJECT**

The tested object was current instrument transformer type PA 123 (Pa 145) manufactured by ABB sp. z o.o. 04-713 Warszawa, ul. Zegańska 1, had following parameters:

- Serial number 2GKP011A1084700 (84703/11)
- Rated primary current 50 - 100 - 200 A
  - Rated short-time current  $I_{th}/1s$  40 - 50 - 50 kA
  - Rated dynamic current  $I_{dyn}$  100 - 125 - 125 kA
  - Rated frequency 50 Hz
  - Rated insulation level LI 550kV/AC 230kV<sup>\*)</sup>
  - Minimum creepage distance 3800 mm (composite insulator)

**\*) Attention ! All voltage test was performed for insulation level LI 650kV/AC 275kV (for current transformer type PA 145).**

View of rated nameplates of tested transformers show figure 1.




Fig. 1 Rated nameplate of tested transformer



**HIGH VOLTAGE LABORATORY  
INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@ten.com.pl

EWN/11/E/12-2

Page 6/18

Identification of tested object was done at following documents attached to hereby Report (Appendix 1):

- Manufacturer Conformity Declaration,
- Dimension drawing No. 2GKA614117 (19.01.2012),
- Electric diagram of Current instrument transformer,
- Drawing of rated nameplate.


**3. AGREED SCOPE OF TESTS**

According to ordered selected tests were done comply following standards:

- PN-EN 60044-1:2000 + A1:2003 + A2:2004 „Przekładniki. Część 1: Przekładniki prądowe” (EN-60044-1:1999 + A1:2000 + A2:2003 „Instrument transformers. Part 1: Current transformers”).

On request of ordering party the additional special test were performed. The performed test results are contained in Table 1.

01.12.2012  
Ciepła Barcza



000122



**HIGH VOLTAGE LABORATORY  
INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@ten.com.pl

EWN/11/E/12-2

Page 7/18

Table 1. List of performed tests

Item	Performed tests	Requirement
<b>TYPE TESTS</b>		
1	Lighting impulse test	PN EN 60044-1, p.7.3
2	Wet test for outdoor transformers	PN EN 60044-1, p.7.4
3	Determination of errors	PN EN 60044-1, p. 11.4, 11.6, 12.4
4	Measurement of the radio interference voltage (RIV)	PN EN 60044-1/A1, p. 7.5
<b>SPECIAL TESTS</b>		
5	Chopped impulse test on the primary winding	PN EN 60044-1, p. 9.1
6	Measurement of capacitance and dielectric dissipation factor	PN EN 60044-1, p. 9.2
7	Mechanical test	PN EN 60044-1, p. 9.3
8	Transmitted overvoltage measurement	PN EN 60044-1/A2, p. 9.3

During mentioned above tests at Factory Laboratory of ABB sp. z o.o. in Przasnysz Leszno 59 Street, were performed determination of errors of transformer to prove positive results of consecutive tests. The complete tests were performed according to mentioned above standards. The tests were supervised by representatives of High Voltage Laboratory of Institute of Power Engineering in Warsaw in purpose to prove results of tests. The tests stands are under authority of Regional Verification Office in Warsaw (No. stand S08/OUM1-5/01 XVI i S08/OUM1-5/01 XVII).

000123



**HIGH VOLTAGE LABORATORY  
INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@ten.com.pl

EWN/11/E/12-2

Page 8/18

**4. PERFORMED TESTS**

**4.0 Routine test and determination of errors before tests in IEn and after tests finishing.**

Before delivery the transformer to IEn Laboratory and after type test and special test completed in ABB Factory Laboratory in Przasnysz were performed determination of errors measurement under supervision of representative of IEn. During test were checked:


- verification of terminals marking,
- power-frequency withstand test on the primary winding 50 Hz,  $U_{test} = 275 \text{ kV}$ ,  $t = 60 \text{ s}$ ,
- partial discharge measurement for current transformers  $q < 10 \text{ pC}$  ( $U_m$ )  $q < 5 \text{ pC}$  ( $1.2 \cdot U_m / \sqrt{3}$ ),
- power-frequency withstand test on secondary windings 50 Hz,  $U_{test} = 3 \text{ kV}$ ,  $t = 60 \text{ s}$ ,
- power-frequency withstand test between sections 50 Hz,  $U_{test} = 4,5 \text{ kV}$ ,  $t = 60 \text{ s}$ ,
- determination of errors.

The test results are presented in reports attached to hereby Report (Appendix 2):

- Tests before type test and special test (Measurements before type test and special tests) - Report No. 2GKP011A1084700 - 19.01.2012,
- Tests after type test and special tests completed (Measurements after type test and special test completed) - 2GKP011A1084700 - 26.03.2012.

**It were proved that all tests required in routine test gave positive results. It were proved that all metrological properties of transformer are comply accurate classes for all winding.**

These tests results are base for later determination of errors for purpose of verification result of tests described below.





#### 4.1 Lightning impulse test

Test was done in test arrangement of surge generator type Haefely 5 MV, 375 kJ. Equivalent circuit diagram is shown on Figure 2. The test was performed on standardized lightning impulse 1,2/50µs. The purpose of test was checking internal insulation of transformer. The influence of atmospheric condition on test voltage value was not taken into consideration.

The Lightning impulse test was performed jointly with chopped impulse test on the primary winding (clause 3.8 of hereby Report).

#### Test condition:

- Full impulse test voltage  $U = 650$  kV,
- Chopped impulse test voltage  $1,15 - 650$  kV =  $747,5$  kV,
- Sequence of impulses:
  - positive polarity – 15 full impulses,
  - negative polarity – 1 full impulse, 2 chopped impulses, 14 full impulses,
- During test was recorded test voltage and current flowed through along of current transformer.




Fig. 2 Equivalent circuit diagram of test arrangement for lightning impulses:

$C_1 = 0,125 \mu\text{F}$ ,  $C_2 = 1,2 \text{ nF}$ ,  $R_1 = 175 \Omega$ ,  $R_2 = 600 \Omega$ ,  $R_3 = 8,95 \Omega$ .

Measurement uncertainty – 1,5 %

The oscillograms not shows failures of transformer insulation.

Result of test - positive.

Recorded oscillograms of all applied impulses are shown in Appendix No. 5 of hereby Report.

*[Handwritten signature]*



#### 4.2 Wet test for outdoor transformers

The test was performed in arrangement of test transformer type TuR 700kV, 0,5A, according to standard PN-EN 60060-1:2011 (EN 60060-1:2010). Equivalent circuit diagram is presented on Figure 3.




Fig. 3 Equivalent circuit diagram for power frequency voltage 50 Hz:

$C = 200 \text{ pF}$  ( $C'$  in series with  $C'$ )

Measurement uncertainty – 1,5 %

During wet test for outdoor transformers the transformer was wetting by artificial rain at parameters:

- vertical component of precipitation  $H_v = 1,6 \text{ mm/min}$
- horizontal component of precipitation  $H_h = 1,7 \text{ mm/min}$
- water electrical resistivity  $\rho = 98 \Omega\text{m}$

The test voltage  $U = 275 \text{ kV}$  (corrected according to density of air) was applied during 1 minute.

During test were not observed any flashover or failure of insulation.

Test result - positive.

СТАНДАРТ  
ОПТИМАЛІА








Fig. 4 Wet test of current transformers type PA 123 (PA 145) at power frequency voltage 50 Hz.

#### 4.3 Determination of errors

##### 4.3.1 Determination of errors

Measurements of errors for current transformers was performed in Factory Laboratory of ABB sp. z o.o. in Przasnysz 59 Leszno 59 Street, under supervision of representative of IEN.

The measurement was done two times:

- Tests before type test and special test (Measurements before type test and special tests) - Report No. 2GKP01.1A.1084700 - 19.01.2012,
- Tests after type test and special tests completed (Measurements after type test and special test completed) - Report No. 2GKP01.1A.1084700 - 26.03.2012.

Detailed information about tests results consists Appendix No. 2 of hereby Report.

000125



Analyzing test results for current transformer was found that:

- For measurement windings 1S1-1S2(5A) class 0,5S FS5 and 2S1-2S2(1A) class 0,5FS5:
  - for currents  $0,05 I_n$ , current error  $\Delta I(\%) < 1,5\%$  and phase displacement  $\delta_\phi(\text{min}) < 90$  min.
  - for currents  $0,20 I_n$ , current error  $\Delta I(\%) < 0,75\%$  and phase displacement  $\delta_\phi(\text{min}) < 45$  min.
  - for currents  $1,0 I_n$  i  $1,2 I_n$ , current error  $\Delta I(\%) < 0,5\%$  and phase displacement  $\delta_\phi(\text{min}) < 30$  min.
- For protective windings 3S1-3S2(5A) class 5P10 and 4S1-2S2(1A) class 5P10:
  - for currents  $1,0 I_n$ , current error  $\Delta I(\%) < 1\%$  and phase displacement  $\delta_\phi(\text{min}) < 60$  min.

For each of current windings values of error are contain in range compatible to appropriate class of accuracy.

##### 4.3.2 Verification of instrument security factor FS of current part measurement windings of instrument transformer

The tested current transformer has two measurement windings:

1S1-1S2  $\rightarrow I_n = 5$  A,  $S_n = 5$ VA, class 0,5S FS5;

2S1-2S2  $\rightarrow I_n = 1$  A,  $S_n = 5$ VA, class 0,5 FS5.

The results of determination of core magnetization characteristics and verification of limiting e.m.f (check of instrument security factor (FS)) are present in Report No. 2GKP01.1A.1084700 - 19.01.2012- (Appendix No. 2 of hereby Report).

It was found that instrument security factor FS is equal to 5 for measurement windings of current transformer is determined properly.


Test result - positive.

##### 4.3.3 Verification of Limits of error ALF for protective winding of current part of instrument transformer

The tested combined transformer has two windings for protection purposes:

3S1-3S2  $\rightarrow I_n = 5$  A,  $S_n = 10$ VA, class 5P10;

4S1-4S2  $\rightarrow I_n = 1$  A,  $S_n = 10$ VA, class 5P10.





The results of determination of core magnetization characteristics and verification of limiting e.m.f (check of accuracy limit factor (ALF)) are present in No. 2GKP011A.1084700 - 19.01.2012- (Appendix No. 2 of hereby Report).

It was found that limit of error ALF equal 10 for windings for protection of current transformer is determined properly.  
 Test result - positive.

**4.4 Radio interference voltage measurement**

Following to requirement of IEC/CISPR 18-2 the measurements was performed in testing arrangement as is show on Figure 5. The interference voltage was measured on resistance 300Ω at frequency 0.5 MHz. To determinate coefficient of correction +24 dB before measurement the instrument was calibrated by stable signal generator. To measurement of interference voltage the instrument LMZ-5 was used. The level of background was checked for range of test voltages 0 - 150 kV. Interference voltages originated form testing arrangement, radio broadcasts etc., were below 5μV (14 dB).

According to PN EN 60044-1/A1 interference voltage at voltage  $U_p=1.1 \cdot U_m / \sqrt{3} = 92$  kV has not to exceed the value  $RIV_{dop} = 2500 \mu V$ .  
 The instrument had logarithmic scale:

$$RIV_{dop} = 2500 \mu V \rightarrow 68 \text{ dB} \text{ (0 dB = } 1 \mu V \text{)}$$

Before the test, the instrument transformer was supplied with voltage  $1.5 \cdot U_m / \sqrt{3}$ , held for 30 sec. Next, within about 10 sec the voltage was decreased to value  $1.1 \cdot U_m / \sqrt{3}$ , held for 30 sec.

The measurements were done at test voltages in range  $0.3 \div 1.1 \cdot U_m / \sqrt{3}$ . Test voltage was decreased step by step with value  $0.1 \times U_p$  since  $U_p=1.1 \cdot U_m / \sqrt{3}$  up to value  $U_p=0.3 \cdot U_m / \sqrt{3}$ . Next, voltage was increased by this same values and finally decreased again. For each of test voltage the measurement of radio interference voltage were performed and registered level in last series of decreasing voltage was drawn in function of test voltage  $U_{test}$ .





Fig. 5 Test arrangement for Radio interference voltage measurement

The results of measurements are present in Table and diagram below.

Up [kV]	92	84	75	67	59	50	42	33	25
$xU_m/\sqrt{3}$	1.1	1.0	0.9	0.8	0.7	0.6	0.5	0.4	0.3
[dB]	→	6	5	2	0	-1	-2	-5	-
	←	6	3	2	0	-1	-3	-5	-
[dB]	→	6	3	2	0	-1	-3	-5	-
Wynik [μV]	32	25	20	16	14	11	9	-	-



Measured Radio Interference Voltage  $RIV = 32 \mu V$  (30dB) is much less than permissible level  $RIV_{perm} = 2500 \mu V$  (68dB).  
 Test result - positive.



**HIGH VOLTAGE LABORATORY**  
**INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@icm.com.pl

EWN/11/E/12-2

Page 15/18

**4.5 Chopped impulse test on the primary winding**

Chopped Impulse Test was supplemented to Lightning Impulse test 1.2/50µs and was described in clause 4.3 of hereby Report.

Recorded oscillograms not show of failure of insulation of current transformers.  
Test result - positive.

Oscillograms of all applied impulses are present in Appendix No. 4 of hereby Report.

**4.6 Measurement of capacitance and dielectric dissipation factor**

The measurement was performed st at ABB's Factory Laboratory (Raports No. 2GKP011A1084700 – 19.01.2012 and No. No. 2GKP011A1084700 – 26.03.2012 of Factory Laboratory ABB sp. z o.o. Przasnysz Division).

Condition of measurements:

$U_p = 10 \text{ kV}$ ;  $110/\sqrt{3} \text{ kV} = 63.5 \text{ kV}$ ;  $123/\sqrt{3} \text{ kV} = 71 \text{ kV}$   
Ambient temperature during measurement was 22,2°C and (22,3°C).

Test results are present in table below:

$U_p$ [kV]	$C_x$ [pF]	$\text{tg}\delta$ [%]
10	973 (973)	0,22 (0,22)
63,5	973 (973)	0,22 (0,22)
71	973 (973)	0,22 (0,22)

The standard specifications for capacitance and dissipation factor for instrument transformers not provide criterion for these parameters. The Standard PN-EN 60044-1:2000 (EN 60044-1:1999) only contain note that value of dissipation factor is usually less than 0,5%.

000127



**HIGH VOLTAGE LABORATORY**  
**INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: ewn@icm.com.pl

EWN/11/E/12-2

Page 16/18

**4.7 Mechanical tests**

The mechanical tests were performed in Distribution Equipment Laboratory of Institute of Power Engineering in Warsaw. The test consist in applying to the transformer mechanical load – static and dynamic, in three direction in turn. Static load was 20% higher than standard requirement for II class of load. The test conditions were as follow:

$$F_R = 3600 \text{ N}, \quad t = 60 \text{ s}$$

It was assumed that dynamic load is 1.4 times higher than static load.

During the tests behaving of current transformer was correct. After test not stated any damages or oil leakage.

Test result - positive.

Detailed information about test arrangement, performed tests and tests results, are present in Report No. EUR/12/E/12-1E – 28.03.2012 – (Appendix 3).

**4.10 Transmitted overvoltage measurement**

During the test to the HV terminal of transformer were applied impulse voltage.


It were recorded maximal value of overvoltages which came in each secondary windings - both current and voltage. According to requirement of Standard for impulse 0.5/50 µs and value

$$U_{\text{test}} = 1,6 \times \sqrt{2} \times U_{\text{pr}}/\sqrt{3} \approx 189 \text{ kV}$$

the values of transmitted overvoltages can not exceed 1,6 kV.

During all measurements to the transformer were applied lightning impulses at value ten times less, that is  $U_1 = 16 \text{ kV}$ . Concerning linear of phenomenon, registered overvoltages should have values less than 160 V (peak-to- peak value).

Registration was don by digital oscilloscope of "Dr. Strauss" with input impedance 50 Ω and transmission band 200 MHz.





**HIGH VOLTAGE LABORATORY  
INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: evn@ten.com.pl

EWN/11/E/12-2

Page 17/18

Results of test are present in table below.

Winding	Overvoltage value $U_{pe}/2 \times 10$ [V]
1S1-1S2	346
2S1-2S2	314
3S1-3S2	420
4S1-4S2	398

It was found that for each of secondary winding of transformer transmitted overvoltages not exceed value of 1600 V.  
Test result - positive.

The oscillograms of all applied and registered impulses are present in Appendix No.6 of hereby Report.

**5. SUMMARY**

- The current instruments transformer type PA 123 (PA 145) manufactured by ABB sp. z o.o. 04-713 Warszawa, ul. Żegalska 1, with parameters described in clause 2 of hereby Report and identified on base provided documents (as presented in Appendix No. 1) was performed.
  - The current instruments transformer type PA 123 (PA 145) for insulation level LI 650kV/ /AC 275kV passed positively selected type test according to requirement of standard: PN-EN 60044-1:2000 + A1:2003 + A2:2004 „Przekładniki „Przekładniki prądowe” (EN-60044-1:1999 + A1:2000 + A2:2003 „Instrument transformers. Part 1: Current transformers”).
- and according program described in Table 1, clause 3 of hereby Report.

000128



**HIGH VOLTAGE LABORATORY  
INSTYTUT ENERGETYKI**

POLAND 01-330 WARSZAWA, ul. Mory 8, tel. (+48 22) 836-80-48,  
fax (+48 22) 836-80-48 e-mail: evn@ten.com.pl

EWN/11/E/12-2

Page 18/18

**6. LIST OF APPENDIXES**

**Appendix No. 1**

Documents provided by ABB Sp. z o.o. used as base of identification of test object:

- Manufacturer Conformity Declaration
- Dimension drawing No. 2GKA614117 (19.01.2012)
- Electric diagram of Current instrument transformer
- Drawing of rated nameplate

**Appendix No. 2**

Reports of routine test and determination of errors of current transformer type PA 123 performed in Factory Laboratory of ABB sp. z o.o.

- Tests before type test and special test (Measurements before type test and special tests) - Report No. 2GKP011A1084700 - 19.01.2012,
- Tests after type test and special tests completed (Measurements after type test and special test completed) - 2GKP011A1084700 - 26.03.2012.

**Appendix No. 3**

Report of performed tests in Distribution Equipment Laboratory of Institute of Power Engineering in Warsaw.

- Test Report No. EUR/12/E/12-1E (Mechanical tests.)

**Appendix No. 4**


Lightning impulse test. Impulse 1,2/50  $\mu$ s, full and chopped:

- Oscillograms of test currents and detection currents.

**Appendix No. 5**

Transmitted overvoltage measurement:

- Oscillograms of measured transmitted to secondary windings overvoltages.





INSTYTUT ENERGETYKI (INSTITUTE OF POWER ENGINEERING)  
Zespół ds. Certyfikacji (Certification Department)

PRODUCT EVALUATION REPORT

Nr DZC/135c/E/2014-1

Product name and symbol: HV current transformer, single-phase,  
outdoor, type: PA 123a

Supplier: ABB Sp. z o.o., Oddział w Przasnyszu, ul. Leszno 59,  
06-300 Przasnysz

621029

Warsaw, February 2015 r.



INSTYTUT ENERGETYKI Report  
Zespół ds. Certyfikacji No DZC/135c/E/2014-1  
page / pages  
2 / 11

Author: Grażyna Wieczorek M. Sc.

Contents:

- 1. Introduction 3
- 2. List of applied documents 4
- 3. Testing laboratory competences 5
- 4. Test result list 5
  - 4.1. Type tests 5
  - 4.2. Routine tests 6
- 5. Summary 9

APPENDIX - Type test reports, special test reports and Manufacturer's Statement (pages not numbered)

Non-conformities observed:

None found

General evaluation result:

Positive  
Based on the analysis made, herewith I conclude for granting of compliance certificates to the HV current transformers type PA 123a, with composite or ceramic insulator, manufactured by ABB Sp. z o.o., Oddział w Przasnyszu

Grażyna Wieczorek

Full name

signature

26.02.2015

date

## 1. Introduction

Report from evaluation of HV overhead, single-phase, current transformer series, types: PA 123a, manufactured by ABB Sp. z o.o., Oddział w Przasnyszu, was developed within the certification process carried out by Zespół ds. Certyfikacji (Certification Team) upon manufacturer's application (Contract No DZC/135c/E/2014 of the 06th October 2014)

This document concerns the new series of current instrument transformers featuring design modifications and type marked: PA 123a.

The PA 123a current transformers are designed for feeding measurement and protection systems in electrical power grids with the highest system voltage of 123 kV and frequency of 50 Hz. Current transformers consist of a current element located inside an enclosure with a composite insulator (cover configuration: straight and spiral) or with a ceramic insulator filled with transformer oil.

The PA 123a current transformer series tests were carried out on selected representatives at the laboratories of Instytut Energetyki (Institute of Power Engineering) in Warsaw and Instytut Elektrotechniki (Electrotechnical Institute) in Warsaw as well as (within the range of product tests and errors measurements) at the manufacturer's laboratory. The selection procedure of measurement transformer representatives included the most severe conditions resulting from the current transformer design and occurring during the temperature-rise tests, short-circuit withstand, voltage and mechanical tests such as: values of continuous and short-circuit currents, winding wire cross-section, different main circuits, power of windings for measurement and protection, housing types, accuracy classes, etc. Tests were carried out on eleven selected transformer prototypes. The results are valid for the entire transformer series acc. to the list as suggested for certification. Test results confirming the transformers features are listed in the reports in cl. 2 of this document. The test results were compared against requirements of the following standards:

- PN-EN 61869-1:2009  
Instrument transformers – Part 1: General requirements
- PN-EN 61869-2:2013-06  
Instrument transformers – Part 2: Detailed requirements for current transformers
- PN-EN 61869-3:2011  
Instrument transformers – Part 3: Detailed requirements for voltage transformers
- PN-EN 60529:2003  
Protection class provided by the housing (IP)
- PN-EN 62262:2003  
Degrees of protection against external mechanical impacts as provided by electric device enclosures (IK coding)


000120

Customer/manufacturer: ABB Sp. z o.o., Przasnysz holds the complex certificate for the following standards: ISO 9001:2008, ISO 14001:2004 and PN-N-18001:2004 – certificate No 0198 150 01525 issued by TÜV Rheinland Polska Sp. z o.o.

## 2. List of applied documents

The current transformers design and the test results were evaluated and analysed based on the following documents delivered by the Manufacturer and included in the reports:

- D1. Report No EWP/10/E/2014-1e, Temperature-rise test -PVA 145a (360 A), IEn, High Current Laboratory, Warsaw, January 2014
- D2. Report No EWP/47/E/2014-1e, Temperature-rise test -PA 145a (1800 A), IEn, High Current Laboratory, Warsaw, January 2014 r.
- D3. Report No EWP/35/E/2013-1e, Temperature-rise test -PVA 145a (2400 A), IEn, High Current Laboratory, Warsaw, January 2014 r.
- D4. Report No EWP/35/E/2013-2e, Temperature-rise test -PVA 145a (900 A), IEn, High Current Laboratory, Warsaw, January 2014 r.
- D5. Test Report No 8595/A/NZL/NBR/15, Temperature-rise test -PA 145a (3000 A), IEl, Distribution Equipment Test Laboratory Warsaw, January 2015 r.
- D6. Report No EUR/34/E/14-1 E, Mechanical tests, IEn, Distribution Equipment Laboratory Warsaw, September 2014 r.
- D7. Report No EUR/34/E/14-2 E, Mechanical tests, IEn, Distribution Equipment Laboratory Warsaw, September 2013 r.
- D8. Report No EUR/34/E/14-3 E, Mechanical tests, IEn, Distribution Equipment Laboratory Warsaw, September 2014 r.
- D9. Report No EUR/34/E/14-4 E, Mechanical tests, IEn, Distribution Equipment Laboratory Warsaw, September 2014 r.
- D10. Report No EUR/71/E/13-3 E, Short-time current test, Test for composite error, test of strength against short-circuit in the secondary circuit, IEn, Distribution Equipment Laboratory Warsaw, January 2014 r.
- D11. Report No EUR/74/E/13 E, Short-time current test, Test for composite error, IEn, Distribution Equipment Laboratory Warsaw, December 2013 r.
- D12. Test Report No 8596/A/NZL/NBR/15, Short-time current test, IEl, Distribution Equipment Test Laboratory Warsaw, January 2015 r.
- D13. Report No EUR/71/E/13-4 E, Short-time current test, Test for composite error, IEn, Distribution Equipment Laboratory Warsaw, January 2014 r.
- D14. Report No EUR/23/E/14 E, Short-time current test, Test for composite error, IEn, Distribution Equipment Laboratory Warsaw, May 2014 r.
- D15. Test Report No EWN/145/E/13 Type tests, special tests and additional tests of combined transformers type PVA123a i PVA145a manufactured by ABB sp. z o.o., IEn, High Voltage Laboratory, Warsaw, January 2014 r.



- D16. Test Report No.Nr EWN/11/E/12-1, Type tests, special tests and additional tests of Voltage transformer typu PV 123, manufactured by ABB sp. z o.o., IEn, High Voltage Laboratory Warsaw, October 2012 r.
- D17. Test Report No.Nr EWN/11/E/12-2, tests of Current transformer type PA 123 (PA 145) with insulation level LI 650kV/AC 275kV, manufactured by ABB sp. z o.o., IEn, High Voltage Laboratory Warsaw, October 2012 r.
- D18. Report No EWP/35/E/2013-3e). Sprawdzanie ochrony przed uderzeniem mechanicznym, IEn, High Current Laboratory, Warsaw, February 2014 r.
- D19. Report No 8281/A/NZL/NBR/12), IP tests for terminal box, IEl, Distribution Equipment Test Laboratory Warsaw, Warsaw, July 2012 r.

D20. Dimensional drawings:

- Dimensional drawing Combined instrument transformer PVA 123a-145a  
2GKK614122/ABB R&D\_TS\_KU568/13 (17.12.2013).
- Dimensional drawing Combined instrument transformer PVA 123a-145a  
2GKK614123/ABB R&D\_TS\_KU571/13 (17.12.2013).
- Dimensional drawing Combined instrument transformer PVA 123a-145a  
2GKK614123/ABB R&D\_TS\_KU572/13 (17.12.2013).
- Dimensional drawing Combined instrument transformer PVA 123a-145a  
2GKK614120/ABB R&D\_TS\_KU569/13/A (17.12.2013).
- Dimensional drawing Combined instrument transformer PVA 123a-145a  
2GKK614121/ABB R&D\_TS\_KU569/13 (17.12.2013).
- Dimensional drawing Current transformer PA 145, 2GKA612004 (01.08.2014).
- Dimensional drawing Current transformer PA 145, 2GKA612002 (11.09.2014).
- Dimensional drawing Current transformer PA 145, 2GKA612001 (11.09.2014).
- Dimensional drawing Current transformer PA 145, 2GKA612003 (11.09.2014).
- Dimensional drawing Voltage transformer PV 123, 2GKV614114/ (19.01.2012).
- Dimensional drawing Current transformer PA 123 (PA 145), 2GKA614117 (19.01.2012).
- Dimensional drawing Current transformer PA 145, 2GKA612004 (01.08.2014).
- Dimensional drawing Current transformer PA 145, 2GKA614301 (01.08.2014).

- D21. Routine test reports and accuracy check reports – see reports from tests D1→D5, D10→D17
- D22. Rating plates – see reports from tests D1→19
- D23. Electrical diagrams – see reports from tests D1→D5, D10→D17
- D24. Manufacturer's Statement issued on 2nd March 2015 r. –concerns total active power dissipated in current transformer windings.

**3. Testing laboratory competences**

- Type tests, routine tests and special tests for PA...a transformers were carried out at the following laboratories:
- Laboratorium Wysokich Napięć (High Voltage Laboratory), a unit of Instytut Energetyki (Institute of Power Engineering) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA No AB 272.
  - Laboratorium Urządzeń Rozdzielczych (Distribution Equipment Laboratory), a unit of Instytut Energetyki (Institute of Power Engineering) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA No AB 324.

- Laboratorium Wielkoprowadowe (High Current Laboratory), a unit of Instytut Energetyki (Institute of Power Engineering) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA Nr AB 323.
- Laboratorium Fabryczne ABB Sp. z o.o. (ABB Manufacturing Plant Laboratory) in Przasnysz – Punkt Legalizacyjny OUM Warszawa (OUM Warsaw Verification Unit) – deviation measurement, and product tests under supervision of Instytut Energetyki (Institute of Power Engineering), Laboratorium Wysokich Napięć (High Voltage Laboratory).
- Laboratorium Badawcze Aparatury Rozdzielczej (Distribution Equipment Test Laboratory), a unit of Instytut Elektrotechniki (Electrotechnical Institute) in Warsaw, holding the PCA Accreditation Certificate of the Research Laboratory PCA No AB 074.

**4. Test result list**

**4.1. Type tests and additional tests**

The tests were made on selected PA ...a, PVA ...a and PV ... transformer designs (various rated currents for the current elements, various main circuit designs, various design of secondary circuits, different accuracy classes and various insulation covers, etc.) The tests results are valid for the entire transformer series acc. to the list as suggested for certification. Table 1 shows produced by manufacturer's solutions for the main circuits of current transformers. Representative designs for short-circuit tests and temperature-rise tests were selected from that list.


PVA...a and PA ...a transformers were selected to temperature-rise test based on the most heat-exposed design solutions.

Dielectric tests were made for two transformers type : PVA 123a, and 145a as well as PA 123 (145) and PV 123.

The short-circuit withstand tests were made for PVA...a and PA ...a transformers. Representative designs were selected according to their main circuits exposition to dynamic and thermal effects.

Table 2 shows performed tests. Their scope meets requirements included in respective standards for: type tests, special tests, routine tests, and some additional requirements. Respective item numbers in PN-EN 61869 and IEC 61869 as well as report numbers with detailed test results are listed.

**Results of all tests were positive.**



**4.2. Routine tests**

Routine tests and accuracy class tests were carried out at the manufacturer's laboratory for all the transformers tested under the IEn supervision.

The tests included:

- oil measurements before filling the instrument transformer,
- Verification of markings of terminals,
- Power-frequency voltage withstand tests on primary terminals,
- Power-frequency voltage withstand tests on secondary terminals,
- partial discharge intensity,
- inter-winding insulation test,
- Test for accuracy,
- over-current coefficient determination,
- magnetisation characteristics determination,
- Measurement of capacitance and dielectric dissipation factor,
- winding resistance measurement.

Test results were listed in protocols, their numbers being the same as that of the transformer tested. After the voltage tests and short circuit tests, additional routine tests and accuracy class tests were carried out.

Tests result: **positive**

**Table 1. Main circuit list:**

Circuit design description	Current circuit assembly drawing number	Drawing title	Max current I <sub>cb</sub>	Max current I <sub>th</sub> (1s) / I <sub>th</sub> (60 s)	Performed positive tests with current	Performed positive tests with current I <sub>th</sub> (1s) / I <sub>th</sub> (60 s)
Red φ40 Cu	2CKK31433A000 1	Main circuit, red φ40 Cu	3000 A	63/58 kA (60 s) / 63 kA	PA 145s 8596/NZL/NBR/15	PA 145s 8596/NZL/NBR/15
Red φ40 Al	2CKK31433A000 1	Main circuit, red φ40 Al	2400 A	63/58 kA	PVA 145s EUR/71/E/13	PVA 145s EUR/71/E/13
Red φ40 Al + pipe φ60x4 Al	2CKK31433A000 1	Main circuit, red φ40 Al + pipe φ60x4 Al	2400 A - 1800 A	63-51/158-158 kA	PVA 145s EUR/71/E/13-3	PVA 145s EUR/71/E/13-3
Red φ40 Al + pipe φ60x4 Al + 2 turns of cable 240mm <sup>2</sup>	2CKK31433A000 1	Main circuit, red φ40 Al + pipe φ60x4 Al + 2 turns of cable 240mm <sup>2</sup>	2400 A - 1800 A - 900 A	63-51/158-158-100 kA	PVA 145s EUR/71/E/13-3	PVA 145s EUR/71/E/13-3
1 turn of cable 240mm <sup>2</sup>	2CKK31433A000 1	Main circuit 1 turn of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
2 turns of cable 240mm <sup>2</sup>	2CKK31433A000 2	Main circuit 2 turns of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>

3 turns of cable 240mm <sup>2</sup>	2CKK31433A000 3	Main circuit 3 turns of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
4 turns of cable 240mm <sup>2</sup>	2CKK31433A000 4	Main circuit 4 turns of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
5 turns of cable 240mm <sup>2</sup>	2CKK31433A000 5	Main circuit 5 turns of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
6 turns of cable 240mm <sup>2</sup>	2CKK31433A000 6	Main circuit 6 turns of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
7 turns of cable 240mm <sup>2</sup>	2CKK31433A000 7	Main circuit 7 turns of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
8 turns of cable 240mm <sup>2</sup>	2CKK31433A000 8	Main circuit 8 turns of cable 240 mm <sup>2</sup>	900 A	40/100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
2 + 2 turns of cable 240mm <sup>2</sup>	2CKK31433A000 1	Main circuit 2+2 turns of cable 240 mm <sup>2</sup>	900 A - 900 A	40-40/100-100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
3 + 3 turns of cable 240mm <sup>2</sup>	2CKK31433A000 2	Main circuit 3+3 turns of cable 240 mm <sup>2</sup>	900 A - 900 A	40-40/100-100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
4 + 4 turns of cable 240mm <sup>2</sup>	2CKK31433A000 3	Main circuit 4+4 turns of cable 240 mm <sup>2</sup>	900 A - 900 A	40-40/100-100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
2 + 2 + 4 turns of cable 240mm <sup>2</sup>	2CKK31433A000 1	Main circuit 2+2+4 turns of cable 240 mm <sup>2</sup>	900 A - 900 A - 900 A	40-40-40/100-100-100 kA	PVA 145s EUR/71/E/13-3 <sup>2)</sup>	PVA 145s EUR/71/E/13-3 <sup>2)</sup>
3 turns of cable 120mm <sup>2</sup>	2CKK31437A000 1	Main circuit 3 turns of cable 120mm <sup>2</sup>	500 A	20/20 kA	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4
6 turns of cable 120mm <sup>2</sup>	2CKK31437A000 2	Main circuit 6 turns of cable 120mm <sup>2</sup>	500 A	20/20 kA	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4
9 turns of cable 120mm <sup>2</sup>	2CKK31437A000 3	Main circuit 9 turns of cable 120mm <sup>2</sup>	500 A	20/20 kA	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4
12 turns of cable 120mm <sup>2</sup>	2CKK31437A000 4	Main circuit 12 turns of cable 120mm <sup>2</sup>	500 A	20/20 kA	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4
3 + 3 turns of cable 120mm <sup>2</sup>	2CKK31439A000 1	Main circuit 3+3 turns of cable 120 mm <sup>2</sup>	300 A - 300 A	20-20 / 50-50 kA	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4
6 + 6 turns of cable 120mm <sup>2</sup>	2CKK31439A000 2	Main circuit 6+6 turns of cable 120 mm <sup>2</sup>	300 A - 300 A	20-20 / 50-50 kA	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4
3 + 3 + 3 turns of cable 120mm <sup>2</sup>	2CKK31439A000 1	Main circuit 3+3+3 turns of cable 120mm <sup>2</sup>	300 A - 300 A - 300 A	20-20-20/50-50-50 kA	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4
Red φ40 Cu + pipe φ60x4 Al	2CKK31439A000 1	Main circuit Red φ40 Cu + pipe φ60x4 Al	3000 A - 1800 A	63-51/158-158 kA (60 s)	PVA 145s EUR/71/E/13-4	PVA 145s EUR/71/E/13-4

<sup>1)</sup> See Manufacturer's Statement issued on 02.03.2015 r. concerning limitation of active power of windings resistance to 80 W.

**Table 2. List of tests made for type PA...a current transformer**

Item	Test type	Requirements	Report numbers
<b>TYPE TESTS</b>			
1	Short-time current test	PN EN 61869-2, p. 7.2.201	8596/NZL/NBR/15 EUR/71/E/13-3 EUR/71/E/13-4 EUR/74/E/13 EUR/23/E/14
2	Temperature-rise test	PN EN 61869-1, p. 7.2.2 PN EN 61869-2, p. 7.2.2	EW/710/E/2014-1 EW/47/E/2014-1 EW/55/E/2013-1

0001432



3	Impulse voltage withstand test	PN-EN 61869-1, p.7.2.3 PN-EN 61869-2, p. 7.2.3	EW/55/E/2013-2 859/NZL/NBR/15
4	Wet test for outdoor type transformers	PN-EN 61869-1, p.7.2.4 PN-EN 61869-2, p.7.2.4	EWN/145/E/13 EWN/11/E/12-1 EWN/11/E/12-2
5	Tests for accuracy	PN-EN 61869-2, p.7.2.6.201 + 203	EWN/145/E/13 and protocols from manufacturer's laboratory
6	RIV test	PN-EN 61869-1, p.7.2.5.1	EWN/145/E/13
7	Test for composite error	PN-EN 61869-2, p.7.2.6.203	EUR/71/E/13-3 EUR/71/E/13-4 EUR/74/E/13 EUR/23/E/14
8	Terminal box verification of the IP coding	PN-EN 61869-1, p.7.2.7.1 PN-EN 60529, p.13.14	828/NZL/NBR/12
9	Mechanical impact test (IK)	PN-EN 61869-1, p.7.2.7.2 PN-EN 62262	EW/55/E/2013-3
<b>SPECIAL TESTS</b>			
10	Chopped impulse voltage withstand test on primary terminals	PN-EN 61869-1, p.7.4.1 PN-EN 61869-2, p. 7.4.1	EWN/145/E/13
11	Mechanical test	PN-EN 61869-1, p.7.4.5	EUR/34/E/14-1 EUR/34/E/14-2 EUR/34/E/14-3 EUR/34/E/14-4
12	Transmitted overvoltage test	PN-EN 61869-1, p.7.4.4	EWN/145/E/13
13	Measurement of capacitance and dielectric dissipation factor	PN-EN 61869-1, p.7.4.3 PN-EN 61869-2, p. 7.4.3	and protocols from manufacturer's laboratory

**5. SUMMARY**

- Based on the test results for selected representatives of transformers series type PA 123a and PA 145a, PVA 145a and PV 123. As well as on analysis of the standards, it was found that:
- There were performed all tests from the type test range, special tests and additional tests sufficient for a complete evaluation of the apparatuses.
  - Instrument transformer errors tests and instrument transformer secondary circuit designs were analysed, and their metrological properties were confirmed.
  - PA 123a instrument transformer main circuit designs were analysed. It was found out that the short-circuit tests and temperature-rise tests as carried out are binding for all design solutions.
  - Tests were made according to requirements of the 61869 series standard (PN and IEC)
  - Taken the test results under consideration, the technical data listed in Table 3 may be referenced to the PA 123a instrument transformer series.

000000

- This document may be a basis for issuing compliance certificates for PA 123a instrument transformer series manufactured by ABB Sp. z o.o. Oddział w Przysmyżu. The certificate validity date is suggested to be November 2017.

**Table 3. List of technical data assigned to PVA 123a**

Transformer type PA 123a	
Highest voltage of current transformer [U <sub>m</sub> ]	≤ 123 kV
Rated frequency [f <sub>k</sub> ]	50 Hz
Rated insulation level	AC 230 kV / LI 550 kV
Burden class	F <sub>g</sub> =3600N
External insulation – minimal creepage distance of insulator:	3640 mm 3800 mm
• ceramic insulator	
• composite insulator	
Degree of protection to mechanical impact of enclosure <sup>1)</sup>	IK7
Degree of protection of secondary terminal enclosure	IP55
<b>Current element</b>	
Rated primary current [I <sub>pr</sub> ]	50 A + 3 000 A
Extended current rating	do 200%
Rated continuous thermal current [I <sub>th</sub> ]	≤ 3000 A
Rated short-time thermal current [I <sub>sh</sub> ] during 1 s	20 kA lub 40 kA lub 63kA
Rated short-time thermal current [I <sub>sh</sub> ] during 3 s	20 kA lub 40kA
Rated dynamic current [I <sub>th</sub> ]	50 kA lub 100 kA lub 158 kA
Rated secondary current [I <sub>sr</sub> ]	1 A lub 5 A
Core power to measurements and to protection (S <sub>r</sub> )	1VA – 200 VA
Measure core accuracy class (cl.)	0.1; 0.2; 0.2S; 0.5; 0.5S; 1; 3; 5
Protective core accuracy class (cl.)	5P; 10P; 5PR; 10PR; PX; PXR; TPX; TPY; TPZ

**REMARKS:** <sup>1)</sup> Do not apply to ceramic insulators



*[Handwritten signature]*

*[Handwritten signature]*


## APPENDIX

**Type test reports, special test reports and manufacturers statements (pages not numbered)**

- D1. Report No EWP/10/E/2014-1e, Temperature-rise test - PVA 145a (360 A), IEn, High Current Laboratory, Warsaw, January 2014 r.
- D2. Report No EWP/47/E/2014-1e, Temperature-rise test - PA 145a (1800 A), IEn, High Current Laboratory, Warsaw, January 2014 r.
- D3. Report No EWP/55/E/2013-1e, Temperature-rise test - PVA 145a (2400 A), IEn, High Current Laboratory, Warsaw, January 2014 r.
- D4. Report No EWP/35/E/2013-2e, Temperature-rise test - PVA 145a (900 A), IEn, High Current Laboratory, Warsaw, January 2014 r.
- D5. Test report No 8595/ANZL/NBR/15, Temperature-rise test - PA 145a (3000 A), IEl, Distribution Equipment Test Laboratory, Warsaw, January 2015 r.
- D6. Report No EUR/34/E/14-1 E, Mechanical tests, IEn, Distribution Equipment Laboratory, Warsaw, September 2014 r.
- D7. Report No EUR/34/E/14-2 E, Mechanical tests, IEn, Distribution Equipment Laboratory, Warsaw, September 2013 r.
- D8. Report No EUR/34/E/14-3 E, Mechanical tests, IEn, Distribution Equipment Laboratory, Warsaw, September 2014 r.
- D9. Report No EUR/34/E/14-4 E, Mechanical tests, IEn, Distribution Equipment Laboratory, Warsaw, September 2014 r.
- D10. Report No EUR/71/E/13-3 E), Short-time current test, Test for composite error, test of strength against short-circuit in the secondary circuit, IEn, Distribution Equipment Laboratory, Warsaw, January 2014 r.
- D11. Report No EUR/74/E/13 E Short-time current test, Test for composite error, IEn, Distribution Equipment Laboratory, Warsaw, December 2013 r.
- D12. Test report No 8596/ANZL/NBR/15, Short-time current test, IEl, Distribution Equipment Test Laboratory, Warsaw, January 2015 r.
- D13. Report No EUR/71/E/13-4 E, Short-time current test, Test for composite error, IEn, Distribution Equipment Laboratory, Warsaw, January 2014 r.
- D14. Report No EUR/23/E/14 E, Short-time current test, Test for composite error, IEn, Distribution Equipment Laboratory, Warsaw, May 2014 r.
- D15. Test report No EWN/145/E/13, Type tests, special tests and additional tests of combined transformers type PVA125a i PVA145a produkcji ABB sp. z o.o., IEn, High Voltage Laboratory, Warsaw, January 2014 r.
- D16. Test report No EWN/11/E/12-1, Type tests, special tests and additional tests of current transformer type PV 123, manufactured by ABB sp. z o.o., IEn, High Voltage Laboratory, Warsaw, October 2012 r.
- D17. Test report No EWN/11/E/12-2, Tests of current transformer type PA 123 (PA 145) with dielectric level LI 650kV/AC 275kV, manufactured by ABB sp. z o.o., IEn, High Voltage Laboratory, Warsaw, October 2012 r.
- D18. Report No EWP/35/E/2013-3e), Mechanical impact test, IEn, High Current Laboratory, Warsaw, February 2014 r.
- D19. Report No 8281/ANZL/NBR/12 IP tests for terminal box, IEl, Distribution Equipment Test Laboratory, Warsaw, July 2012 r.
- D20. Statement issued on 2<sup>nd</sup> March 2015 r. refers to the total active power dissipated in the current transformer windings.



000134





**Instytut Elektrotechniki**  
Electrotechnical Institute

ZESPÓŁ LABORATORIÓW INSTYTUTU ELEKTROTECHNIKI  
LABORATORIUM BADAWCZE APARATURY ROZDZIELCZEJ  
ul. M. Poczaryskiego 28, 04-703 WARSZAWA  
tel.: +48 22 812 23 38, fax: +48 22 812 04 07



Testing Laboratory is accredited by Polish Centre of Accreditation,  
signature of EA, IMLA, No. AG 074

AB 074

**TEST REPORT No. 8595/A/NZL/NBR/15**

Test objects:

Client:

Manufacturer:

Test specification:

Normative document(s):

Reference/Order

number:

Date of tests

completion:

Test results:

Current transformer  
PA 145a

ABB Sp. z o.o.  
ul. Leszno 59, 06-300 Przasnysz

ABB Sp. z o.o.  
ul. Leszno 59, 06-300 Przasnysz

Temperature rise test

PN-EN 61869-2:2019-06

504-021300/038

15 January 2015 r.

POSITIVE

Authorised by

*Przemysław Berowski*  
Przemysław Berowski, Ph.D.

Head of Laboratories of the  
Electrotechnical Institute  
*Robert Franaszek*  
Robert Franaszek, M.Sc.

WARSAW, 11.02.2015

The Test Report applies only to the apparatus tested. The responsibility for conformity of any apparatus having the same designations with that tested rests with the Manufacturer.

© Only integral reproduction of this Test Report is permitted without written permission from Laboratory.

000135


This Test Report comprises 12 sheets in total.

*[Signature]*

Table of contents

1 List of applicable standards ..... 3  
2 Range of tests performed ..... 3  
3 Ratings assigned by the manufacturer ..... 4  
4 Temperature rise test ..... 5  
5 Photographs ..... 9  
6 Drawings ..... 10  
7 Uncertainty electrical and non electrical quantities in laboratory ..... 12

TESTOWA  
OPRACOWANIE



*[Handwritten signature]*




1 List of applicable standards

- PN-EN 61869-1:2009 Instrument transformers – Part 1: General requirements
- PN-EN 61869-2:2013-06 Instrument transformers – Part 2: Additional requirements for current transformers

2 Range of tests performed

- Temperature rise test by PN-EN 61869-2:2013-06 clause 7.2.2

СТАНДАРТ  
СЕРТИФИКАТ



Handwritten signature

000136



3 Ratings assigned by the manufacturer

Test object: Current transformer  
 Type: PA 145a  
 Manufacturer: ABE Sp. z o.o., ul. Leszno 59, 06-300 Przasnysz  
 Serial No.: 2GKFP014A1287155  
 Year of manufacture: 2014  
 Rating plate: Figure 1, page 10  
 Design documentation: 1. Dimensional drawing No. 2GKA612004  
 2. Drawing of current circuit No. 2GKK314159A0001

Rated primary current.....  $I_{pr}$  ..... 1500 – 3000 A  
 Rated continuous thermal current.....  $I_{ct}$  ..... 1800 – 3000 A  
 Rated frequency.....  $f$  ..... 50 Hz  
 Highest system voltage.....  $U_n$  ..... 145 kV  
 Rated power-frequency withstand voltage..... 275 kV  
 Rated lightning-impulse withstand voltage..... 650 kV  
 Rated short-time thermal current .....  $I_b$  ..... 63 – 63 kA  
 Rated dynamic current .....  $I_{dyn}$  ..... 158 – 158 kA  
 Rated duration of short circuit.....  $t_k$  ..... 1 s

Detailed list of components specified in technical project:

1. Dimensional drawing No. 2GKA612004
2. Drawing of current circuit No. 2GKK314159A0001

Handwritten signature



4 Temperature rise test

Test performed according to PN-EN 61869-2:2013-06 clause 7.2.2  
 Condition of test object before test..... New  
 Date of test..... 14 January 2015 r.  
 Ambient temperature:  
 • Before test..... 20,4°C  
 • After test..... 18,8°C  
 Duration of the test..... 24 h 25 min.  
 Test current..... 1. 3 600 A  
 ..... 2. 3 000 A - after 16 hours  
 Frequency..... 50 Hz  
 Primary current range..... 3000 A  
 Supply connection..... Bars Cu 3x1000 mm<sup>2</sup>  
 Test object on testing stand..... Phot. 1 - 2, page 9


The temperatures were measured with used of recorder HIOKI 8423, No. NBR-801-30600 and thermocouples type K.

*[Handwritten signature]*


000137



Measurement points



*[Faint stamp]*



*[Handwritten signature]*



Temperature rise test at current 3000 A / 50 Hz - results

Table 1 Temperature rise test results

Thermocouple location	Thermocouple No.	Stabilized temperature rise [K]	
		Measured	Permitted
Oil in top core	1	31,80	55
Head	2	29,45	---
Connection terminal P1	3	54,25	75
Bolt connection P1	4	56,25	75
Connection terminal P2	5	48,95	75
Bolt connection P2	6	47,70	75
Current circuit 3000 A	7	49,15	---

Table 2 Resistance and temperature rise of secondary windings test results

Heating time [h]	T <sub>a</sub> [°C]	Measurements										Deflection of the oil level indicator [mm]	
		R <sub>1S1-1S2</sub> [mΩ]	R <sub>2S1-2S2</sub> [mΩ]	R <sub>3S1-3S2</sub> [mΩ]	R <sub>4S1-4S2</sub> [mΩ]	ΔT <sub>1S1-1S2</sub> [K]	ΔT <sub>2S1-2S2</sub> [K]	ΔT <sub>3S1-3S2</sub> [K]	ΔT <sub>4S1-4S2</sub> [K]	ΔT <sub>5S1-5S2</sub> [K]	ΔT <sub>6S1-6S2</sub> [K]		
0	17,20	450,2	5,458	587,5	5,675	0	0	0	0	0	0	0	0
1	18,15	463,2	5,540	601,5	5,722	7,30	3,65	5,70	2,00	2,00	4	4	4
2	19,00	467,9	6,601	608,2	5,789	10,00	6,40	8,50	4,90	8,20	8	8	8
3	19,50	474,1	5,676	616,3	5,863	13,50	9,95	12,00	8,20	8,20	12	12	12
4	19,85	480,4	5,756	624,7	5,946	17,10	13,75	15,75	11,95	11,95	15	15	15
5	20,15	487,3	5,841	633,5	6,034	21,00	17,95	19,80	16,10	16,10	18	18	18
6	20,25	493,7	5,923	642,2	6,119	24,65	22,10	23,95	20,25	20,25	19	19	19
7	20,35	500,3	6,003	650,8	6,203	28,40	26,30	28,15	24,50	24,50	21	21	21
8	20,40	506,1	6,076	658,5	6,280	31,70	30,20	32,05	28,45	28,45	22	22	22
9	20,50	511,7	6,147	665,8	6,354	34,90	34,05	35,85	32,40	32,40	23	23	23
10	20,50	516,9	6,211	672,8	6,421	37,85	37,65	39,60	36,10	36,10	25	25	25
11	20,55	521,6	6,270	678,9	6,483	40,55	41,00	42,95	39,55	39,55	26	26	26
12	20,55	525,6	6,323	684,7	6,540	42,80	44,05	46,15	42,85	42,85	27	27	27
13	20,60	529,8	6,375	690,0	6,593	45,20	47,10	49,20	45,95	45,95	28	28	28
14	20,65	533,3	6,420	694,8	6,641	47,20	49,75	52,00	48,85	48,85	28	28	28
15	20,60	536,7	6,463	699,5	6,685	49,10	52,30	54,75	51,55	51,55	28	28	28
16	20,70	539,8	6,501	703,3	6,725	50,90	54,65	57,10	54,05	54,05	29	29	29
17	20,60	540,6	6,517	704,4	6,749	51,35	55,55	57,80	55,40	55,40	28	28	28
18	20,50	541,5	6,529	705,6	6,764	51,80	56,30	58,55	56,35	56,35	26	26	26
19	20,45	541,2	6,535	706,2	6,771	51,65	56,55	58,90	56,75	56,75	25	25	25
20	20,15	542,0	6,537	701,4	6,775	52,05	56,75	59,05	57,00	57,00	25	25	25
21	18,75	541,7	6,533	706,2	6,773	51,35	56,65	59,00	56,90	56,90	25	25	25
22	18,35	541,7	6,533	706,2	6,769	51,50	56,45	58,90	56,65	56,65	24	24	24
23	18,60	541,1	6,528	705,8	6,764	51,20	56,10	58,60	56,35	56,35	24	24	24
24	18,85	541,0	6,525	705,0	6,758	51,20	55,85	58,15	55,95	55,95	23	23	23

Permitted temperature rise 65 K

Table 3 Resistance and temperature rise of primary windings test results

Date of test	Before test	After test
14.01.2015	14.01.2015	15.01.2015
R <sub>P1-P2/A</sub> [μΩ]	29	34,5
Ambient temperature [°C]	20,4	18,8
Temperature rise [K]	---	48,1
Permitted temperature rise [K]	---	65

Resistance was measured at direct current : ..... primary circuit: 100 A  
 ..... secondary circuit 5 A: 0,5 A  
 ..... secondary circuit 1 A: 0,1 A  
 The measuring instrument type RMO100GP No. 14G743G

According to PN-EN 61862-2 clause 7.2.2.2.03 was estimated thermal time constants as the time elapsed until 63% of maximum estimated temperature rise.

Table 4 Thermal time constants

Thermocouple location	Thermocouples No.	Time constant T <sub>0</sub> [h]
Oil in top core	1	6
Head	2	4
Connection terminal P1	3	1
Bolt connection P1	4	1
Connection terminal P2	5	1,5
Bolt connection P2	6	1,8
Current circuit 3000 A	7	2,5

Condition of tested object after the test:



- The stabilized temperature rise of various parts of the current transformer did not exceed the values specified in the PN-EN 61869-1:2009, clause 6.4.1, table 5.
- No deterioration and failure was noted.

Test result: Object passed the test


000108



5 Photographs



Phot. 1 Test object on temperature rise testing stand



Phot. 2 Test object on temperature rise testing stand

000139



6 Drawings

**ABB**  
**Current Transformer**

Insulation level	145275/650 kV	Standard	PN-EN 61869-2	Type	PA 145a
Oil type	Nybro Libra	Weight / Oil weight	360 / 120 kg	Temp. range	-40°C → +40°C
S/N	2GKPO14A1287155				

$K_n$	1500-3000/5-1.5-1-1	A/A
$I_n/1S$	63-63	kA
$I_{cb}$	1800-3000	A
		158-158
		kA

A	VA	Class	FS/ALF	Ext. %
1S1-1S2	5	200	0,2	10
2S1-2S2	1	100	0,1	5
3S1-3S2	5	20	5P	60
4S1-4S2	1	35	10P	40
5S1-5S2				
6S1-6S2				

Transportation:  Vertical /  Horizontal

РЕПО C  
СЕРТИФИКАТ




Figure 1 Rating plate

*[Handwritten signature]*







**Instytut Elektrotechniki**  
Electrotechnical Institute

ZESPÓŁ LABORATORIÓW INSTYTUTU ELEKTROTECHNIKI  
LABORATORIUM BADAWCZE APARATURY ROZDZIELCZEJ  
ul. M. Poznańskiego 28, 04-703 WARSZAWA

tel.: +48 22 812 23 38, fax: +48 22 812 04 07

*Testing Laboratory is accredited by Polish Centre of Accreditation,  
signature of EA MLA, No. AB 074*



AB 074

**TEST REPORT No. 8596/A/NZL/NBR/15**

Test objects:

Client:

Manufacturer:

Test specification:

Normative document(s):

Reference/Order

number:

Date of tests

completion:

Test results:

Current transformer  
PA 145a

ABB Sp. z o.o.  
ul. Leszno 59, 06-300 Przasnysz

ABB Sp. z o.o.  
ul. Leszno 59, 06-300 Przasnysz

Short-time current tests

PN-EN 61869-2:2013-06

504-021300/038

23 January 2015 r.

POSITIVE

Authorised by

*Przemysław Berowski*  
Przemysław Berowski, Ph.D.

Head of Laboratories of the  
Electrotechnical Institute

*Robert Franaszek*  
Robert Franaszek, M.Sc.

WARSAW, 11.02.2015

The Test Report applies only to the apparatus tested. The responsibility for conformity of any apparatus having the same designators with that tested rests with the Manufacturer.

© Only integral reproduction of this Test Report is permitted without written permission from Laboratory.


This Test Report comprises 28 sheets in total.

000141

Table of contents

1 List of applicable standards ..... 3  
2 Range of tests performed ..... 3  
3 Ratings assigned by the manufacturer ..... 4  
4 Short-time current test ..... 5  
5 Photographs ..... 15  
6 Drawings ..... 16  
7 Uncertainty electrical and not electrical quantities in laboratory ..... 18  
8 Annex A – Routine test report of current instrument transformer before short-time current test ..... 19  
9 Annex B – Routine test report of current instrument transformer after short-time current test ..... 24

BRDNO  
CZĘSTOCHAŁA



*Robert Franaszek*




1 List of applicable standards

- PN-EN 61869-1:2009 Instrument transformers – Part 1: General requirements
- PN-EN 61869-2:2013-06 Instrument transformers – Part 2: Additional requirements for current transformers
- GOST 7746-2001 Current transformers. General specifications<sup>1</sup>

2 Range of tests performed

- Short-time current test by PN-EN 61869-2:2013-06 clause 7.2.201

LABORATORIUM  
CERTYFIKOWANA



*[Handwritten signature]*

*[Handwritten signature]*

000142

<sup>1</sup> These standards are outside scope of certification by PCA, but ILL laboratory is entitled to carry out test according to GOST standards under the confirmation of competence by ENAC/ROSBERT and ORZMET.



3 Ratings assigned by the manufacturer

Test object: Current transformer  
 Type: PA 145a  
 Manufacturer: ABB Sp. z o.o., ul. Leszno 59, 06-300 Przasnysz  
 Serial No.: 2GKP014A1287155  
 Year of manufacture: 2014  
 Rating plate: Figure 1, page 16  
 Design documentation: 1. Dimensional drawing No. 2GKA612004  
 2. Drawing of current circuit No. 2GKK314159A0001  
 3. Routine test report of current instrument transformer before short-time current test - type: PA 145a, No. 2GKP014A1287155; ABB Sp. z o.o., Przasnysz, 17.12.2014  
 4. Routine test report of current instrument transformer after short-time current test - type: PA 145a, No. 2GKP014A1287155; ABB Sp. z o.o., Przasnysz, 30.01.2015

Rated primary current.....  $I_{pr}$ ..... 1500 – 3000 A  
 Rated continuous thermal current.....  $I_{ctn}$ ..... 1800 – 3000 A  
 Rated frequency.....  $f_r$ ..... 50 Hz  
 Highest system voltage.....  $U_m$ ..... 145 kV  
 Rated power-frequency withstand voltage..... 275 kV  
 Rated lightning-impulse withstand voltage..... 650 kV  
 Rated short-time thermal current.....  $I_{sh}$ ..... 63 – 63 kA  
 Rated dynamic current.....  $I_{dyn}$ ..... 158 – 158 kA  
 Rated duration of short circuit.....  $k$ ..... 1 s

Detailed list of components specified in technical project:


1. Dimensional drawing No. 2GKA612004
2. Drawing of current circuit No. 2GKK314159A0001

*[Handwritten signature]*



4 Short-time current test

Test performed according to PN-EN 61869-2:2013-06 clause. 7.2.201.



Sch. 1 Test circuit

G	Generator	MB	Master Breaker	MS	Making Switch
L	Reactors	R	Resistor	PT	Power Transformer
S	Current Measurement	U <sub>z</sub>	Voltage Measurement	TO	Tested Object

Supply parameters:

- Power..... 283 MVA
- Voltage..... 4.5 kV
- Current..... 63 kA
- Impedance..... 71 mΩ
- Frequency..... 50 Hz
- Earthing condition:
  - o Generator..... Earthed by 700 Ω
  - o Short-circuit point..... Insulated



000143



Dynamic test at dynamic current 158 kA

Test object.....Current transformer PA 145a  
 Primary current range:.....1500 A  
 Condition of test object before test:.....New  
 Date of test:.....23 January 2015 r.  
 Ambient temperature:.....2°C  
 Expected current parameters:  
 • Test peak current.....158 kA  
 • Duration of short-circuit.....0.06 s  
 Test object on testing stand:.....Phot. 1, page 15  
 Test results:.....Table 1, page 6, Osc. 90065, page 10  
 Scaling oscillogram:.....Osc. 90064, str. 9


Table 1 Test results

Oscillogram No.	90065
Symmetrical current (r.m.s)	76.6 kA
Peak value of current	161.3 kA
Duration	61.8 ms


Condition of tested object after the test:

No deterioration and failure was noted.

Test result: Object passed the test



OPROJEKTA  
MARIUSZ C





Dynamic test at dynamic current 100 kA

Test object: .....Current transformer PA 145a  
 Primary current range: .....1500 A  
 Condition of test object before test: .....After dynamic test  
 Date of test: .....23 January 2015 r.  
 Ambient temperature: .....2°C  
 Expected current parameters:  
 • Test peak current: .....100 kA  
 • Duration of short-circuit: .....0,06 s  
 Test object on testing stand: .....Phot. 1, page 15  
 Test results: .....Table 2, page 7, Osc. 90066, page 11  
 .....Table 3, page 7, Osc. 90067, page 12  
 .....Table 4, page 7, Osc. 90069, page 13  
 Scaling oscillogram: .....Osc. 90064, page 9

Table 2 Test results 1

Oscillogram No.	90066
Symmetrical current (r.m.s)	48,0 kA
Peak value of current	101,2 kA
Duration	61,8 ms

Table 3 Test results 2

Oscillogram No.	90067
Symmetrical current (r.m.s)	48,1 kA
Peak value of current	101,3 kA
Duration	61,3 ms

Table 4 Test results 3

Oscillogram No.	90069
Symmetrical current (r.m.s)	47,6 kA
Peak value of current	101,39 kA
Duration	81,7 ms

Condition of tested object after the test:

No deterioration and failure was noted.

Test result: Object passed the test

000144



Thermal test at thermal current 63 kA

Test object: .....Current transformer PA 145a  
 Primary current range: .....1500 A  
 Condition of test object before test: .....After dynamic tests  
 Date of test: .....23 January 2015 r.  
 Ambient temperature: .....2°C  
 Expected current parameters:  
 • Test current: ..... $I_k$ .....63 kA  
 • Duration of short-circuit: ..... $t_k$ .....1 s  
 Test object on testing stand: .....Phot. 1, page 15  
 Test results: .....Table 5, page 8, Osc. 90071, page 14  
 Scaling oscillogram: .....Osc. 90064, page 9

Table 5 Test results

Oscillogram No.	90071
Symmetrical current (r.m.s)	63,2 kA
Peak value of current	124,1 kA
Voltage on primary terminals P1-P2	24,54 V
Duration	1,23 s
Integral $\int dt$	4,93 GA <sup>2</sup> s

Condition of tested object after the test:


No deterioration and failure was noted.

Test result: Object passed the test

Current transformer complies with the requirements of:


- short-time current test at thermal current 63 kA/1 s and at dynamic current 158 kA
- short-time current test at thermal current 40 kA/3 s and 3 dynamic tests at dynamic current 100 kA.

Current transformer PA 145a - dynamic test



Stamp: LABORATORIA BANCHELE MATERIALE ELETTRICO VARAZZA  
Signature: [Handwritten signature]

Current transformer PA 145a - calibration




Signature: [Handwritten signature]

000145



Current transformer PA 145a - dynamic test  
Date: 2015-01-23 15:03:30 Oscylogram Nr: 90067

LABORATORIUM BADENSKA  
WARSZAWA  
UL. ARKUSZOWSKA 17/19




*Handwritten signature*  
 LABORATORIUM BADENSKA  
 WARSZAWA  
 UL. ARKUSZOWSKA 17/19  
 02-250 00 00



Current transformer PA 145a - dynamic test  
Date: 2015-01-23 14:52:00 Oscylogram Nr: 90066

LABORATORIUM BADENSKA  
WARSZAWA  
UL. ARKUSZOWSKA 17/19



90066

*Handwritten mark*




Oscylogram Nr: 90071


Data: 2015-01-23 15:39:30

LABORATORIUM ELEKTRYCZNE  
MAREK S.A.

Current transformer PA 145a - Thermal test



BRUC  
C...




Oscylogram Nr: 90069

Data: 2015-01-23 15:19:52

LABORATORIUM ELEKTRYCZNE  
MAREK S.A.


Current transformer PA 145a - dynamic test




471000



5 Photographs



Phot. 1 Test object on short-time current testing stand



Phot. 2 Test object after tests

000148

6 Drawings

**ABB**  
**Current Transformer**

Insulation level	145/275/650 kV	Standard	PN-EN 61869-2	Type	PA 145a
Oil type	Nyro Libra	Weight/Oil weight	360 / 120 Kg	fn	50 Hz
S/N	2GKP014A1287155			Temp. range	-40°C → +40°C

$K_n$	1500-3000/S-1-5-1-1	A/A
$I_{br}/I_S$	63-63	kA
$I_{ch}$	1800-3000	A
		158-158
		kA


  

A	VA	Class	FS/ALF	Ext. %
1S1+1S2	5	200	0,2	10
2S1+2S2	1	100	0,1	5
3S1+3S2	5	20	5P	60
4S1+4S2	1	35	10P	40
5S1+5S2				
6S1+6S2				

Transportation  Vertical /  Horizontal

Figure 1 Rating plate

ВЕРНО  
СЕРТИФИКАТ



Handwritten signature

Handwritten signature





7 Uncertainty electrical and non electrical quantities in laboratory

Measured quantity	Range	Frequency	Measured parameter / uncertainty [%]		
			RMS	Peak	
Voltage U / Divider RC	0 ≤ U ≤ 1000 V	dc - 20kHz	≤ 1.5	≤ 1.0	
	1000 V ≤ U ≤ 10 kV	> 20kHz	≤ 2.5	≤ 2.0	
	U > 10 kV	50Hz - 20kHz	≤ 2.5	≤ 1.5	
		> 20kHz	≤ 3.0	≤ 2.0	
Current I / Shunt	0 ≤ I ≤ 100 A	dc - 5kHz	≤ 1.5	≤ 1.0	
		> 5kHz	≤ 2.0	≤ 1.5	
	100 A ≤ I ≤ 10 kA	dc - 5kHz	≤ 1.5	≤ 1.0	
		> 5kHz	≤ 2.0	≤ 1.5	
	I > 10 kA	dc - 5kHz	≤ 2.0	≤ 1.5	
		> 5kHz	≤ 3.0	≤ 2.0	
	Current I / Current transformer	0 ≤ I ≤ 100 A	50Hz - 5kHz	≤ 2.5	≤ 2.0
			> 5kHz	≤ 3.0	≤ 2.0
		100 A ≤ I ≤ 10 kA	50Hz - 5kHz	≤ 2.5	≤ 2.0
			> 5kHz	≤ 3.0	≤ 2.0
10 kA ≤ I ≤ 30 kA		50Hz - 5kHz	≤ 3.5	≤ 3.0	
		> 5kHz	≤ 4.0	≤ 3.5	
Resistance R bridge, millimeter		20 μΩ ≤ R ≤ 600 μΩ		≤ 5 %	
		0.6 mΩ ≤ R ≤ 600 mΩ		≤ 3 %	
Frequency f oscilloscope, recorder TF		≤ 10 kHz		≤ 0.2 %	
		10 MHz ≤ f ≤ 1 MHz		≤ 0.5 %	
Time t oscilloscope, recorder TF	≤ 1 μs		≤ 20 %		
	> 1 ms		≤ 10 %		
Temperature T thermocouples	-50 °C ≤ T ≤ 100 °C		≤ 0.2 %	thermometer	
	-100 °C ≤ T ≤ 200 °C		≤ 0.8 %	thermocouples K, recorder	
Relative humidity	20 % db 90% RH		≤ 5 % RH		
	≤ 0.05 mm		≤ 0.05 mm		
Length Lengthmeter	≤ 1 mm		≤ 0.1 mm		
	> 30 mm		≤ 5 %		
Gas pressure p	≤ 20 bar		≤ 5 %		
	20 bar ≤ p ≤ 200 bar		≤ 10 %		
Atmosph. pressure			≤ 0.01 MPa		




Figure 2 Dimensional drawing

0001000

8 Annex A - Routine test report of current instrument transformer before short-time current test

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 59		Routine test report of current instrument transformer		TYPE: PA145a	Serial no: 2GKP014A1287155
1th Is [kA]: 60-63	Idm [kA]: 158-158	1ch [A]: 1800-3600	PN-EN 61869-2	50 Hz	
Winding	Isn [A]	Sn [VA]	class	Ratio [A/A]	
1S1-1S2	5	200	0,2FS 10	1500-3000/5	
2S1-2S2	1	100	0,1FS 5	1500-3000/1	
3S1-3S2	5	20	5P 60	1500-3000/5	
4S1-4S2	1	35	10P 40	1500-3000/1	

List of performed tests:

- Oil dielectric parameters check before filling (oil after treatment):  
19.8 acc. IEC 60247, breakdown voltage acc. IEC 60156
- Verification of formal markings
- Pressure and tightness test: oil overpressure: 0.8 bar / 24h - no traces of oil leakage
- Power-frequency withstand test on primary winding
- Partial discharge measurement
- Power-frequency withstand test on secondary windings
- Inter-turn overvoltage test
- Determination of errors
- Determination of the over current factors: FS, ALF
- Measurement of capacitance and dielectric dissipation factor - tgδ
- Determination of core magnetization characteristics
- Measurement of windings' resistance

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil tg δ according to IEC  
Tg δ = 0.1963 %; electrical stress = 1kV/mm, f = 50Hz, oil temp. = 90C

- Measurement of breakdown voltage according to IEC 60158

Mean breakdown voltage = 76.27 kV, Relative standard deviation = 5.87

f = 50Hz, oil temp. = 25.4 °C, measurement without the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	77.7
2	71.9
3	72.7
4	65.2
5	70.4
6	75.7

000150



Partial discharge measurement

- Measurement according to procedure A (PD test voltages were reached while decreasing the voltage after the power-frequency withstand test on primary winding)

Stress voltage: 275 kV / 60 s  
Frequency: 50 Hz

Test voltage	1.2 Um = 174 kV	1.2 Um / √3 = 100.5 k
Level of partial discharge	1 pC	0.9 pC

Remarks: background noise level: 0.7 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating)

Inter-turn overvoltage test

Winding	Peak voltage on secondary winding [kV/peak]	Current in primary winding [A]
1S1-1S2	4.5	1450
2S1-2S2	4.5	350
3S1-3S2	4.5	1000
4S1-4S2	3.24	3600

Determination of errors ε1 (%), Δφ 1 min)

Ip1 (A): 1600

1S1-1S2: 200 VA		p.f. = 0.8 lag.		1S1-1S2: 60 VA		p.f. = 0.8 lag.	
ε1	0.05 in	1.0 in	1.2 in	0.05 in	0.2 in	1.0 in	1.2 in
Δφ1	-0.313	-0.47	-0.62	-0.046	-0.089	0.082	0.082
Δφ1	8.3	3.1	1.0	0.7	3.9	1.8	0.8
2S1-2S2: 100 VA		p.f. = 0.8 lag.		2S1-2S2: 25 VA		p.f. = 0.8 lag.	
ε1	0.05 in	1.0 in	1.2 in	0.05 in	0.2 in	1.0 in	1.2 in
Δφ1	-0.058	-0.039	-0.003	0.015	0.014	0.017	0.018
Δφ1	1.3	0.3	-0.5	-0.4	0.3	0.2	0.0
3S1-3S2: 20 VA		p.f. = 0.8 lag.		4S1-4S2: 35 VA		p.f. = 0.8 lag.	
ε1	1.0 in	1.0 in	1.0 in	1.0 in	1.0 in	1.0 in	1.0 in
Δφ1	-0.016	-0.016	-1.323	-1.323	-1.323	-1.323	-1.323
Δφ1	0.3	0.3	83.5	83.5	83.5	83.5	83.5

Ip1 (A): 3000

1S1-1S2: 200 VA		p.f. = 0.8 lag.	
ε1	0.05 in	1.0 in	1.2 in
Δφ1	-	-0.043	-
Δφ1	-	1.0	-

Measurements uncertainty: s1 = ± 0.045 %, Δφ1 = ± 2.3 min

Determination of the over current factors:

- Instrument security factor (FS) of measuring cores

Winding	Io [A]	U [V]	EFs	Condition	Assessment
1S1-1S2	5	233.67	422.08	U < EFs	OK
2S1-2S2	0.5	227	526.03	U < EFs	OK

- accuracy limit factor (ALF) - test for composite error  $\epsilon_c$  of protective cones

Winding	EALF [V]	I <sub>a</sub> [A]	$\epsilon_c$ [%]	Condition	Assessment
3S1-SS2	430.12	0.047	0.02	$\epsilon_c \leq 5\%$	OK
4S1-4S2	1625.98	0.888	2.25	$\epsilon_c \leq 10\%$	OK
5S1-5S2		0.242		$\epsilon_c \leq$	

Measurement of capacitance and dielectric dissipation factor - tg  $\delta$


Temperature: 23 °C, Frequency: 60

Primary voltage	Tg $\delta$ [%]	Capacitance [pF]	Leak current [mA]
10 kV	0.24	1124	3.575
78 kV	0.24	1125	28.87
84 kV	0.24	1125	28.73


Core magnetization characteristics:

Winding 1S1-1S2

[V]	[mA]
234	5313.7
231.8	3068.1
229.6	1998.1
224.5	942.9
218.3	468.63
212.9	208.3
204.6	97.07
186.1	46.27
167.6	34.48
148.2	29.26
129.2	25.57
91.1	18.91
53.2	13
15.5	5.47
2.6	1.68




000151




Winding 2S1-2S2

[V]	[mA]
228.5	645.1
205.2	3.9
191.8	2.07
166.3	1.89
183	1.77
179.4	1.63
178	1.49
172.8	1.35
169.3	1.21
162.7	1.55
133.6	0.77
102.3	0.44
67.3	0.33
32	0.21
5	0.06




Winding 3S1-3S2

[V]	[mA]
525.1	9728
523.8	8209
520.3	4960.4
518.7	3801.5
508.4	1070.4
474.3	140.39
459.1	79.03
442.6	53.68
404.7	34.65
368	26.14
330.8	24.68
293.8	21.8
182.3	14.74
69.5	7.21
5.8	1.01



Winding 4S1-4S2

[V]	[mA]
1924.7	2612.2
1916.6	2155
1905.1	1669.8
1888.6	1321.3
1884.8	1068.3
1800.2	1020.7
1739.8	858.8
1684.2	992
1614.7	832.1
1364.8	748
1205.8	660
852.6	480.29
507.6	279.03
163.2	84.7
23.4	13.23



\*) Average rectifier effective value.

Measurement of windings' resistance

	R (23 °C)	Rct (75 °C)
P1-P2 range 1500A	83.0 μΩ	75.9 μΩ
P1-P2 range 3000A	26.0 μΩ	31.3 μΩ
1S1-1S2	0.452 Ω	0.545 Ω
2S1-2S2	5.390 Ω	6.419 Ω
3S1-3S2	0.590 Ω	0.711 Ω
4S1-4S2	5.680 Ω	6.805 Ω

Checked by: *GOSL* (OG-4) (KJ-21) Przasnysz

000152



9 Annex B - Routine test report of current instrument transformer after short-time current test

ABB Sp. z o.o. 06-300 Przasnysz ul. Leszno 59		Routine test report of current instrument transformer After short time current test		TYPE: PA145a Serial no: 2GKP014A1287155	
Ith [kA]:	IcIn [A]:	Ith [A]:	Sn [VA]	class	Ratio [A/A]
63-63	158-158	1800-3600			50 Hz
Winding					
1S1-1S2	5	200	0,2FS 10	1500-3000/5	
2S1-2S2	1	100	0,1FS 5	1500-3000/1	
3S1-3S2	5	20	5P 60	1500-3000/5	
4S1-4S2	1	35	10P 40	1500-3000/1	

List of performed tests:

- Oil dielectric parameters check before filling (oil after treatment):  
tg δ acc. IEC 60247, breakdown voltage acc. IEC 60156
- Verification of terminal
- Pressure and tightness test: oil overpressure: 0.8 bar / 24h - no traces of oil leakage
- Power-frequency withstand on primary winding   
- P1+P2: Up = 247.5kV / 60s, f = 50Hz
- Partial discharge
- Power-frequency withstand test on secondary   
- Up = 3 kV/60s, 60Hz
- Inter-turn overvoltage   
- lower value (U peak=4.5kV or U peak(for 166)/ 60s
- Determination of error
- Determination of the over current factors: FS, ALF
- Measurement of capacitance and dielectric dissipation factor - tg δ
- Determination of core magnetization characteristics
- Measurement of windings' resistance

Oil dielectric parameters check before filling (oil after treatment)

- Measurement of oil tg δ according to IEC  
Tg δ = 0.1983 %; electrical stress = 1kV/mm, f = 50Hz, oil temp. = 60C
- Measurement of breakdown voltage according to IEC 60156  
Mean breakdown voltage = 76.27 kV, Relative standard deviation = 6.87  
f = 50Hz, oil temp. = 25.4 °C, measurement without the stirrer, type of electrodes used: partially spherical.

Sample	Breakdown voltage [kV]
1	77.7
2	77.9
3	72.7
4	83.2
5	70.4
6	75.7

**Partial discharge measurement**

- Measurement according to procedure B

Stress voltage: 247.5 kV / 60 s  
Frequency: 50 Hz

Test voltage	1.2 Um = 174 kV	1.2 Um / √3 = 100.5 k
Level of partial discharge	1.1 pC	1 pC

Remarks: background noise level: 0.7 (measured after voltage switch off), measuring circuit was calibrated with 5 pC (calibrating)

**Inter-turn overvoltage test**

Winding	Peak voltage on secondary winding [kV(peak)]	Current in primary winding [A]
1S1-1S2	4.5	1450
2S1-2S2	4.5	350
3S1-3S2	4.5	900
4S1-4S2	3.19	3600

Determination of errors  $\epsilon \leq 1\%$ ,  $\Delta p \leq 1 \text{ min}$

Ipn (A): 1500			1S1-1S2: 50 VA			p.f. = 0.8 lag.		
1S1-1S2: 200 VA	0.2 In	1.0 In	0.05 In	0.2 In	1.0 In	1.2 In		
$\epsilon \downarrow$	-0.314	-0.148	-0.043	-0.035				
$\Delta p \downarrow$	6.2	3.0	0.9	0.7	3.9	1.7	0.8	
2S1-2S2: 100 VA			2S1-2S2: 26 VA			p.f. = 0.8 lag.		
0.05 In	0.2 In	1.0 In	0.05 In	0.2 In	1.0 In	1.2 In		
$\epsilon \downarrow$	-0.062	-0.043	-0.013	-0.007				
$\Delta p \downarrow$	1.5	0.4	0.6	0.3	0.3	0.2	0.3	
3S1-3S2: 20 VA			4S1-4S2: 35 VA			p.f. = 0.8 lag.		
1.0 In	1.0 In	1.0 In	1.0 In	1.0 In	1.0 In			
$\epsilon \downarrow$	-0.017		-1.328					
$\Delta p \downarrow$	0.3		63.2					
4S1-4S2: 0 VA			p.f. = 1					
1.0 In								
$\epsilon \downarrow$								
$\Delta p \downarrow$								

Ipn (A): 3000			p.f. = 0.8 lag.		
1S1-1S2: 200 VA	0.2 In	1.0 In	1.2 In		
$\epsilon \downarrow$	-	-0.044			
$\Delta p \downarrow$	-	1.0			

Measurements uncertainty:  $\epsilon \downarrow = \pm 0.045 \%$ ,  $\Delta p \downarrow = \pm 2.3 \text{ min}$

**Determination of the over current factors:**

- Instrument security factor (FS) of measuring cores

Winding	In [A]	Iv [V]	Ecs [V]	Condition	Assessment
1S1-1S2	5	233.75	422.57	U < Efs	<input checked="" type="checkbox"/>
2S1-2S2	0.5	227	526.61	U < Efs	<input checked="" type="checkbox"/>

- accuracy limit factor (ALF) - test for composite error  $\epsilon_c$  of protective cores

Winding	EALF [V]	In [A]	$\epsilon_c$ [%]	Condition	Assessment
3S1-3S2	430.4	0.047	0.02	$\epsilon_c \leq 5\%$	<input checked="" type="checkbox"/>
4S1-4S2	1626.33	0.896	2.24	$\epsilon_c \leq 10\%$	<input checked="" type="checkbox"/>

**Measurement of capacitance and dielectric dissipation factor - tg  $\delta$**


Temperature: 22.6 °C, Frequency: 50

Primary voltage	Ig $\delta$ [%]	Capacitance [pF]	Leak current [mA]
10 kV	0.24	1127	3.662
76 kV	0.24	1128	26.9
84 kV	0.24	1128	29.78

**Core magnetization characteristics:**

Winding 1S1-1S2


I [V]	I [mA]
234.6	6267
233.4	4558
231.2	2025.9
227.9	1511.7
216.5	321.59
203.8	133.29
203.6	90.26
194.7	44.86
166	33.81
147.4	26.97
128.7	25.04
91	18.62
53.6	12.97
16	5.63
2.4	1.5






Winding 2S1-2S2

[V]	[mA]
228.4	610.7
204.5	3.78
189.1	2.08
186.3	2
182.6	1.84
179.2	1.69
175.8	1.55
172.7	1.47
169.3	1.31
162.2	1.63
131.4	0.73
100.3	0.42
85.1	0.32
30.2	0.2
3.8	0.04



Winding 4S1-4S2

[V]	[mA]
1923.8	2526.7
1814.6	2019.7
1903.9	1621.3
1885.5	1277
1863.8	1140.8
1824.8	1048.2
1785.5	1002.7
1729.2	959.3
1667.7	919.7
1509	827.1
1188	647.8
849.1	465.35
505.9	277.81
152.9	84.27
15.5	3.02



\*) Average rectifier effective value.

Measurement of windings' resistance

	R (22 °C)	Ret (75 °C)
P1-P2 range 1500A	83.0 μΩ	78.1 μΩ
P1-P2 range 3000A	28.0 μΩ	31.4 μΩ

000154



1S1-1S2	0.460 Ω	0.555 Ω
2S1-2S2	5.470 Ω	6.600 Ω
3S1-3S2	0.589 Ω	0.712 Ω
4S1-4S2	5.640 Ω	6.815 Ω
5S1-5S2	6.120 Ω	7.395 Ω

Checked by: *G.O.S.H.* OGA (KJZT) Przasnysz, 2015-01-30

DEPTO C  
OPRACOWANIA

